


3 EXTERIOR EQUIPMENT MOUNTING DETAIL
NTS

	ABBREVIATIONS	NOTES
A, AMP	AMPERE	
AIC	AMPERE INTERRUPTING CAPACITY	
AF	FRAME RATING IN AMPERES	
AS	SWITCH RATING IN AMPERES	
AT	TRIP RATING IN AMPERES	
AWG	AMERICAN WIRE GAUGE	
C	CONDUIT	
CKT	CIRCUIT	
(E)	EXISTING TO REMAIN	
EC	EMPTY CONDUIT	
ELEC	ELECTRICAL	
EMT	ELECTRO METALLIC TUBING	
FA	FIRE ALARM	
G, GND	GROUND	
HP	HORSEPOWER	
MECH	MECHANICAL	
MCB	MAIN CIRCUIT BREAKER	
(N)	NEW EQUIPMENT OR DEVICE	
NEC	NATIONAL ELECTRIC CODE	
NEMA	NATIONAL ELECTRICAL MANUFACTURER'S ASSOCIATION	
NO	NORMALLY OPEN	
NTS	NOT TO SCALE	
Ø, PH	PHASE	
PNL	PANEL	
PVC	POLYVINYL CHLORIDE CONDUIT	
PWR	POWER	
RSC	RIGID STEEL CONDUIT	
TEL	TELEPHONE	
TYP	TYPICAL	
UON	UNLESS OTHERWISE NOTED	
V	VOLT	
VA	VOLT AMPERES	
W	WATT	
(X)	EXISTING TO BE DEMOLISHED	

SYMBOLS	WIRING DEVICE SYMBOLS
	20A, 125V, DUPLEX RECEPTACLE OUTLET +18" UNLESS NOTED OTHERWISE
	SURFACE 20A, 125V, DUPLEX RECEPTACLE OUTLET +18" UNLESS NOTED OTHERWISE
	20A, 125V, DOUBLE DUPLEX RECEPTACLE OUTLET +18" UNLESS NOTED OTHERWISE
	SURFACE 20A, 125V, DOUBLE DUPLEX RECEPTACLE OUTLET +18" UNO
	SPECIAL PURPOSE RECEPTACLE OUTLET, +18" UNLESS NOTED OTHERWISE, NEMA CONFIGURATION AS NOTED ON PLANS
	SURFACE SPECIAL PURPOSE RECEPTACLE OUTLET, +18" UNLESS NOTED OTHERWISE, NEMA CONFIGURATION AS NOTED ON PLANS
	20A, 125V, DEDICATED DUPLEX RECEPTACLE OUTLET +18" UON
	DUPLEX OUTLET WITH GROUND FAULT INTERRUPTER
	CEILING MOUNTED 20A, 125V, DUPLEX RECEPTACLE OUTLET
	CEILING MOUNTED 20A, 125V, DOUBLE DUPLEX RECEPTACLE OUTLET
	FLOOR MOUNTED DUPLEX CONVENIENCE/TELECOM OUTLET WITH BLANK STAINLESS STEEL COVER. COORDINATE TYPE AND FINISH WITH ARCHITECT.
	SPST WALL SWITCH, LETTERS INDICATE THE NUMBER OF SWITCHES AND OUTLETS THEY CONTROL
	DIMMER SWITCH
	OCCUPANCY LIGHT CONTROL SWITCH; WALL MOUNTED

GENERAL NOTES			
1.	ALL WORK SHOWN IS NEW, UNLESS NOTED OTHERWISE.		
2.	ALL WORK TO BE IN ACCORDANCE WITH NATIONAL ELECTRIC CODE, 2020 EDITION.		
3.	SEAL ALL CONDUIT PENETRATIONS OF FLOORS AND FIRE RATED ASSEMBLIES TO MAINTAIN FIRE RATING.		
4.	PROVIDE NEW TYPEWRITTEN DIRECTORIES REFLECTING WORK PERFORMED FOR ALL NEW PANELBOARDS IN THIS PROJECT.		
5.	PLANS ARE PREPARED WITH REQUIRED BRANCH CIRCUITS INDICATED BY CIRCUIT NUMBERS. PROVIDE AND INSTALL ALL CONDUITS, CONDUCTORS, BOXES, MISCELLANEOUS FITTINGS, ETC. FOR A COMPLETE AND OPERABLE SYSTEM (HOMERUN SHOWN). BRANCH CIRCUIT INSTALLATION SHALL COMPLY WITH SPECIFICATIONS AND N.E.C.		
6.	ALL NEUTRAL CONDUCTORS ON POWER BRANCH CIRCUITING ROUNDHOUSES TO BE #10 AWG UNLESS NOTED OTHERWISE.		

SHEET LIST			
E-0.1	SYMBOL LIST AND SINGLE LINE DIAGRAM		
E-1.0	EXISTING PHOTOMETRIC PLAN		
E-1.1	NEW PHOTOMETRIC PLAN		
E-2.0	ELECTRICAL POWER PLAN		
E-3.0	SPECIFICATIONS		



1 PANEL SCHEDULES
NTS

MOUNTING SURFACE				PANEL A										50,000		A.I.C. SYM		
240'120			VOLTS	1	PHASE	3	WIRE				MAIN				MLO		BUS 600 A	
VOLT AMPS			DESCRIPTION	R E C	L E T	P O L E	B K R	C I R	C I R	B K R	P O L E	L T G	R E C	DESCRIPTION	VOLT AMPS			
Ø A	Ø B	Ø C													Ø A	Ø B	Ø C	
			SPACE					1	A	2	100	2		EV CAR CHRGR	9600			
			SPACE					3	B	4	-	-		-		9600		
9600			EV CAR CHRGR			2	100	5	A	6	100	2		EV CAR CHRGR	9600			
	9600		-			-	-	7	B	8	-	-		-		9600		
9600			EV CAR CHRGR			2	100	9	A	10	100	2		EV CAR CHRGR	9600			
	9600		-			-	-	11	B	12	-	-		-		9600		
			SPACE					13	A	14				SPACE				
			SPACE					15	B	16				SPACE				
			SPACE					17	A	18				SPACE				
			SPACE					19	B	20				SPACE				
			SPACE					21	A	22				SPACE				
			SPACE					23	B	24				SPACE				
			SPACE					25	A	26				SPACE				
			SPACE					27	B	28				SPACE				
			SPACE					29	A	30				SPACE				
			SPACE					31	B	32				SPACE				
			SPACE					33	A	34				SPACE				
			SPACE					35	B	36				SPACE				
			SPACE					37	A	38				SPACE				
			SPACE					39	B	40				SPACE				
			SPACE					41	A	42				SPACE				
19200	19200		VA/LINE											28800	28800			
Ø A= 48000			Ø B= 48000												Ø C=			
CONTINUOUS LOADS			NON-CONTINUOUS LOADS															
x1.25= _____			UP TO 10 kVA _____			x1.00= _____						OTHER			96000	x1.00	96000	
			RECEPTACLES															
			REMAINDER															
			TOTAL DESIGN kVA= 96			TOTAL DESIGN AMPS= 400												



RISER NOTES

- PROVIDE EMPTY CONDUIT AS NOTED STUBBED INTO TRANSFORMER VAULT AND RUN UNDER THE STREET TO A CHRISTY BOX LOCATED ON NORTH SIDE OF STREET FOR POTENTIAL FUTURE TRANSFORMER.
- ELECTRICAL CONTRACTOR IS RESPONSIBLE FOR CONNECTION TO YVEA PAD MOUNTED TRANSFORMER. COORDINATE CONNECTION SCHEDULE WITH UTILITY COMPANY DURING CONSTRUCTION.
- BOND NEUTRAL TO GROUND BUS AND THEN TO (2) GROUND RODS, AT LEAST 6' APART, AND INCOMING COLD WATER PIPE. PROVIDE GROUND RODS AT 3/4" X 8' (COPPER CLAD STEEL).
- VERIFY CONNECTION REQUIREMENTS WITH MANUFACTURER.

DIAGRAM NOTES

- ALL WORK SHOWN IS NEW UNLESS OTHERWISE NOTED.
- ALL WIRING SHOWN IS SIZED FOR COPPER CONDUCTORS, UON
- SEE DETAIL #3 FOR EQUIPMENT MOUNTING DETAIL.

2 SINGLE LINE DIAGRAM
NTS

SKI TIME
SQUARE DRIVE
PUBLIC
TURNAROUND

BASELINE
ENGINEERING

1169 Hilltop Parkway, Suite 204
PO Box 770152
Steamboat Springs, CO 80477



WILDER ENGINEERING LLC
Andrew Wilder PE
1170 Blue Sage Drive
Steamboat Springs, CO 80487
P: 970-819-7848
E: andy@wilder-eng.com



Issue	By	Date	Issue Description	By
-			PROGRESS SET - 1.6.23	AW
-			100% DESIGN - 1.16.23	AW
-			BID DOCUMENTS - 2.8.23	AW
Δ			REVISION #1 - 2.9.24	AW
Δ			EV REVISION - 7.11.24	AW

Scale:	NTS
	24x36
Description:	SYMBOLS, ONE LINE
Project Name:	SKI TIME SQ TURNAROUND
Project Number:	2022009
Sheet No.	E-0.1

SKI TIME
SQUARE DRIVE
PUBLIC
TURNAROUND

BASELINE
ENGINEERING

1169 Hilltop Parkway, Suite 204
PO Box 770152
Steamboat Springs, CO 80477




WILDER ENGINEERING LLC
Andrew Wilder PE
1170 Blue Sage Drive
Steamboat Springs, CO 80487
P: 970-819-7848
E: andy@wilder-eng.com



Issue	By	Date & Issue Description	By
—	CHECK	SET — 5.25.22	AW
—	CHECK	SET — 5.26.22	AW
—	CHECK	SET — 10.6.22	AW
—	DD	SET — 10.19.22	AW
—	PROGRESS	SET — 1.6.23	AW
—	100% DESIGN	— 1.16.23	AW
—	BID DOCUMENTS	— 2.8.23	AW
—	REVISION #1	— 2.9.24	AW
—	EV REVISION	— 7.11.24	AW

Scale:	1"=25'-0"
	24x36
Description:	EXISTING PHOTOMETRIC
Project Name:	SKI TIME SQ TURNAROUND
Project Number:	2022009
Sheet No.	E-1.0



GENERAL NOTES

1. CALCULATION VALUES ARE IN FOOTCANDLES.

PHOTOMETRIC COLOR KEY CHART

BLUE	LESS THAN OR EQUAL TO 0.4 FC
GREEN	GREATER THAN 0.4 FC AND LESS THAN 0.7 FC
RED	GREATER THAN AND EQUAL TO 0.7 FC

1 ELECTRICAL PHOTOMETRIC PLAN – EXISTING
1"=25'-0"

LIGHTING FIXTURE SCHEDULE								
SYMBOL	ITEM	TYPE	MOUNTING HEIGHT	LAMPS		FIXTURE VOLTAGE	INPUT WATTS	CATALOG NUMBER
				TYPE	COLOR			
	F1	EXISTING URA FIXTURE	12'	LED	—	—	76	URA STANDARD
	F2	EXISTING POST TOP HIGH PRESSURE SODIUM FIXTURE	12'	HPS	—	—	81	YVEA POST TOP STANDARD

2 FIXTURE SCHEDULE
NTS

SKI TIME
SQUARE DRIVE
PUBLIC
TURNAROUND

BASELINE
ENGINEERING

1169 Hilltop Parkway, Suite 204
PO Box 770152
Steamboat Springs, CO 80477




WILDER ENGINEERING LLC
Andrew Wilder PE
1170 Blue Sage Drive
Steamboat Springs, CO 80487
P: 970-819-7848
E: andy@wilder-eng.com



Issue	By	Date & Issue Description	By
—	CHECK	SET — 5.25.22	AW
—	CHECK	SET — 5.26.22	AW
—	CHECK	SET — 10.6.22	AW
—	DD	SET — 10.19.22	AW
—	PROGRESS	SET — 1.6.23	AW
—	BID	DOCUMENTS — 2.8.23	AW

Scale:	1"=25'-0"
24x36	
Description:	PROPOSED PHOTOMETRIC
Project Name:	SKI TIME SQ TURNAROUND
Project Number:	2022009
Sheet No.	E-1.1



SKI TIME
SQUARE DRIVE
PUBLIC
TURNAROUND

BASELINE
ENGINEERING

1169 Hilltop Parkway, Suite 204
PO Box 770152
Steamboat Springs, CO 80477




WILDER ENGINEERING LLC
Andrew Wilder PE
1170 Blue Sage Drive
Steamboat Springs, CO 80487
P: 970-819-7848
E: andy@wilder-eng.com



Issue	By	Date & Issue Description	By
—	—	PROGRESS SET — 1.6.23	AW
—	—	100% DESIGN — 1.16.23	AW
—	—	BID DOCUMENTS — 2.8.23	AW
⚠	—	REVISION #1 — 2.9.24	AW
⚠	—	EV REVISION — 7.11.24	AW

Scale:	1" = 25'-0"
24x36	
Description:	POWER PLAN
Project Name:	SKI TIME SQ TURNAROUND
Project Number:	2022009
Sheet No.	E-2.0



GENERAL NOTES

1. ALL EQUIPMENT SHOWN IS NEW UNLESS OTHERWISE NOTED.
2. PROVIDE TYPEWRITTEN DIRECTORIES REFLECTING ALL NEW WORK PERFORMED IN THIS PROJECT.
3. PROVIDE CONDUIT TO BASE OF CHARGER FOR MOUNTING OF ELECTRIC CAR CHARGER. VERIFY WITH CITY ON FINAL LOCATIONS. THIS CHARGING POINT HAS (2) CAR CHARGERS. VERIFY WITH CHARGING MANUFACTURER ALL REQUIREMENTS PRIOR TO INSTALLATION.
4. VERIFY LOCATIONS OF ALL ELECTRICAL EQUIPMENT WITH CIVIL DRAWINGS AND CONDITIONS IN THE FIELD.
5. ALL EQUIPMENT SHOWN IS CONNECTED TO NEW PANEL 'A', UON.

SHEET NOTES

1. SEE RISER DIAGRAM FOR ELECTRICAL DISTRIBUTION EQUIPMENT. PROVIDE ALL NEC REQUIRED WORKING CLEARANCES.
2. PROVIDE EMPTY CONDUIT FOR POTENTIAL FUTURE UTILITY TRANSFORMER.
3. PROVIDE CONDUIT TO BASE OF CHARGER FOR MOUNTING OF ELECTRIC CAR CHARGER. VERIFY WITH CITY ON FINAL LOCATIONS. THIS CHARGING POINT HAS (2) CAR CHARGERS. VERIFY WITH CHARGING MANUFACTURER ALL REQUIREMENTS PRIOR TO INSTALLATION.
4. PROVIDE CONDUIT TO BASE OF CHARGER FOR MOUNTING OF ELECTRIC CAR CHARGER. VERIFY WITH CITY ON FINAL LOCATIONS. THIS CHARGING POINT HAS (1) CAR CHARGERS. VERIFY WITH CHARGING MANUFACTURER ALL REQUIREMENTS PRIOR TO INSTALLATION.

1 ELECTRICAL POWER PLAN
1"=25'-0"

SECTION 16010 - BASIC ELECTRICAL REQUIREMENTS

1) PART 1 GENERAL

a) POWER AND CONTROL WIRING

i) Provide power system conduit and wiring to mechanical equipment. Controls system conduit and wiring for mechanical systems is included under Division 15. "Power" wiring includes line voltage wiring from distribution apparatus to disconnecting means provided or installed under this section, and from such disconnecting means to motors, and to terminal boxes of 'package' equipment. "Controls" wiring includes wiring, regardless of voltage, which provides start-stop control for mechanical equipment and/or which is used to monitor functions of mechanical systems. Where line voltage wiring is extended from a local disconnecting means to relays, thermostats, by-pass timers, starter coils or the like, or from mechanical control panels or motor control centers to control devices, such extensions are considered "control" wiring.

b) MOUNTING HEIGHTS

i) Mounting heights and locations: verify the exact location of equipment with architect prior to installation. Wall mounted devices requiring operational access shall be mounted a minimum of 15 inches above finished floor to bottom of device and a maximum of 48 inches above finished floor to top of device. Visual alarms shall be mounted not less than 80 inches to the bottom or 96 inches to the top of the device.

c) REGULATORY REQUIREMENTS

i) Conform to:

- (1) NFPA-70 - National Electric Code.
- ii) Comply with the current applicable codes, ordinances, and regulations of the authority or authorities having jurisdiction, the Owner's insurance underwriter, and applicable base building standards.
- iii) When conflict exists between two or more governing codes, comply with the stricter requirement.
- iv) Obtain permits, and request inspections from authority having jurisdiction.

d) PROJECT/SITE CONDITIONS

i) Install Work in locations shown on Drawings, unless prevented by Project conditions. Coordinate installation of work in available space with work furnished under other Divisions.

2) PRODUCTS

- a) Where manufacturer's model or series numbers are specified or shown, these indicate generally acceptable types required. Furnish products which comply with all requirements, as specified or shown.
- b) When more than one unit of the same class of equipment is required, provide units produced by a single manufacturer.

3) TESTS

- a) Furnish test equipment, facilities, and technical personnel required to perform field tests.
- b) At completion of job, check voltage at several points of utilization on the system. Energize all loads installed.

4) CLEANING

a) Clean all fixtures and equipment at the completion of the project. Wipe clean exposed lighting fixture reflectors and trim pieces with a non-abrasive cloth just prior to occupancy.

5) RECORD DRAWINGS

a) Upon completion of the Work, deliver to Architect and up-to-date set of "as-built" record drawings on a reproducible medium including AutoCAD.

6) DEMOLITION

- a) Remove, relocate, and reroute existing electrical equipment to facilitate new construction or remodeling work.
- b) Examine the site to observe and note existing conditions prior to submitting a bid.
- c) Schedule demolition in advance. Schedule work to avoid disruption of normal operations.
- d) Reconnect circuits serving equipment required to remain in service to other panelboards, motor control centers, or other appropriate distribution equipment. Provide additional panelboards, motor control centers, or other appropriate distribution equipment where there is insufficient available capacity in remaining existing equipment for reconnection.
- e) Remove existing conduit and wire back to panelboard, motor control center, or other distribution source.
- f) Where a circuit is interrupted by removal of a device or fixture from that circuit, provide additional conduit and wire to restore service to the remaining devices and fixtures on that circuit.
- g) Electrical equipment to be removed that is in good working order shall be carefully removed and offered to the Owner. Items rejected by the Owner shall be removed from the project site and properly disposed of.

SECTION 16100 - BASIC MATERIALS AND METHODS

1) PART 1 GENERAL

a) REFERENCES

i) All equipment and installations shall meet or exceed minimum requirements of ADA, ANSI, ASTM, IEEE, IES, NEC, NEMA, NETA, NFPA, OSHA, SMACNA, UL, and the State Fire Marshal. Equipment shall be certified for use in the State of the project and shall meet the State energy code. Provide products and materials that are new, clean, free of defects, and free of damage and corrosion.

b) PERFORMANCE REQUIREMENTS

i) Provide support system for equipment and conduit, including wiring, with a minimum safety factor of 4. For empty conduits, include weight of 4 type XHHW wires of maximum permissible size.

c) QUALITY ASSURANCE

i) All equipment and installations shall meet or exceed minimum requirements of ADA, ANSI, ASTM, IEEE, IES, NEC, NEMA, NETA, NFPA, OSHA, SMACNA, UL, and the State Fire Marshal. Equipment shall be certified for use in the State of the project and shall meet the State energy code. Provide products and materials that are new, clean, free of defects, and free of damage and corrosion.

2) PART 2 PRODUCTS

a) CONDUIT

i) General

- (1) Exposed Dry and Damp Locations:
 - (a) Use electrical metallic tubing.
- (2) Concealed Locations:
 - (a) Furred, Ceiling Spaces and Stud Walls: Use electrical metallic tubing.
 - (b) Connections to Lighting Fixtures in Accessible Ceilings: Use flexible conduit.
- (3) Equipment Connections:
 - (a) Connections to Liquid-Handling Equipment in Dry Locations: Use liquid-tight flexible conduit.
- (4) Equipment for Dry Systems in Dry Locations: Use flexible conduit.

ii) Electrical Metallic Tubing:

- (1) Continuous, seamless steel tubing, galvanized or sherardized on exterior, coated on interior with smooth hard finish of lacquer, varnish or enamel, with steel, set screw or compression type fittings. Provide concrete type fittings where required.
- (2) Use for general purpose feeders and branch circuits.

iii) Flexible Steel Conduit:

- (1) Single strip, continuous, flexible interlocked double-wrapped steel, hot dip galvanized inside and out forming smooth internal wiring channel, with steel, compression type fittings.
- (2) Use in dry locations only, connections to lighting fixtures in suspended ceilings, connections to equipment installed above suspended ceilings, transformer connections, busway plug in units, and connections to equipment where vibration isolation is required, maximum length of 6 feet.

iv) Liquid Tight Flexible Steel Conduit:

- (1) Same as flexible steel conduit except with tough, inert, watertight plastic outer jacket. Fittings shall be cast malleable iron body and gland nut, cadmium plated with one-piece brass grounding bushings threaded to interior of conduit. Spiral molded vinyl sealing ring between gland nut and bushing and nylon insulated throat.
- (2) Use same as flexible steel conduit in damp or wet locations and at motor connections.

b) BUILDING WIRE AND CABLE

i) Provide wire with a minimum insulating rating of 600 volts, except for wire used in low voltage (below 50 volts) control or signal systems. The use of teflon (multi-conductor) for low tension systems may be permitted for fire alarm, signal and communication systems (voice and data) as approved on shop drawings by engineers and where permitted by local codes and union practice.

ii) Conductors

- (1) Electrical grade, annealed copper, and fabricated in accordance with ASTM standards. Minimum size number 12 AWG for branch circuits; number 14 AWG for control wiring.
- (2) Unless otherwise specified, all wires numbers 10 and smaller shall be solid.
- (3) All wires number 8 and larger shall be stranded in accordance with ASTM Class B stranding designations.
- (4) Control wires shall be stranded in accordance with ASTM Class B stranding designations.
- (5) Cables for low tension systems shall be multi-conductor, 16 gauge, color coded and insulated in armored cable assembly, with number of conductors as required.
- (6) All 600 volt wire and cables unless otherwise specified shall be single conductor suitable for use in wet and dry and locations.

iii) Connectors

- (1) Make connections, splices, taps and joints with solderless devices, mechanically and electrically secure. Protect exposed wires and connecting devices with electrical tape or insulation to provide insulation values not less than on conductor.

iv) Cables (No. 8 and Larger):

- (1) Use set screw or compression type connectors, taps and splices specifically designed for the particular connection. Insulate splice either by taping or by use of "Bakelite" covers designed to fit around splice.

v) Branch Circuit Wires (Number 10 and Smaller): Use any of the following types of terminals and connecting devices:

- (1) Hand Applied: Coiled, tapered, spring wound devices with a conducting corrosion-resistant coating over the spring steel and a plastic cover and skirt providing full insulation for splice and wired ends. Screw connector on by hand.
- (2) Tool Applied: Steel cap, with conduction and corrosion resistant metallic plating, open at both ends, fitted around the twisted ends of the wire and compressed or crimped by means of a special die designed for the purpose. Specifically fitted plastic or rubber insulating cover wrap over each connector.

c) BOXES

i) Pressed steel, galvanized or cadmium-plated, 4 inches minimum octagonal or square with galvanized cover or extension ring as required.

ii) Back-to-back outlets in the same wall, or "through-wall" type boxes are not permitted. Provide 12 inch minimum spacing for outlets shown on opposite sides of a common wall. Provide acoustical potting compound on all outlet boxes.

d) WIRING DEVICES

i) Switches and Receptacles: Arrow Hart, Hubbell, Leviton, Pass & Seymour, or Slater.

ii) Wall Dimmers: Lutron.

iii) Occupancy Sensors: Mytech, Novitas, or Watt Stopper.

iv) Floor Boxes and Fittings:

- (1) Poke through type: Wiremold Legrand.
- (2) Recessed flush floor box type: Steel City or Wiremold Legrand.

v) Plugstrip: Wiremold.

vi) Device and cover plate colors shall be as selected by Architect.

e) SUPPORTS

i) Support raceways on accepted types of wall brackets, specialty steel clips, or hangers, ceiling trapeze hangers, or malleable iron straps. Plumber's perforated straps are not permitted. Acceptable manufacturers' brackets or hangers are Kindorf, Elcan, Binkley, Multi-Frame, Power-Strut, or Unistrut. Do not suspend raceways or equipment from other raceways, steam, water, or other piping or ductwork, except as otherwise permitted. Provide independent and secure support methods.

f) PANELBOARDS

i) Acceptable Manufacturers: Cutler-Hammer/Westinghouse, General Electric, Siemens, or Square D/Groupe Schneider.

ii) AIC Rating: Branch panelboards and overcurrent protection devices shall have a minimum short circuit rating of 10,000 RMS symmetrical amperes minimum interrupting capacity (120/208V) or 14,000 RMS symmetrical amperes minimum interrupting capacity (277/480V).

iii) AIC Rating: Distribution panelboards and overcurrent protection devices shall have a minimum short circuit rating of 42,000 RMS symmetrical amperes minimum interrupting capacity (120/208V) or 200,000 RMS symmetrical amperes minimum interrupting capacity (277/480V).

iv) Enclosures: Corrosion resistant galvanized (zinc finished) sheet steel. Fronts shall be cold rolled steel, finish coated with ANSI 61 grey enamel over a rust inhibitor. Panel locks shall be keyed alike.

v) Doors: One piece bolt on front with a lockable hinged door over the overcurrent protection devices.

vi) Bus Bars: Silver plated aluminum or copper. Neutral bus shall be full size. Neutral bus shall be 200% rated when supplied from a double neutral feeder. Provide an equipment ground bus in each panelboard. In addition to the equipment ground bus, provide an isolated ground bus when supplied from a feeder which includes an isolated grounding conductor.

f) LIGHTING FIXTURES

i) Acceptable Manufacturers: See fixture schedule on sheet E1.1 for fixture types.

j) All exterior fixtures shall conform to section 405 of the Steamboat Springs Municipal Code Community Development Code.

vii) Overcurrent Protection Devices: Molded case circuit breakers for branch panelboards and 120/208V rated distribution panels, and fusible switch units for 277/480V rated distribution panels.

g) MOTOR STARTERS

i) Acceptable Manufacturers: Eaton/Cutler-Hammer, General Electric, Siemens, or Square D/Groupe Schneider.

ii) Manual Motor Starters

iii) Fractional Horsepower Manual Starter: General-purpose, Class A, manually operated, full-voltage controller for fractional horsepower induction motors, with thermal overload unit, and toggle operator.

iv) Voltage, Rating and Thermal Element: As required by motor controller.

v) Enclosure: NEMA ICS 6; Type 1.

h) PULL LINE

i) 1/8 inch diameter braided yellow polypropylene.

3) PART 3 EXECUTION

a) INSTALLATION

i) Conduit

- (1) Install conduit in accordance with NECA "Standard of Installation".
- (2) Do not combine individual homeruns into common conduit.
- (3) Do not support conduit with wire or perforated pipe straps. Remove wire used for temporary supports.
- (4) Arrange conduit to maintain headroom and present neat appearance.
- (5) Use conduit hubs to fasten conduit to cast boxes.
- (6) Provide insulated equipment ground conductor in flexible conduit.
- (7) Install conduit to preserve fire resistance rating of partitions and other elements.
- (8) Do not attach conduit to ceiling support wires.

ii) Building Wire and Cable

- (1) Use conductor not smaller than 12 AWG for power and lighting circuits.
- (2) Neatly train and lace wiring inside boxes, equipment, and panelboards.
- (3) Make splices, taps, and terminations to carry full ampacity of conductors with no perceptible temperature rise.
- (4) Use hardened and tempered steel, tin-plated or stainless steel Belleville washer with slightly larger tin-plated mild steel flat washer for aluminum lugs.
- (5) Use insulated spring wire connectors with plastic caps for copper conductor splices and taps, 8 AWG and smaller.

iii) Boxes

- (1) Install electrical boxes as shown on Drawings, and as required for splices, taps, wire pulling, equipment connections and compliance with regulatory requirements.
- (2) Install electrical boxes to maintain headroom and to present neat mechanical appearance.
- (3) Install boxes to preserve fire resistance rating of partitions and other elements; arrange boxes to meet regulatory requirements.
- (4) Align adjacent wall-mounted outlet boxes for switches, thermostats, and similar devices to each other.
- (5) Do not use through-walls boxes or install flush mounting boxes back-to-back in walls; provide minimum 6 inch separation. Provide minimum 24 inches separation in acoustic rated walls.
- (6) Use stamped steel bridges in bar hanger assemblies to fasten flush mounting outlet box between studs.
- (7) Use adjustable steel channel fasteners for hung ceiling outlet box.
- (8) Do not fasten boxes to ceiling support wires.
- (9) Support steel metal boxes independently of conduit.
- (10) Use gang box where more than one device is mounted together, including floor boxes. Do not use sectional box.
- (11) Plaster Rings: Use for all concealed work; depth of rings as required to reach finished surfaces.
- (12) Coordinate trimming of openings for outlet boxes in partitions to achieve neat, closely-fitting openings.
- (13) Install knockout closure in unused box opening.

iv) Wiring Devices

- (1) Install devices plumb, level, and rigidly in place.
- (2) Install switches 2 inches to 8 inches from trim on the strike side.
- (3) Install decorative plates on switch, receptacle, and blank outlets in finished areas. Use multi-gang plates for multiple devices.
- (4) Connect wiring devices by wrapping conductor around screw terminal.

v) Supporting Devices

- (1) Fasten hanger rods, conduit clamps, and outlet and junction boxes to building structure using expansion anchors, beam clamps, steel ramset fasteners.
- (2) Use toggle bolts or hollow wall fasteners in plaster or gypsum board partitions and walls; sheet metal screws or spring steel bar retainer clips in sheet metal studs.
- (3) Do not fasten supports to piping, ductwork, mechanical equipment, or conduit.
- (4) Do not use powder-actuated anchors without specific permission.
- (5) Do not drill structural steel members without specific permission.
- (6) Fabricate supports from structural steel or steel channel, rigidly welded or bolted to present a neat appearance. Use hexagon head bolts with spring lock washers under nuts.

vi) Electrical Identification

- (1) Provide wire markers on each conductor in panelboard gutters, pull boxes, and at load connection. Identify with branch circuit for power and lighting circuits, and with control wire number as indicated on equipment manufacturer's shop drawings for control wiring. If more than one neutral conductor is present, mark each with related circuit numbers.
- (2) Color code all secondary branch circuit and feeder conductors as follows:
 - (a) Four Wire, Three Phase, Grounded Wye System: For 120/208 volt systems, use one black, one red, one blue, one white (neutral). For 277/480 volt systems, use one brown, one orange, one yellow and one gray (neutral).
- (3) Use wire with insulation of required color. For sizes of wire, which may not be available in specified colors use self-adhesive wrap around, markers of solid colors to color code conductors.
- (4) Color code conductors at accessible locations.
- (5) Pull Rope Marking: Affix label identifying termination point at each end of pull rope.

vii) Disconnect Switches

- (1) Install disconnect switches shown mounted on walls at +4'-6" to centerline of switch.
- (2) Install disconnect switches shown on or adjacent to equipment on field fabricated galvanized steel frames.

viii) Panelboards

- (1) Provide filler plates for unused spaces in panelboards.
- (2) Provide typed circuit directory in plastic holder for each branch circuit panelboard.

ix) Motor Starters

- (1) Install motor control equipment in accordance with manufacturer's instructions.
- (2) Select and install heater elements in motor starters to match installed motor characteristics.

x) Pull Line: Provide in each empty conduit except sleeves and nipples; leave 8 inches of slack at each outlet.

xi) Firestopping: Provide firestopping around all pipes, conduits, sleeves, etc., which pass through rated walls, partitions and floors.

END OF SECTION

SKI TIME
SQUARE DRIVE
PUBLIC
TURNAROUND

BASELINE
ENGINEERING

1169 Hilltop Parkway, Suite 204
PO Box 770152
Steamboat Springs, CO 80477



WILDER ENGINEERING LLC
Andrew Wilder PE
1170 Blue Sage Drive
Steamboat Springs, CO 80487
P: 970-819-7848
E: andy@wilder-eng.com



Issue	By	Date & Issue Description	By
—	PROGRESS SET	— 1.6.23	AW
—	100% DESIGN	— 1.16.23	AW
—	BID DOCUMENTS	— 2.8.23	AW
—	REVISION #1	— 2.9.24	AW
—	EV REVISION	— 7.11.24	AW

Scale: NTS
24x36
Description: SPECIFICATIONS
Project Name: SKI TIME SQ TURNAROUND
Project Number: 2022009
Sheet No.
E-3.0

IFGC PIPE SIZING CALCULATOR FOR NATURAL GAS PRESSURES LESS THAN 15 PSI		
METER DISCHARGE PRESSURE = 14 (W.C.) ALLOWABLE PRESSURE DROP = 7 (W.C.) TOTAL EQUIVALENT LENGTH OF PIPE = 180 FEET ALTITUDE CORRECTION FACTOR = 831 BTU/CFH @ ALT.		
NOMNAL SCHD. 40 STEEL PIPE SIZE	CAPACITY (CFH)	CAPACITY (MBH)
1/2"	150	125
3/4"	314	262
1"	592	492
1-1/4"	1215	1010
1-1/2"	1820	1513
2"	3506	2914
2-1/2"	5588	4644
3"	9878	8209
4"	20148	16743
5"	36450	30290
6"	59021	49047
*PIPE CAPACITY IS CALCULATED USING FORMULA FOR LOW PRESSURE GAS (15 PSI AND LESS) LOCATED IN IFGC APPENDIX A Q = 29.137(P^2.8327)(W)(C)(L)^.541 Q = CAPACITY (CFH) D = INSIDE PIPE DIAMETER H = ALLOWABLE PRESSURE DROP (W.C.) C = FACTOR FOR VISCOSITY, DENSITY AND TEMPERATURE = .6064 L = LENGTH OF PIPE (FEET)		

SNOWMELT BOILER SCHEDULE																			
SYMBOL	SERVICE	MANUFACTURER	MODEL	SNOWMELT ZONE AREA	HEATING CAPACITY					GPM	ELECTRICAL					COMB. AIR SIZE IN	UNIT WEIGHT (LBS.)	REMARKS	
					INPUT @ S.L. MBH	OUTPUT @ S.L. MBH	OUTPUT @ 670°F MBH	EWT (°F)	LWT (°F)		VOLTAGE	PHASE	FLA	MCA	MOCp				
B-1	SNOWMELT	LOCHINVAR	KBX500N	2,308	500,000	485,000	349,200	120	140	30	120	1	9.2	11.5	20	14	8	X	1, 2, 3, 4
REMARKS: 1. ACCEPTABLE MANUFACTURERS: AERCO, LAARS, RHEIM. 2. BURNER SHALL BE DESIGNED TO FIRE ON NATURAL GAS, 720 BTU/CF, 7" WC. 3. PROVIDE INDIVIDUAL FACTORY MOUNTED BOILER CONTROL PANEL WITH (BUILDING STANDARD) CONTROLS TO COMMUNICATE WITH BUILDING AUTOMATION SYSTEM. COORDINATE WITH CONTROLS CONTRACTOR. 4. 40% GLYCOL.																			

EXPANSION TANK SCHEDULE															
SYMBOL	MANUFACTURER	MODEL	TYPE	APPROX SYSTEM VOLUME (GAL)	SYSTEM TEMPERATURE RANGE		INITIAL PRESSURE IN TANK (PSIG)	MAX OPERATING PRESSURE (PSIG)	RELIEF PRESSURE AT TANK		MIN VOLUME TANK (GAL)	MIN BLADDER VOLUME (GAL)	PIPE SIZE TO TANK (IN)	APPROX. OPERATING WT. (LBS)	REMARKS
					MIN (F)	MAX (F)			RELIEF VALVE (PSIG)	AT TANK (PSIG)					
ET-1	BELL AND GOSSETT	B130	BLADDER	500	25	180	12	30	35	X	34	22	1	450	1, 2, 3, 4
REMARKS: 1. ASME CONSTRUCTION. 2. REPLACEABLE BUTYL BLADDER 3. PRECHARGED, ADJUSTABLE. 4. RATED FOR GLYCOL USE.															

PUMP SCHEDULE																
SYMBOL	MANUFACTURER	SERVICE	PUMP TYPE	PUMP SERIES	MODEL	GPM	HEAD FT WC	EFF %	MIN HP	RPM	ELECTRICAL		SUCTION SIZE IN	DISCH SIZE IN	APPROX OPERATING WEIGHT	REMARKS
											VOLTS	PHASE				
P-1	BELL AND GOSSETT	SNOWMELT	BASE MTD	E-1510	1.25AD	30	115	52	5	1800	208	3	1-1/2	1-1/2	100	1, 2
REMARKS: 1. ACCEPTABLE MANUFACTURERS: ARMSTRONG, TACO. 2. 40% GLYCOL.																

SNOWMELT SYSTEM SUMMARY													
LOCATION	PROJECT NAME	ZONE SEE CIVIL PLANS	PROJECT ELEVATION (FT.)	SNOWMELT DESIGN TEMPERATURE (°F)	SNOWMELT DESIGN WIND SPEED (MPH)	TOTAL AREA PH 1 (SQ. FT.)	BTUH PER AREA SQ. FT.	TOTAL LOAD (BTUH)	TOTAL GPM @ 25 DEG DELTA T	SNOWMELT GLYCOL LEVEL (%)	SNOWMELT FLUID TEMP. DROP (°F)	TOTAL FLUID VOLUME (GAL)	GLYCOL VOLUME (GAL)
STEAMBOAT COLORADO	KUTUK APARTMENTS	NEW #2	9,700	0	10	2,057	145	298,285	30	40	25	135	54
BOILER SELECTION CALCULATIONS: TOTAL SNOW- MELT LOAD 298,285 BTUH / (0.97 * 0.72) = 427,0690 BTUH REQUIRED SELECTED BOILER AT 500,000 BTUH TOTAL.													
0.97 BOILER EFFICIENCY 0.72 ALTITUDE ADJUSTMENT													

PLUMBING EQUIPMENT SCHEDULE						
SYMBOL	TYPE	ADA	ACCESSORIES	FINISH	MANUFACTURER & MODEL NUMBER	REMARKS
HB-1	SURFACE MOUNTED EXPOSED TYPE HOSE BIBB, ALL BRASS REMOVABLE TEE HANDLE, SPOUT OUTLET VACUUM BREAKER	N/A	3/4" HOSE THREAD OUTLET, PROVIDE WITH SHUT/OFF BALL VALVE IN BRANCH PIPE	ROUGH BRASS	WOODFORD 24	1/2" SUPPLY CONNECTION
NOTE: ALL CONNECTIONS TO POTABLE WATER SYSTEM SHALL CONFORM TO NSF/ANSI-61 AND NSF/ANSI-372 EFFECTIVE 01/04/2014.						

TOTAL CONNECTED GAS LOAD SCHEDULE					
EQUIPMENT	QTY	INPUT EACH (BTUH @ SL)	INPUT TOTAL (BTUH @ SL)	INLET PRESSURE	NOTES
EXISTING EQUIPMENT					
BOILER	1	399,000	399,000	7" WC	EXISTING TO REMAIN
POOL HEATER	1	400,000	400,000	7"WC	EXISTING TO REMAIN
SPA HEATER	1	300,000	300,000	7"WC	EXISTING TO REMAIN
WATER HEATER	1	199,999	199,999	7"WC	EXISTING TO REMAIN
TOTAL GAS LOAD REMAINING			1,298,999		
NEW EQUIPMENT					
BOILER B-1	1	500,000	500,000	7" WC	1, 2, 3
TOTAL NEW LOAD=			500,000		
TOTAL EXISTING LOAD TO REMAIN=			1,298,999		
BUILDING TOTAL CONNECTED LOAD=			1,798,999		NEW AND EXISTING
NOTES: 1. MODIFICATIONS TO GAS METER AND/OR SERVICE PIPING SHALL BE PERFORMED BY THE GAS COMPANY. SUBMIT REQUIRED GAS SERVICE APPLICATION TO GAS COMPANY IN A TIMELY MANNER TO MEET THE CONSTRUCTION SCHEDULE. 2. FARTHEST CONNECTED DEVICE DISTANCE BASED ON 180' 3. PIPE SIZING BASED ON PRESSURE AT METER OUTLET OF 14 INCHES WC. CONTRACTOR TO FIELD VERIFY OUTLET PRESSURE PRIOR TO STARTING WORK.					

AIR SEPARATOR SCHEDULE								
SYMBOL	MANUFACTURER	MODEL	TYPE	SIZE (IN)	FLOW (GPM)	WPD (FT)	BUILT IN STRAINER	REMARKS
AS-1	BELL AND GOSSETT	R-3F	FLANGED	3	30	0.25	YES	1, 2
REMARKS: 1. BLOWDOWN FOR ROUTINE MAINTENANCE. 2. AUTOMATIC AIR VENT.								
SPECIFICATIONS: A. TANGENTIAL OPENINGS. B. CONSTRUCTED PER ASME SECTION VIII DIVISION 1 C. CARBON STEEL SHELL. D. TYPE 304 STAINLESS STEEL STRAINER, 3/16" DIAMETER PERFORATIONS, 51% OPEN AREA. E. MAXIMUM WORKING PRESSURE 125 PSIG.								

GENERAL NOTES:

CONTRACTOR SHALL DESIGN THE SNOW MELT SYSTEM ZONES BASED ON UPONOR, OR EQUAL. CONTRACTOR SHALL SUBMIT SHOP DRAWINGS OF THE SNOW MELT ZONES FROM MANUFACTURER. SEE CIVIL PLANS FOR SNOW MELT ZONE LOCATIONS AND ADDITIONAL INFORMATION.

MECHANICAL LEGEND		
NOT ALL ITEMS LISTED BELOW ARE USED ON THIS SET OF MECHANICAL DRAWINGS		
GENERAL		
SYMBOL	DESCRIPTION	
	REFERENCE BUBBLE	
	MECHANICAL/ELECTRICAL EQUIPMENT DESIGNATION	
	REMOVE EXISTING	
	UNDERCUT DOOR	
	AIR FLOW	
	CONNECT NEW TO EXISTING	
DOUBLE LINE DUCTWORK		
SYMBOL	DESCRIPTION	
	RECTANGULAR SUPPLY AIR DUCT UP	
	RECTANGULAR SUPPLY AIR DUCT DOWN	
	RECTANGULAR RETURN AIR / EXHAUST DUCT UP	
	RECTANGULAR RETURN AIR / EXHAUST DUCT DOWN	
	ROUND DUCT UP	
	ROUND DUCT DOWN	
	BRANCH DUCT 45 TAKE-OFF	
	RECTANGULAR DUCT ELBOW WITH TURNING VANES	
	RADIUS ELBOW RECTANGULAR/ROUND DUCT	
	DUCT TRANSITION	
	FLEX CONNECTION	
SINGLE LINE DUCTWORK		
SYMBOL	DESCRIPTION	
	RECTANGULAR DUCT ELBOW WITH TURNING VANES	
	RADIUS ELBOW RECTANGULAR/ROUND DUCT	
	DUCT TRANSITION	
	CONICAL SPIN-IN FITTING	
	CONICAL SPIN-IN FITTING W/DAMPER	
	FLEXIBLE DUCT	
CONTROL DEVICES AND DAMPERS		
SYMBOL	DESCRIPTION	
	HUMIDISTAT	
	PRESSURE SENSOR	
	WALL MOUNTED THERMOSTAT	
	UNIT MOUNTED THERMOSTAT	
	SWITCH	
	FIRE DAMPER	
	RADIATION DAMPER	
	SMOKE DAMPER	
	COMBINATION FIRE AND SMOKE DAMPER	
	MANUAL VOLUME DAMPER	
	WILOCKING QUADRANT	
	MOTORIZED DAMPER	
PIPING		
SYMBOL	ABBV. DESCRIPTION	
	HS HOT WATER SUPPLY	
	HR HOT WATER RETURN	
	CWS CHILLED WATER SUPPLY	
	CWR CHILLED WATER RETURN	
	CS CONDENSER SUPPLY	
	CR CONDENSER RETURN	
	HPS HIGH PRESSURE STEAM	
	HPC HIGH PRESSURE CONDENSATE	
	PC PUMPED CONDENSATE	
	D EQUIPMENT DRAIN	
	RL REFRIGERANT LIQUID	
	RS REFRIGERANT SUCTION	
PIPING SYMBOLS		
SYMBOL	DESCRIPTION	
	ARROW IN LINE INDICATES DIRECTION OF FLOW	
	INDICATES PIPE SLOPE DOWN	
	BOTTOM PIPE CONNECTION	
	PIPING UP	
	PIPING DOWN	
	FIXTURE TRAP OR DRAIN TRAP	
	PIPING CAP OR PLUG	
	PUMP	
	BALANCING VALVE/ FLOW MEASURING DEVICE	
	CALIBRATED BALANCING VALVE	
	BALL VALVE	
	PLUG VALVE	
	GATE VALVE	
	CHECK VALVE	
	BUTTERFLY VALVE	
	FLOW SWITCH	
	SOLENOID VALVE	
	PRESSURE REDUCING VALVE	
	3-WAY TEMPERATURE CONTROL VALVE	
	2-WAY TEMPERATURE CONTROL VALVE	
	RELIEF VALVE	
	STRAINER	
	STRAINER WITH BLOW-OFF VALVE	
	UNION	
	PRESSURE GAUGE	
	THERMOMETER	
	P/T	
	PRESSURE AND TEMPERATURE TAP	
	CONCENTRIC REDUCER	
	ECCENTRIC REDUCER	
	FLEXIBLE CONNECTOR	
	HOSE END DRAIN VALVE	
	MANUAL AIR VENT	
ABBREVIATIONS		
AFF	ABOVE FINISHED FLOOR	
AP	ACCESS PANEL	
C	COMMON	
(E)	EXISTING	
EC	ELECTRICAL CONTRACTOR	
ELEV	ELEVATION	
EQ	EQUIPMENT	
GC	GENERAL CONTRACTOR	
MC	MECHANICAL CONTRACTOR	
(N)	NEW	
NC	NORMALLY CLOSED	
NIC	NOT IN CONTRACT	
NO	NORMALLY OPEN	
NTS	NOT TO SCALE	
OA	OUTSIDE AIR	
PRV	PRESSURE REDUCING VALVE	
RA	RETURN AIR	
RE	REFER TO	
SA	SUPPLY AIR	
SRV	SAFETY RELIEF VALVE	
TCC	TEMPERATURE CONTROL CONTRACTOR	
TYP	TYPICAL	
NOTE:		
APPLICABLE CODE STANDARDS		
2018 INTERNATIONAL BUILDING CODE	2018 INTERNATIONAL MECHANICAL CODE	2018 INTERNATIONAL ENERGY CONSERVATION CODE
2018 INTERNATIONAL FIRE CODE	2018 INTERNATIONAL PLUMBING CODE	2018 INTERNATIONAL FUEL GAS CODE



KUTUK SNOW MELT UPGRADES
STEAMBOAT SPRINGS, COLORADO






ISSUE DATE
CONSTRUCTION DOCUMENTS 11/10/23

MEP JOB: 22336
DESIGNED: MAB
CHECKED: KVB

MECHANICAL EQUIPMENT SCHEDULES



M1.0



KUTUK SNOW MELT UPGRADES
STEAMBOAT SPRINGS, COLORADO


ISSUE	DATE
CONSTRUCTION DOCUMENTS	11/10/23

MEP JOB: 22336
DESIGNED: MAB
CHECKED: KVB

MECHANICAL
DIAGRAMS




M1.1



DRAWING NOTES

- EXISTING GAS METER. NEW GAS LOAD 2,399.9 BTUH. COORDINATE NEW GAS LOAD WITH ATMOS ENERGY IN A TIMELY MANNER THAT MEETS THE CONSTRUCTION SCHEDULE. MODIFICATIONS TO THE GAS SERVICE AND GAS METER SHALL BE PERFORMED BY ATMOS ENERGY.
- EXISTING HEATING WATER SUPPLY AND RETURN PIPING TO EXISTING SNOW MELT ZONES. FIELD VERIFY.
- CONNECT NEW 1-1/4\" GAS PIPING TO EXISTING GAS METER. PROVIDE NEW 2\" MANIFOLD AT EXISTING GAS METER AND CONNECT EXISTING 1-1/2\" GAS AND NEW 1-1/4\" GAS.
- NEW 2\" CONTROL WIRING CONDUIT TO EACH SNOW MELT ZONE VALVE BOX ASSEMBLY AND SNOW MELT SENSOR. CONTRACTOR SHALL FIELD DETERMINE ROUTING DURING CONSTRUCTION. NOTIFY THE ENGINEER OF ANY DISCREPANCIES.



MECHANICAL FLOOR PLAN

SCALE: 1/8\" = 1'-0\"

KUTUK SNOW MELT UPGRADES
STEAMBOAT SPRINGS, COLORADO


ISSUE	DATE
CONSTRUCTION DOCUMENTS	11/10/23

MEP JOB: 22336
DESIGNED: MAB
CHECKED: KVB

MECHANICAL
FLOOR PLAN



M2.0



1. EXISTING SNOW MELT BOILER AND ALL ASSOCIATED ACCESSORIES AND PIPING TO REMAIN.
2. EXISTING BOILER FLUE AND COMBUSTION AIR DUCT TO REMAIN.
3. EXISTING POOL/SPA HEATER, NO CHANGE.
4. EXISTING FLOOR DRAIN TO REMAIN, FIELD VERIFY ACTUAL LOCATION.
5. EXISTING WATER HEATER, NO CHANGE.
6. EXISTING BOILER FLUE, NO CHANGE.
7. EXISTING FLUE UP TO ROOF, FIELD VERIFY ACTUAL FLUE ROUTING. CONTRACTOR SHALL NOTE ROUTING AND MATERIALS THAT MAY POTENTIALLY BE REQUIRED TO REMOVE FOR NEW BOILER FLUE ROUTING.
8. EXISTING GAS PIPING DOWN TO POOL/SPA BOILER TO REMAIN. REMOVE GAS PIPING SERVING EXISTING BOILER TO REMAIN.
9. EXISTING 1-1/2" GAS PIPING, NO CHANGE.
10. EXISTING GAS PRESSURE REGULATING VALVE, NO CHANGE.
11. EXISTING POOL/SPA EQUIPMENT, FIELD VERIFY, NO CHANGE.
12. EXISTING HEATING WATER UNIT HEATER TO REMAIN.
13. EXISTING HEATING WATER SUPPLY AND RETURN TO EXISTING SNOW MELT ZONES TO REMAIN. FIELD VERIFY.
14. EXISTING SNOW MELT PUMPS TO REMAIN.
15. REMOVE AND RELOCATE EXISTING CONTROL PANEL. CONTRACTOR SHALL FIELD VERIFY PROPER FUNCTION AND PURPOSE. MAINTAIN FUNCTIONALITY AT NEW LOCATION.
16. REMOVE EXISTING WALL. CONTRACTOR SHALL FIELD VERIFY AND MOVE/RELOCATE EXISTING EQUIPMENT CURRENTLY ON THE WALL.



1. EXISTING POOL/SPA EQUIPMENT LOCATION, NO CHANGE.
2. PROVIDE NEW CONCRETE PAD FOR BOILER. CONCRETE PAD SHALL BE 4" TALL AND 4" WIDER THAN THE OVERALL FOOTPRINT OF THE BOILER. COORDINATE DIMENSIONS WITH BOILER SELECTION BY M.C.
3. EXISTING POOL/SPA HEATING BOILERS, NO CHANGE.
4. EXISTING WATER HEATER, NO CHANGE.
5. EXISTING FLUE UP THRU ROOF, FIELD VERIFY. CONTRACTOR SHALL FIELD VERIFY EXISTING FLUE ROUTING TO DETERMINE ROUTING OF NEW FLUE IN THE SAME MANNER.
6. NEW BOILER FLUE ROUTING SHALL MATCH ROUTING OF EXISTING FLUE. CONTRACTOR SHALL FIELD VERIFY ACTUAL ROUTING. CONTRACTOR SHALL BE RESPONSIBLE FOR ALL CUTTING AND PATCHING OF MATERIALS REQUIRED FOR FLUE INSTALLATION. REPAIR WALLS, CEILINGS AND ROOFS TO MATCH EXISTING. TERMINATE WITH GOOSENECK AND OPENING BIRD SCREEN PROTECTION.
7. EXISTING GAS PRESSURE REGULATING VALVE.
8. EXISTING HEATING WATER UNIT HEATER, NO CHANGE.
9. COMBUSTION AIR INTAKE FOR BOILER OPEN TO GARAGE. PROVIDE BIRD SCREEN.
10. EXISTING SNOW MELT ZONE PUMP(S) TO REMAIN.
11. EXISTING SNOW MELT ZONE MANIFOLD, FIELD VERIFY.
12. HEATING WATER SUPPLY AND RETURN PIPING TO NEW SNOW MELT ZONE.
13. EXISTING HEATING WATER SUPPLY AND RETURN PIPING TO EXISTING SNOW MELT ZONES, FIELD VERIFY.
14. 2" CONDUIT FOR NEW SNOW MELT SYSTEM CONTROL WIRING. CONDUIT SHALL BE ROUTED TO NEW SNOW MELT SYSTEM SENSOR AND TO EACH NEW ZONE VALVE BOX.
15. NEW LOCATION, EXISTING CONTROL PANEL. CONTRACTOR SHALL FIELD VERIFY PROPER FUNCTION AND PURPOSE. MAINTAIN FUNCTIONALITY AT NEW LOCATION. PROVIDE NEW ELECTRICAL CONDUIT AS REQUIRED.
16. NOT USED.
17. PROVIDE NEW CONCRETE PAD FOR PUMP. CONCRETE PAD SHALL BE 4" TALL AND 4" WIDER THAN THE OVERALL FOOTPRINT OF THE PUMP. COORDINATE DIMENSIONS WITH PUMP SELECTION.
18. EXPANSION TANK ET-1.
19. GLYCOL FEEDER ASSEMBLY.
20. EXISTING SNOW MELT BOILER INTAKE AND FLUE PIPING, FIELD VERIFY.
21. EXISTING SNOW MELT BOILER AND ALL ASSOCIATED ACCESSORIES TO REMAIN, FIELD VERIFY.
22. COLD WATER PIPING TO NEAREST COLD WATER BRANCHMAIN, FIELD VERIFY.



KUTUK SNOW MELT UPGRADES


STEAMBOAT SPRINGS, COLORADO

ISSUE	DATE
CONSTRUCTION DOCUMENTS	11/10/23

MEP JOB: 22336
DESIGNED: MAB
CHECKED: KVB

MECHANICAL ROOM
PLANS

M3.0



SNOW MELT SYSTEM REQUIREMENTS

A. ALL LABOR, MATERIALS, TRANSPORTATION, EQUIPMENT, AND SERVICES TO INSTALL A HYDRONIC SNOW MELTING SYSTEM.

A. MANUFACTURER'S SUBMITTAL DATA SHALL CONSIST OF SHOP DRAWINGS, AND/OR DESCRIPTIONS OF MATERIALS, DETAILS OF INSTALLATION, CAPACITY RATINGS, AND CONTROL SEQUENCING.

A. COMPONENTS OF THE BURIED TUBING SYSTEM SHALL BE PROVIDED BY ONE MANUFACTURER, INCLUDING TUBE, FITTINGS, MANIFOLDS, CONTROLS, AND OTHER ANCILLARY ITEMS REQUIRED FOR A COMPLETE INSTALLATION.

1.04 MANUFACTURER'S WARRANTY

DATE OF OWNER ACCEPTANCE OF PROJECT.

A. THE SNOWMELT SYSTEM CONTROL PANEL, OUTDOOR SENSOR, AND SNOW/ICE SENSOR SHALL BE FURNISHED BY THE SNOWMELT SYSTEM MANUFACTURER. THE BAS CONTRACTOR SHALL INSTALL THE COMPLETE SNOWMELT CONTROL SYSTEM AND SHALL FURNISH ALL CONTROL DEVICES, VALVES, WIRING, AND TUBING NOT FURNISHED BY THE SNOWMELT SYSTEM MANUFACTURER.

2.01 TUBE

B. THE TUBE SHALL BE MANUFACTURED IN ACCORDANCE WITH ASTM STANDARD SPECIFICATION F875-01. THE TUBE SHALL BE LISTED TO ASTM BY INDEPENDENT THIRD PARTY TESTING LABORATORY.

C. THE TUBE SHALL HAVE AN OXYGEN DIFFUSION BARRIER CAPABLE OF LIMITING OXYGEN DIFFUSION THROUGH THE TUBE TO NO GREATER THAN $0.10 \text{ g / M}^2 \text{ / DAY}$ AT 104° F WATER TEMPERATURE.

D. THE TUBE SHALL BE A MAXIMUM OF $3/4"$ DIAMETER IN ACCORDANCE WITH ASTM STANDARD SPECIFICATION AS ABOVE.

E. THE MINIMUM BEND RADIUS FOR COLD BENDING OF THE TUBE SHALL NOT BE LESS THAN SIX (6) TIMES THE OUTSIDE DIAMETER. BENDS WITH A RADIUS LESS THAN STATED SHALL REQUIRE THE USE OF A BEND SUPPORT AS SUPPLIED BY THE TUBE MANUFACTURER.

A. MULTIPLE CONNECTION MANIFOLDS SHALL BE OF CAST BRASS CONSTRUCTION, MANUFACTURED OF ALLOYS TO PREVENT DEZINCIFICATION, AND SHALL HAVE INTEGRAL CIRCUIT BALANCING VALVES. MANIFOLDS SHALL BE ABLE TO VENT AIR FROM THE SYSTEM AND SHALL BE PROVIDED WITH SUPPORT BRACKETS AND TUBE BEND SUPPORTS. MANIFOLD CIRCUITS SHALL BE ISOLATED FROM SUPPLY AND RETURN TUBING WITH VALVES THAT ARE SUITABLE FOR ISOLATION AND BALANCING.

A. FITTINGS SHALL BE MANUFACTURED OF DEZINCIFICATION RESISTANT BRASS. THESE FITTINGS SHALL BE SUPPLIED BY THE TUBE MANUFACTURER. THE FITTINGS SHALL CONSIST OF A COMPRESSION FITTING WITH INSERT COMPRESSION RING AND A COMPRESSION NUT.

A. REMOVABLE ACCESS COVERS SHALL BE OF REINFORCED CONCRETE FORMED IN PLACE OR PRE-CAST CONCRETE OVER PIPE CONNECTIONS, FITTINGS, AND DISTRIBUTION MANIFOLDS. THEY SHALL BE BOTH INCONSPICUOUS AND HEAVY ENOUGH TO PREVENT UNAUTHORIZED REMOVAL. TAPERED FORMS FOR COVERS SHALL BE FURNISHED. COVERS SUBJECT TO VEHICULAR TRAFFIC SHALL BE TRAFFIC RATED.

A. PROVIDE A MICROPROCESSOR BASED CONTROL PANEL THAT ACTIVATES THE SNOW MELTING SYSTEM BASED ON SIGNALS FROM A SNOW SENSOR AND AN OUTDOOR AIR TEMPERATURE SENSOR. THE CONTROL PANEL SHALL INCLUDE THE FOLLOWING FEATURES:

1. SELECTABLE LCD DISPLAY OF SLAB SURFACE TEMPERATURE, SURFACE TEMPERATURE SETTING, MELT SEQUENCE TIME REMAINING, ACCUMULATED HOURS OF USE, AND PERCENT HEAT OUTPUT. CONTROL PANEL SHALL BE CAPABLE OF ENABLING OR DISABLING THE SYSTEM AS NECESSARY.
2. STATUS LIGHTS INDICATING POWER ON, REMOTE ENABLE SIGNAL PRESENT, WARM WEATHER CUT-OFF, MELTING MODE ACTIVATED, WATER DETECTED, COLD WEATHER CUT-OFF, IDLING MODE ACTIVATED, PUMP ACTIVATED, SYSTEM MELTING, AND SENSOR FAULT.
3. SLAB SURFACE MELTING TEMPERATURE SETPOINT ADJUSTMENT.
4. SLAB SURFACE IDLING TEMPERATURE SETPOINT ADJUSTMENT.
5. MOISTURE SENSOR SENSITIVITY SETPOINT ADJUSTMENT.
6. MELTING SYSTEM MINIMUM ON TIME ADJUSTMENT.
7. COLD WEATHER CUT-OFF TEMPERATURE SETPOINT ADJUSTMENT.

B. TEST BUTTON TO INITIATE TEST SEQUENCE.

B. PROVIDE AN OUTDOOR AIR TEMPERATURE SENSOR CONSISTING OF A 10,000 OHM THERMISTOR PROTECTED WITHIN A WHITE U.V. RESISTANT PVC PLASTIC ENCLOSURE.

C. PROVIDE A SNOW/ICE SENSOR WHICH BITS FLUSH WITH THE SLAB SURFACE AFTER BEING MOUNTED INTO A SENSOR SOCKET. THE SENSOR SHALL MEASURE SLAB SURFACE TEMPERATURE AND SENSOR CORE TEMPERATURE AND SHALL DETECT MOISTURE ON THE SENSOR SURFACE. THE SENSOR SOCKET SHALL BE CONSTRUCTED OF DIE CAST BRASS.

- A. HYDRONIC RADIANT HEAT TUBING LOOPS SHALL BE INSTALLED IN ACCORDANCE WITH THE MANUFACTURER'S WRITTEN INSTALLATION INSTRUCTIONS.
- B. ALL FITTINGS AND MANIFOLDS SHOULD BE ACCESSIBLE THROUGH ACCESS COVERS FOR MAINTENANCE. TUBING LOOPS SHALL BE INSTALLED WITHOUT SPICES, AS A MINIMUM, FROM THE POINT AT WHICH THE TUBING ENTERS THE MANIFOLD TO THE POINT AT WHICH IT EXITS THE MANIFOLD.
- C. INSTALLATION SHALL FOLLOW THE MANUFACTURER'S SHOP DRAWINGS FOR TUBING LAYOUT, TUBE SPACING, MANIFOLD CONFIGURATION, MANIFOLD LOCATION, AND CONTROLS. ALL NOTES ON THE SHOP DRAWINGS SHALL BE FOLLOWED.
- D. DISTRIBUTION MANIFOLDS SHALL BE ATTACHED TO SUPPLY AND RETURN MAINS AT ACCESS COVER LOCATIONS. A MINIMUM OF ONE SUPPLY AND ONE RETURN MANIFOLD IS REQUIRED AND FOR ALTERNATE EXPANSION/CONSTRUCTION JOINTS.
- E. PIPING SHALL BE ATTACHED TO REINFORCING STEEL USING WIRE TIES. ALL LOOPS SHALL BE FORM A CONTINUOUS CONDUIT WITHOUT JOINTS FROM SUPPLY TO RETURN MANIFOLDS.
- F. NO PIPE SHALL EXTEND THROUGH EXPANSION, CONSTRUCTION, OR WORKING JOINTS IN CONCRETE SLAB. COORDINATE EXPANSION JOINTS INSTALLED DURING, OR CUT AFTER, CONCRETE POUR WITH TUBING LAYOUT.
- G. ALL PIPE CONNECTIONS, FITTINGS, AND DISTRIBUTION MANIFOLDS SHALL BE FREE OF CONCRETE AND ARRANGED TO BE EASILY SERVICED BY REMOVAL OF POURED-IN-PLACE CONCRETE ACCESS COVERS.
- H. COORDINATE SYSTEM FLUSHING AND GLYCOL FILL WORK WITH WATER TREATMENT CONTRACTOR.
- I. ALL PIPING CONNECTIONS SHALL BE FIELD WRAPPED WITH INSULATION. WRAP AND INSTALL PER MANUFACTURER'S RECOMMENDATIONS.

A. THE TUBING SYSTEM SHALL BE PRESSURIZED WITH WATER OR AIR TO A PRESSURE OF 60 PSIG 24 HOURS PRIOR TO ENCASEMENT IN THE CONCRETE SLAB. THE TUBING SYSTEM SHALL REMAIN AT THIS PRESSURE DURING THE SLAB INSTALLATION AND FOR A MINIMUM OF 24 HOURS THEREAFTER TO ENSURE SYSTEM INTEGRITY.

A. AT STARTUP TIME, THE CONTRACTOR SHALL FOLLOW THE MANUFACTURER'S RECOMMENDATIONS FOR SYSTEM WATER AND TEMPERATURE BALANCING, RECORD BALANCE SETTINGS AT EACH MANIFOLD LOCATION, AND INCLUDE A COMPLETE RECORD OF THESE SETTINGS IN THE OPERATION AND MAINTENANCE MANUALS.

3.04 SEQUENCE OF CONTROL

- B. THE SNOWMELT SYSTEM SHALL BE CONTROLLED BY A MICROPROCESSOR BASED CONTROL PANEL FURNISHED BY THE SNOWMELT SYSTEM MANUFACTURER. THE OUTDOOR TEMPERATURE SENSOR AND SNOW/ICE SENSOR SHALL ALSO BE FURNISHED BY THE SNOWMELT SYSTEM MANUFACTURER.
- C. THE CONTROL PANEL SHALL CONTINUOUSLY MONITOR THE SNOW/ICE SENSOR LOCATED IN THE SLAB. WHEN SNOW, ICE, OR WATER ARE DETECTED THE MELTING MODE SHALL BE INITIATED, UNLESS THE WARM WEATHER OR COLD WEATHER CUT-OFF CONTROLS HAVE BEEN ACTIVATED.
- D. IF THE OUTDOOR AIR TEMPERATURE IS ABOVE 40 deg F (ADJUSTABLE), THE SNOWMELT SYSTEM SHALL ENTER THE WARM WEATHER CUT-OFF MODE. IT SHALL REMAIN THERE UNTIL THE OUTDOOR AIR TEMPERATURE DROPS BELOW THE MELTING TEMPERATURE SETPOINT. THE WARM WEATHER CUT-OFF MODE SHALL DEACTIVATE THE SNOWMELT SYSTEM.
- E. THE MELTING MODE SHALL BE CAPABLE OF BEING ACTIVATED EITHER THROUGH THE SNOW/ICE SENSOR OR THROUGH A REMOTE ENABLE SIGNAL FROM THE BAS. WHEN THE MELTING MODE IS ACTIVATED, THE PUMP SHALL BE ENERGIZED AND THE HEAT RELAY SHALL CYCLE ON AND OFF, USING PULSE WIDTH MODULATION (PWM) CONTROL, TO MAINTAIN THE SLAB SURFACE AT THE MELTING TEMPERATURE SETPOINT.
- F. THE SLAB SHALL BE MAINTAINED AT AN IDLING TEMPERATURE WHEN THE SNOWMELT SYSTEM IS NOT IN THE MELTING MODE. CONTROL OPERATION IS SIMILAR TO THE MELTING MODE EXCEPT THE SLAB IS MAINTAINED AT A LOWER IDLING TEMPERATURE SETPOINT.
- G. IF A SENSOR FAULT OCCURS, A WARNING LIGHT SHALL BE ACTIVATED AT THE CONTROL PANEL.
- H. DESIRED SLAB SURFACE MELTING TEMPERATURE, SLAB SURFACE IDLING TEMPERATURE, AND COLD WEATHER CUT-OFF TEMPERATURE SETPOINTS SHALL BE ADJUSTABLE AT THE CONTROL PANEL.

THESE SPECIFICATIONS APPLY TO THE ANTLERS SNOW MELT TUBING EXPANSION. CONTRACTOR SHALL TEST GLYCOL SOLUTION FOR 40% GLYCOL MIXTURE AT THE ANTLER'S EXPANSION.

THESE SPECIFICATIONS APPLY TO THE PARCEL B SNOW MELT EXPANSION. SNOW MELT PIPING FOR THIS PROPERTY SHALL BE INSTALLED, TESTED, DRAINED AND CAPPED FOR FUTURE EXPANSION.

ISSUE	DATE
CONSTRUCTION DOCUMENTS	11/10/23

MEP JOB: 22336

DESIGNED: MAB


CHECKED: KVB

MECHANICAL SPECIFICATIONS



M4.2

* PROVIDE NEW SIEMENS BREAKER. MATCH EXISTING AIC RATING




DESIGNATION	DESCRIPTION	VOLTAGE	PH	HP	KVA	FLA (MCA)	CONDUCTORS	CONDUIT	SWITCH	CB	FUSE SIZE/TYPE	REMARKS
B-1	BOILER	120	1	-	-	9.2	2-#12; 1-#12 GND	1/2"	STO	201	-	-
P-1	PUMP	208	3	5	-	-	3-#8; 1-#8 GND	1"	6/0	40/3	40A FRN-R	-




NOTE: ALL CONDUCTORS ARE COPPER UNLESS NOTED OTHERWISE





BOILER ROOM DEMOLITION PLAN

SCALE: 1/4" = 1'-0"




BOILER ROOM EQUIPMENT PLAN

SCALE: 1/4" = 1'-0"

DRAWING NOTES

1. NEW EMERGENCY POWER OFF (EPO) SWITCH FOR BOILER SHUT DOWN. PROVIDE PROTECTIVE CASE TO PREVENT ACCIDENTAL ACTIVATION.
2. EXTEND CABLE AND CONDUIT FOR CONTROLLERS AS REQUIRED.
3. EXTEND CABLE AND CONDUIT FOR T-STAT AS REQUIRED.




KEY PLAN


SCALE: NONE

ISSUE	DATE
CONSTRUCTION DOCUMENTS	11/10/23

MEP JOB: 22336
DESIGNED: KSP
CHECKED: RCC

**ELECTRICAL -
BOILER ROOM
PLANS**






KUTUK SNOW MELT
STEAMBOAT SPRINGS, COLORADO

[illegible]

ELECTRICAL SPECIFICATIONS



E3.0

DIVISION 26 - ELECTRICAL SPECIFICATIONS

BASIC ELECTRICAL REQUIREMENTS

GENERAL

- PRIOR TO SUBMITTING BIDS, THE ELECTRICAL CONTRACTOR SHALL VISIT THE SITE TO VERIFY EXISTING ELECTRICAL EQUIPMENT CONDITIONS AND DIFFICULTIES THAT WILL AFFECT EXECUTION OF THE WORK. FIELD VERIFY QUANTITIES OF EXISTING LIGHT FIXTURES, ELECTRICAL DEVICES, COMMUNICATION DEVICES, FIRE ALARM DEVICES, AND ELECTRICAL EQUIPMENT. NOTIFY THE ARCHITECT AND ENGINEER OF ANY EXISTING CONDITIONS WHICH MODIFY THE SCOPE OF WORK AS SHOWN ON THE CONSTRUCTION DOCUMENTS. SUBMISSION OF A BID PROPOSAL WILL BE CONSTRUED AS EVIDENCE THAT SUCH AN EXAMINATION HAS BEEN MADE AND LATER CLAIMS FOR MOBILIZATION, LABOR, EQUIPMENT, AND/OR MATERIALS REQUIRED BECAUSE OF DIFFICULTIES ENCOUNTERED WILL NOT BE RECOGNIZED.
2. ELECTRICAL CONTRACTOR SHALL FULLY COORDINATE WITH OWNER REPRESENTATIVES. ALL ELECTRICAL WORK PERFORMED UNDER THIS CONTRACT SHALL CONFORM WITH LATEST EDITIONS OF THE NATIONAL ELECTRICAL CODE, UNIFORM BUILDING CODE OR INTERNATIONAL BUILDING CODE, LOCAL BUILDING AND FIRE DEPARTMENT REQUIREMENTS. PERFORM WORK IN ACCORDANCE WITH REQUIREMENTS OF OWNER REPRESENTATIVES.
3. ELECTRICAL CONTRACTOR SHALL MAINTAIN ON THE JOB AN UP TO DATE SET OF WORKING DRAWINGS, MARKED UP TO SHOW ELECTRICAL SYSTEMS AS INSTALLED. PROVIDE ARCHITECT WITH ONE SET OF REPRODUCIBLES WITH "AS BUILT" PROJECT RECORD AFTER COMPLETION OF PROJECT. INFORMATION CLEARLY INDICATED. INCLUDE DISCREPANCIES IN FEEDER SIZES, EQUIPMENT SIZES AND LOCATIONS, AND DEVICE TYPES AND LOCATIONS.
4. ELECTRICAL CONTRACTOR SHALL OBTAIN AND PAY FOR ALL LOCAL FEES, PERMITS, AND SERVICES OF INSPECTION AUTHORITIES REQUIRED BY ELECTRICAL WORK FOR THIS ELECTRICAL CONSTRUCTION.
5. REFER TO ARCHITECTURAL AND MECHANICAL EQUIPMENT DRAWINGS FOR EXACT LOCATIONS OF ELECTRICAL DEVICES AND LIGHT FIXTURES. DO NOT DEVIATE FROM THE ELECTRICAL PLANS. ADDITIONAL ELECTRICAL REQUIREMENTS ON ARCHITECTURAL PLANS, KITCHEN EQUIPMENT PLANS, AND MECHANICAL PLANS SHALL BE INCLUDED IN THE ELECTRICAL CONTRACTORS BID.
6. THE ELECTRICAL DRAWINGS ARE DIAGRAMMATIC AND INDICATE THE GENERAL ARRANGEMENT OF ELECTRICAL WORK. LOCATIONS ARE APPROXIMATE AND SHALL BE SUBJECT TO MINOR MODIFICATIONS AS DIRECTED BY THE GENERAL CONTRACTOR AND OWNER REPRESENTATIVES. ELECTRICAL CONTRACTOR SHALL BE RESPONSIBLE FOR THE EXACT FITTING OF ALL MATERIALS; EQUIPMENT, ETC. IN THE BUILDING AND TENANT SPACE. ALL DIMENSIONS SHALL BE VERIFIED ON THE JOB. ELECTRICAL CONTRACTOR SHALL CUT CHANNEL, CHASE AND/OR DRILL FLOORS, WALLS, PARTITIONS, CEILINGS, OR OTHER SURFACES AS REQUIRED FOR INSTALLATION, SUPPORT, ANCHORAGE, ETC. OF WORK. PROVIDE X-RAY OF FLOOR PRIOR TO CORE DRILLS. THE GENERAL CONTRACTOR SHALL BE RESPONSIBLE FOR THE SUBSEQUENT PATCHING WORK.
7. EXISTING EQUIPMENT IS SHOWN FOR REFERENCE PURPOSES AND SHALL REMAIN. EXISTING EQUIPMENT NOT SHOWN SHALL ALSO REMAIN. EXISTING EQUIPMENT TO REMAIN SHALL BE PROTECTED FROM DAMAGE.
8. WORK SHOWN AS EXISTING CONDITIONS WAS TAKEN FROM OWNER FURNISHED DRAWINGS AND/OR VERIFIED DURING FIELD SURVEY. MEP IS NOT RESPONSIBLE FOR THE ACCURACY OF ANY INFORMATION OR THE ADEQUACY, SAFETY AND CONFORMANCE TO CURRENT PREVAILING CODES OF ANY WORK SHOWN AS EXISTING ON THESE DOCUMENTS.
9. IT IS THE INTENT OF THESE DOCUMENTS TO RESULT IN A COMPLETE ELECTRICAL INSTALLATION IN COMPLETE ACCORDANCE WITH APPLICABLE CODES AND ORDINANCES. THE DRAWINGS ARE DIAGRAMMATIC IN CHARACTER AND DO NOT NECESSARILY INDICATE EVERY REQUIRED JUNCTION BOX, PULL BOX, FITTINGS, ETCETERA. ITEMS NOT SPECIFICALLY MENTIONED IN THE SPECIFICATION OR NOTED ON THE DRAWINGS, BUT WHICH ARE OBVIOUSLY NECESSARY TO MAKE A COMPLETE WORKING INSTALLATION, SHALL BE INCLUDED.
10. DRAWINGS AND SPECIFICATIONS ARE COMPLEMENTARY. WHATEVER IS CALLED FOR IN EITHER IS BINDING AS THOUGH CALLED FOR IN BOTH. THE MORE STRINGENT REQUIREMENTS SHALL GOVERN.
11. IF CONFLICTS ARE DISCOVERED IN CONTRACT DOCUMENTS AS WORK PROGRESSES, A SET OF PRINTS MARKED WITH RED PENCIL SHOWING RECOMMENDED MODIFICATIONS SHALL BE SUBMITTED TO THE ENGINEER FOR APPROVAL PRIOR TO INSTALLATION.
12. IN THE EVENT THAT DISCREPANCIES EXIST OR REQUIRED ITEMS OR DETAILS HAVE BEEN OMITTED, NOTIFY THE ARCHITECT IN WRITING OF SUCH DISCREPANCY OR OMISSION AT LEAST THREE DAYS PRIOR TO BID DATE. FAILURE TO DO SO SHALL BE CONSTRUED AS WILLINGNESS TO SUPPLY NECESSARY MATERIALS AND LABOR REQUIRED FOR THE PROPER COMPLETION OF THIS WORK. FOR DISCREPANCIES WHICH ARE NOT REPORTED BY CONTRACTOR THE MOST STRINGENT REQUIREMENT SHALL APPLY.
13. IN THE EVENT THAT ADDITIONAL INFORMATION IS REQUIRED DURING CONSTRUCTION, REQUEST SUCH INFORMATION FROM THE ARCHITECT IN WRITING PRIOR TO PERFORMING RELATED WORK. THE REQUEST FOR INFORMATION SHALL INCLUDE AN EXPLANATION OF THE INFORMATION REQUIRED INCLUDING REFERENCES TO RELATED PORTIONS OF THE DOCUMENTS AND CONTRACTORS RECOMMENDATIONS.
14. THE TERM "PROVIDE" SHALL MEAN FURNISH AND INSTALL ITEMS OR SYSTEMS IN ACCORDANCE WITH PLANS AND SPECIFICATIONS.
15. INSTALL EQUIPMENT AND MATERIALS IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS UNLESS LOCAL CODES OR REGULATIONS TAKE PRECEDENCE.
16. PROVIDE APPURTENANCES AND CONSUMABLES AS REQUIRED.
17. WORK SHALL CONFORM TO BASE BUILDING SPECIFICATIONS EXCEPT AS AMENDED BY THESE SPECIFICATIONS. CONTRACTOR SHALL VERIFY EXISTING CIRCUITS PRIOR TO STARTING WORK.
18. COMPLY WITH THE LATEST EDITION OF NATIONAL ELECTRICAL CODE, APPLICABLE STATE AND LOCAL CODES, ORDINANCES AND OSHA REGULATIONS.
19. WHERE A CONFLICT EXISTS BETWEEN ANY PREVAILING CODES AND WORK INDICATED ON THESE DOCUMENTS, THE MORE STRINGENT REQUIREMENT SHALL GOVERN.
20. PAY FOR ALL ELECTRICAL PERMITS, LICENSES AND CONSTRUCTION FEES.
21. EXAMINE SITE AND PREMISES PRIOR TO SUBMISSION OF BID. NO ADDITIONAL COMPENSATION WILL BE MADE FOR EXTRA EXPENSE INCURRED DUE TO FAILURE TO EXAMINE EXISTING SITE CONDITIONS.
22. DEMOLITION OR ABANDONING ANY ELECTRICAL AND COMMUNICATIONS CONDUIT, WIRING, CABLEING, OR DEVICE MEANS TO REMOVE IN ITS ENTIRETY. REMOVE UNUSED CONDUITS FROM CEILING SPACES IN AREAS OF WORK. ABANDONED OUTLET JUNCTION BOXES ARE TO BE REMOVED AND COVERED WITH NEW GYPSUM BOARD. ABANDONED POLE THRU OUTLETS SHALL HAVE COVER PLATES AND BE FILLED WITH FIRE RATED FOAM SEALANT TO MAINTAIN FIRE RATING OF FLOOR.
23. ELECTRICAL CONTRACTOR SHALL RE-USE EXISTING BRANCH CIRCUIT CONDUIT AND WIRING WHERE POSSIBLE. RE-USE EXISTING PREFABRICATED LIGHTING SYSTEM CONDUIT AND WIRING WHERE POSSIBLE. RE-ROUTE AND EXTEND AS NECESSARY FOR THIS TENANT FINISH CONSTRUCTION. PROVIDE ADDITIONAL NEW CONDUIT, WIRING, COMPONENTS, AND CONNECTIONS AS REQUIRED FOR COMPLETE AND OPERATIONAL SYSTEMS. TYPICAL.
24. SCHEDULE SERVICE INTERRUPTIONS IN WRITING WITH OWNER AND BUILDING OCCUPANTS ONE (1) WEEK IN ADVANCE.
25. COORDINATE WORK AND POWER OUTAGES WITH BUILDING MANAGEMENT, AFFECTED TENANTS, AND OTHER TRADES.
26. COORDINATE BUILDING ELECTRICAL SERVICE REVISIONS AND ADDITIONS WITH LOCAL UTILITY COMPANY.
27. EQUIPMENT REMOVED IS THE PROPERTY OF THE OWNER AND SHALL BE RETURNED TO THE OWNER FOR DISPOSITION. SALVAGE ALL REMOVED EQUIPMENT FOR OWNER AND STORE IN OWNER DESIGNATED LOCATION. EQUIPMENT NOT RETAINED BY THE OWNER SHALL BE REMOVED FROM THE SITE BY THE CONTRACTOR.
28. ALL MATERIALS SHALL BE NEW AND BEAR THE "UL" LABEL.
29. PROVIDE SUBMITTALS (ELECTRONIC PDF FORMAT) ON ALL PROPOSED MATERIALS. SUBMITTALS SHALL CLEARLY INDICATE COMPLETE MODEL NUMBERS OF MATERIALS OR EQUIPMENT PROPOSED. SUBMITTALS SHALL BE SUBMITTED WITHIN 10 DAYS OF AWARD OF CONTRACT FOR REVIEW. SUBMITTALS SHALL BE PROVIDED IN A TIMELY MANNER WITH LEAD TIMES FOR MATERIALS AND ADEQUATE TIME FOR ENGINEER REVIEW TAKEN INTO ACCOUNT. CONTRACTOR IS RESPONSIBLE FOR ANY ADDITIONAL COSTS ASSOCIATED WITH EXPEDITING MATERIAL DELIVERIES OR SUBSTITUTIONS OF MATERIALS FROM WHAT WAS SPECIFIED IN THE PLANS OR SPECIFICATIONS.
30. REMOVE ALL REFUSE AND WASTE MATERIAL FROM HAZARDOUS WASTE DAILY.
31. LEFT OVER OR REMOVED EQUIPMENT REQUIRING BUILDING DANGER SHALL BE REMOVED FROM THE SITE BY THE CONTRACTOR UPON COMPLETION OF THE CONSTRUCTION PROJECT AND DISPOSED OF PER EPA REQUIREMENTS.
32. PROVIDE TEST EQUIPMENT AND CONDUCT NECESSARY TESTING TO DETERMINE CONFORMITY WITH EQUIPMENT SPECIFICATIONS. PERFORM TESTS UNDER OBSERVATION OF OWNER'S REPRESENTATIVE. CORRECT DEFECTS AND RETEST. COMPLETE TESTS TO SATISFACTION OF OWNER'S REPRESENTATIVE.
33. PROVIDE UPDATED, COMPLETE AND ACCURATE TYPED PANELOBOARD CIRCUIT DIRECTORIES AT THE COMPLETION OF WORK. CLEARLY LABEL ALL SPACES AND SPARES IN PENCIL. CLEAN EXPOSED PANELOBOARD SURFACES AND CHECK TIGHTNESS OF ELECTRICAL CONNECTIONS. REPLACE DAMAGED CIRCUIT BREAKERS AS REQUIRED AND PROVIDE FILLER PLATES FOR VACANT SPACES.
34. PROVIDE UPDATED LABELING OF ALL NEW AND RELOCATED ELECTRICAL EQUIPMENT IN SCOPE OF WORK INCLUDING

BUT NOT LIMITED TO, ENGINE GENERATOR SYSTEMS, TRANSFER SWITCHES, TRANSFORMERS, SWITCHGEAR, SWITCHBOARDS, PANELBOARDS, MOTOR CONTROL CENTERS, AND DISCONNECTS TO INDICATE THE AMPERE RATING, VOLTAGE RATING, PHASE, CONDUCTOR COLOR CODING WITHIN THE EQUIPMENT AND APPLICABLE AIR RATING.

35. GUARANTEE ELECTRICAL INSTALLATION AND ALL WORK UNDER THIS DIVISION (EXCLUDING LAMPS) FOR A PERIOD OF TWO YEARS FROM DATE OF FINAL ACCEPTANCE BY OWNER AGAINST ALL EVIDENCE OF IMPERFECT WORKMANSHIP, FAILURE OR MALFUNCTION OF MATERIALS AND EQUIPMENT. REPLACE WORK FOUND DEFECTIVE WITHIN THIS PERIOD PROMPTLY AT NO COST TO OWNER.

36. GUARANTEE ELECTRICAL INSTALLATION AND ALL WORK UNDER THIS DIVISION (EXCLUDING LAMPS) FOR A PERIOD OF TWO YEARS FROM DATE OF FINAL ACCEPTANCE BY OWNER AGAINST ALL EVIDENCE OF IMPERFECT WORKMANSHIP, FAILURE OR MALFUNCTION OF MATERIALS AND EQUIPMENT. REPLACE WORK FOUND DEFECTIVE WITHIN THIS PERIOD PROMPTLY AT NO COST TO OWNER.

MATERIALS AND EQUIPMENT

3. WIRE AND CABLE SHALL BE MINIMUM NUMBER 12 AWG COPPER WITH THWN OR THHN INSULATION. NUMBER 10 AWG AND SMALLER WIRE EXCEPT FOR MOTOR CIRCUITS SHALL BE SOLID. LARGER WIRE AND MOTOR CIRCUIT FEEDERS SHALL BE STRANDED. MOTOR CONNECTIONS SHALL BE WITH STRANDED CONDUCTORS. WIRE AND CABLE SHALL BE AS MANUFACTURED BY SOUTHWIRE, OR APPROVED EQUIVALENT.
4. ALL CONDUCTORS SHALL BE THIRTYTHREE INSULATED COPPER UNLESS OTHERWISE NOTED ON THE DRAWINGS. #12 AWG FOR 120 VOLT, 20 AMPERE CIRCUITS, 15 FEET OR LESS; #12 AWG FOR 277 VOLT, 20 AMPERE CIRCUITS, 150 FEET OR LESS TO FIRST DEVICE; TYPE THHN, OR THWN INSULATION. PROVIDE WIRE COLOR CODING AS REQUIRED BY THE NATIONAL ELECTRICAL CODE. ALL WIRING SHALL BE RUN CONCEALED AND IN EMT CONDUIT. ALL HOMERUNS SHALL BE IN EMT CONDUIT. ALL EMPTY CONDUITS INDICATED ON THE DRAWINGS SHALL BE SUPPLIED WITH NYLON PULL LINES.
5. ALL ELECTRICAL WIRING SHALL BE INSTALLED IN CONDUIT. WRITTEN APPROVAL FROM DESIGN ENGINEER AND PROPERTY MANAGEMENT FOR THE USE OF "MC" AND "AC" TYPE CABLE/JUNCTION. IF APPROVED, "MC" AND "AC" TYPE CABLE SHALL BE PERMITTED FOR USE IN CONDUIT. WIRING FROM JUNCTION BOXES TO DEVICES ONLY. ALL HOME RUNS SHALL BE RUN IN CONDUIT. "MC" AND "AC" CABLE/JUNCTION SHALL BE INSTALLED PER NATIONAL ELECTRICAL CODE AND LOCAL BUILDING DEPARTMENT REQUIREMENTS. USE APPROVED TYPE COUPLINGS AND CONNECTORS. PROVIDE CONDUIT SUPPORTS AS REQUIRED BY THE NATIONAL ELECTRICAL CODE AS A MINIMUM. PER-MANUFACTURED CABLE ASSEMBLIES SHALL NOT BE PERMITTED.
6. INTERIOR CONDUIT SHALL BE ELECTRICAL METALLIC TUBING WITH SET SCREW FITTINGS.
7. EXTERIOR CONDUIT SHALL BE RIGID METAL CONDUIT, GALVANIZED, WITH THREADED FITTINGS.
8. CONDUIT IN AREAS SUBJECT TO MECHANICAL INJURY SHALL BE RIGID METAL CONDUIT, GALVANIZED, WITH THREADED FITTINGS.
9. CONDUIT SUBJECT TO VIBRATION OR WHERE USED FOR MECHANICAL EQUIPMENT CONNECTIONS SHALL BE PVC JACKETED FLEXIBLE METAL CONDUIT.
10. OUTLET AND JUNCTION BOXES SHALL BE OF PRESSED STEEL, AND AS MANUFACTURED BY STEEL CITY, APPLETON, OR RACO. OUTLET BOXES SHALL BE DOUBLE GANG BOX WITH SINGLE OR DOUBLE GANG TRIM RINGS AS REQUIRED.
11. WIRING DEVICES SHALL BE SPECIFICATION GRADE, 20 AMP FOR GENERAL APPLICATION, 20 AMP OR GREATER FOR DEDICATED CIRCUITS AND AS REQUIRED BY CIRCUIT LOAD. LEVITON #530 RECEPTACLES, 530G3 (GRANGE) ISOLATED GROUND RECEPTACLES, AND #1221 (SWITCHES) (OR EQUAL) CLOUT TO MATCH EXISTING BUILDING STANDARD OR PROVIDE (WHITE) UNLESS OTHERWISE NOTED.
12. FIRE RESISTIVE WALLS AND OPENINGS MAY HAVE OPENINGS FOR STEEL ELECTRICAL OUTLET BOXES NOT EXCEEDING 16 SQUARE INCHES IN AREA, PROVIDED THE AGGREGATE AREA OF SUCH OPENINGS IS NOT MORE THAN 100 SQUARE INCHES FOR ANY 100 SQUARE FEET OF WALL. TYPICAL.
13. ALL 15 AMPERE AND 20 AMPERE, 125 VOLT AND 250 VOLT NON-LOCKING RECEPTACLES INSTALLED IN DAMP OR WET LOCATIONS SHALL BE LISTED AS WEATHER-RESISTANT PER 2011 NEC, ARTICLE 406.9 (A) AND (B). ALL RECEPTACLES MOUNTED IN WET LOCATIONS AS REFERENCED ABOVE SHALL HAVE AN "IN USE" WEATHERPROOF COVER.
14. ALL 125 VOLT, SINGLE PHASE, 15 AND 20 AMPERE RECEPTACLES SHALL HAVE GFCI PROTECTION FOR PERSONNEL IN THE FOLLOWING AREAS: BATHROOMS, KITCHENS (AREAS WITH A SINK AND PERMANENT FIXTURES FOR FOOD PREPARATION AND COOKING), ROOFTOPS, OUTDOORS AND WITHIN 6 FEET FROM THE OUTSIDE EDGE OF SINKS.
15. EQUIPMENT SHALL BE GROUNDED IN ACCORDANCE WITH NATIONAL ELECTRICAL CODE. A SEPARATE EQUIPMENT GROUNDING CONDUIT SHALL BE INSTALLED WITH ALL FEEDER AND BRANCH CIRCUITS CONDUCTORS. GROUND WIRES SHALL BE COPPER.
16. FUSES SHALL BE AS INDICATED AND AS MANUFACTURED BY COOPER-BUSSMANN.
17. CIRCUIT BREAKERS SHALL BE THERMAL-MAGNETIC, QUICK-MAKE, QUICK-BREAK, TRIP-FREE AND TRIP INDICATING. MULTI-POLE CIRCUIT BREAKERS SHALL BE EQUIPPED WITH AN INTERNAL COMMON TRIP MECHANISM. CIRCUIT BREAKERS SHALL BE OF SAME MANUFACTURER AS PANELBOARD OR DISCONNECTING DEVICE.
18. MOTOR AND CIRCUIT DISCONNECTS SHALL BE HEAVY DUTY, FUSIBLE OR NON-FUSIBLE AS INDICATED.

EXECUTION

1. ELECTRICAL CONTRACTOR SHALL USE #10 AWG CU WIRE WHEN LENGTH OF CONDUCTOR EXCEEDS 75 FEET FOR 120 VOLT, 20 AMP CIRCUITS AND 150 FEET FOR 277 VOLT, 20 AMP CIRCUITS. SIZE CONDUCTORS FOR MINIMUM VOLTAGE DROP ALLOWED PER THE NATIONAL ELECTRICAL CODE.
2. ELECTRICAL CONTRACTOR SHALL USE #8 AWG CU WIRE WHEN LENGTH OF CONDUCTOR EXCEEDS 150 FEET FOR 120 VOLT, 20 AMP CIRCUITS AND 300 FEET FOR 277 VOLT, 20 AMP CIRCUITS. SIZE CONDUCTORS FOR MINIMUM VOLTAGE DROP ALLOWED PER THE NATIONAL ELECTRICAL CODE.
3. NEUTRALS, RACEWAYS, AND NON-CURRENT CARRYING PARTS OF ELECTRICAL EQUIPMENT AND ASSOCIATED ENCLOSURES SHALL BE GROUNDED IN FULL ACCORDANCE WITH THE NATIONAL ELECTRICAL CODE. PROVIDE HARD WIRED GROUND CONNECTIONS TO ALL DEVICES AND SEPARATE INSULATED GROUND WIRE CONTINUOUS IN EACH CIRCUIT (#12 AWG CU MINIMUM GREEN TRACER GROUND).
4. ALL FLOOR AND WALL PENETRATIONS WHERE ELECTRICAL DEVICES AND RACEWAY HAVE BEEN REMOVED MUST BE REPAIR AND SEALED TO MAINTAIN THE REQUIRED FIRE RATING. CONDUITS PENETRATING FLOOR OR WALLS OR CEILINGS SHALL BE FIRE STOPPED WITH A U.L. LISTED FIRE STOPPING COMPOUND SEALANT TO MAINTAIN THE REQUIRED FIRE RATING. FIRE RATED FLOOR AND WALL PENETRATIONS IMMEDIATELY.
5. ELECTRICAL CONTRACTOR SHALL PROVIDE PRODUCT LITERATURE INFORMATION ON SITE FOR FIELD INSPECTOR REGARDING FIRE RATING OF FLOOR BOXES AND POKE THRU DEVICES.
6. ALL CONDUITS PENETRATING A ONE HOUR FIRE RATED WALL OR CEILING SHALL BE FIRE STOPPED WITH A U.L. LISTED FIRE STOPPING COMPOUND SEALANT.
7. ELECTRICAL CONTRACTOR SHALL COORDINATE EXACT LOCATIONS OF LIGHTING FIXTURES IN MECHANICAL ROOMSPACES WITH MECHANICAL DUCT WORK INSTALLER PRIOR TO ROUGH IN. LOCATE BELOW DUCT WORK (8'-0" A.F.F. MIN) ENTERED IN THE AS BUILT AS FAR AS POSSIBLE. ELECTRICAL CONTRACTOR SHALL FIELD VERIFY ALL MECHANICAL EQUIPMENT LOCATIONS AND REQUIREMENTS WITH MECHANICAL PLANS, MECHANICAL CONTRACTOR, AND ACTUAL MECHANICAL EQUIPMENT SUPPLIED. INCLUDE ALL REQUIRED OUTLETS; HEAVY DUTY DISCONNECT SWITCHES, FUSES, CONTROLS, CONTROL WIRING AND ALL CONNECTIONS IN THE ELECTRICAL BID.
8. COORDINATE ALL INTERRELATIONS TO AND BETWEEN NEW AND EXISTING SYSTEMS INCLUDING, BUT NOT LIMITED TO: POWER, LIGHTING, FIRE ALARM AND DETECTION, TELEPHONE AND INTERCOM.
9. COORDINATE LOCATIONS OF DEVICES WITH ARCHITECT PRIOR TO ROUGH-IN.
10. COORDINATE WITH MECHANICAL CONTRACTOR FOR LOCATIONS OF EQUIPMENT CONNECTIONS PRIOR TO ROUGH-IN.
11. ALL NEW LIGHT SWITCHES, RECEPTACLE OUTLETS, TELEPHONE OUTLETS, FIRE ALARM DEVICES, AND COMMUNICATION DATA OUTLETS SHALL MEET THE REQUIREMENTS FOR AMERICANS WITH DISABILITIES (A.D.A.) AND ANSI A117.1 REQUIREMENTS FOR MOUNTING HEIGHTS AND ORIENTATIONS. TYPES, UNLESS OTHERWISE NOTED, ALL RECEPTACLES SHALL BE A MINIMUM OF 15" A.F.F. AT BOTTOM OF DEVICE AND SWITCHES A MAXIMUM OF 48" A.F.F. AT TOP OF DEVICE, TYPES UNLESS OTHERWISE NOTED.
12. COORDINATE LOCATIONS OF MECHANICAL EQUIPMENT CONTROL PANELS WITH DIVISION 23. CIRCUITS FOR CONTROL PANEL POWER IS INDICATED ON PANELBOARD SCHEDULES.
13. REMOVE CONDUCTORS AND CONDUIT BACK TO SOURCE FOR EQUIPMENT WHICH IS TO BE REMOVED UNLESS EXISTING WIRING AND CONDUIT CAN BE REMOVED TO ACCESSIBLE JUNCTION BOX AT CONTRACTORS OPTION TO FEED NEW EQUIPMENT. MAINTAIN CIRCUIT CONTINUITY OF REMAINING DEVICES AND EQUIPMENT. CONTRACTOR IS TO PHASE WORK TO MAINTAIN CONTINUITY OF CIRCUITS IN AREAS WHICH ARE IN ANOTHER PHASE.
14. EXTEND EXISTING CIRCUITRY TO RECONNECT TO RELOCATED ITEMS AS INDICATED OR UNLESS OTHERWISE NOTED.
15. PROVIDE BLANK COVER PLATES ON WALLS TO REMAIN FOR REMOVED OR RELOCATED DEVICES. COVER PLATES SHALL MATCH EXISTING.

IFGC PIPE SIZING CALCULATOR FOR NATURAL GAS PRESSURES LESS THAN 15 PSI		
METER DISCHARGE PRESSURE = 14 ("W.C.) ALLOWABLE PRESSURE DROP = 7 ("W.C.) TOTAL EQUIVALENT LENGTH OF PIPE = 75 FEET ALTITUDE CORRECTION FACTOR = 831 BTU/CFH @ ALT.		
NOMINAL SCHD. 40 STEEL PIPE SIZE	CAPACITY (CFH)	CAPACITY (MBH)
1/2"	241	201
3/4"	504	420
1"	950	790
1-1/4"	1951	1622
1-1/2"	2923	2430
2"	5630	4679
2-1/2"	8973	7457
3"	15862	13182
4"	32353	26886
5"	58532	48640
6"	94776	78759
PIPE CAPACITY IS CALCULATED USING FORMULA FOR LOW PRESSURE GAS (1.5 PSI AND LESS) LOCATED IN IFGC APPENDIX A Q = 2310 $\sqrt{2.622(P)(W)(C)/L}$ IF 541 Q = CAPACITY (CFH) D = INSIDE PIPE DIAMETER H = ALLOWABLE PRESSURE DROP ("W.C.) Cr = FACTOR FOR VISCOSITY, DENSITY AND TEMPERATURE = .6064 L = LENGTH OF PIPE (FEET)		

SNOWMELT BOILER SCHEDULE																		
SYMBOL	SERVICE	MANUFACTURER	MODEL	HEATING CAPACITY					GPM	ELECTRICAL				FLUE SIZE IN	COMB. AIR SIZE IN	UNIT WEIGHT (LBS.)	REMARKS	
				INPUT @ S/L MBH	OUTPUT @ S/L MBH	OUTPUT @ 670F MBH	EWT (°F)	LWT (°F)		VOLTAGE	PHASE	FLA	MCA					MOCp
EXISTING TO REMAIN, NOTED FOR REFERENCE ONLY																		
(E)B-1	SNOWMELT	AERCO	BMK 1500	1500	1410	1190	120	140	119	120	1	9.2	11.5	20	14	8	X	4
NEW BOILER																		
B-2	SNOWMELT	AERCO	BMK 1500	1500	1410	1190	120	140	119	120	1	9.2	11.5	20	14	8	X	1,2,3,5
REMARKS: 1. ACCEPTABLE MANUFACTURERS: LAARS, LOCHINVAR. 2. BURNER SHALL BE DESIGNED TO FIRE ON NATURAL GAS, 720 BTU/CF, 7" WC. 3. PROVIDE INDIVIDUAL FACTORY MOUNTED BOILER CONTROL PANEL WITH (BUILDING STANDARD) CONTROLS TO COMMUNICATE WITH BUILDING AUTOMATION SYSTEM. COORDINATE WITH CONTROLS CONTRACTOR. 4. EXISTING BOILER TO REMAIN, SHOWN FOR REFERENCE ONLY. FIELD VERIFY. 5. 50% GLYCOL.																		

IN-LINE PUMP SCHEDULE															
SYMBOL	MANUFACTURER	SERVICE	PUMP TYPE	MODEL	GPM	HEAD FT WC	EFF %	MIN HP	RPM	ELECTRICAL		SUCTION SIZE IN	DISCH SIZE IN	APPROX OPERATING WEIGHT	REMARKS
										VOLTS	PHASE				
EXISTING TO REMAIN, NOTED FOR REFERENCE ONLY															
(E)P-1	ARMSTRONG	SNOW-MELT	INLINE	4300	101	115	74	10	3600	208	3	3	3	100	3
NEW PUMP															
P-2	ARMSTRONG	SNOW-MELT	INLINE	4300	101	115	74	10	3600	208	3	3	3	100	1,2
REMARKS: 1. ACCEPTABLE MANUFACTURERS: BELL AND GOSSETT, TACO. 2. PUMP SELECTION BASED ON 50% ETHYLENE GLYCOL. 3. EXISTING PUMP TO REMAIN, SHOWN FOR REFERENCE ONLY.															

SNOWMELT SYSTEM SUMMARY														
LOCATION	PROJECT NAME	ZONE	PROJECT ELEVATION (FT.)	SNOWMELT DESIGN TEMPERATURE (°F)	SNOWMELT DESIGN WIND SPEED (MPH)	TOTAL AREA PH 1 (SQ. FT.)	BTUH PER AREA SQ. FT.	TOTAL LOAD (BTUH)	TOTAL GPM @ 25 DEG DELTA T	SNOWMELT GLYCOL LEVEL (%)	SNOWMELT FLUID TEMP. DROP (°F)	TOTAL FLUID VOLUME (GAL.)	GLYCOL VOLUME (GAL.)	REMARKS
STEAMBOAT COLORADO	TORIAN PLUM APARTMENTS	EXISTING #1	6,700	0	10	10,776	140	1,508,000	101	50	25	108	44	1
		NEW #2	6,700	0	10	7,230	140	1,012,000	81	50	25	100	40	2
NEW BOILER SELECTION CALCULATIONS:														
TOTAL SNOW-MELT LOAD			1,012,000 BTUH / (0.94 * 0.72)			= 1,500,000 BTUH INPUT @ S.L. REQUIRED			SELECTED BOILER AT 1,500,000 INPUT BTUH TOTAL					
			0.94 BOILER EFFICIENCY											
			0.72 ALTITUDE ADJUSTMENT											
REMARKS:														
1. EXISTING SNOW MELT ZONE.														
2. EXISTING SNOW MELT ZONE INSTALLED, ACTIVATED UNDER THIS PROJECT.														

TOTAL CONNECTED GAS LOAD SCHEDULE					
EQUIPMENT	QTY	INPUT EACH (BTUH @ SL)	INPUT TOTAL (BTUH @ SL)	INLET PRESSURE	NOTES
EXISTING EQUIPMENT					
EXISTING BOILER B-1	1	1,500,000	1,500,000	7" WC	EXISTING TO REMAIN
TOTAL GAS LOAD REMAINING			1,500,000		
NEW EQUIPMENT					
NEW BOILER B-2	1	1,500,000	1,500,000	7" WC	1, 2, 3
TOTAL NEW LOAD=			1,500,000		
TOTAL EXISTING LOAD TO REMAIN=			1,500,000		
BUILDING TOTAL CONNECTED LOAD=			3,000,000		NEW AND EXISTING
NOTES: 1. MODIFICATIONS TO GAS METER AND/OR SERVICE PIPING SHALL BE PERFORMED BY THE GAS COMPANY. SUBMIT REQUIRED GAS SERVICE APPLICATION TO GAS COMPANY IN A TIMELY MANNER TO MEET THE CONSTRUCTION SCHEDULE. 2. FARTHEST CONNECTED DEVICE DISTANCE BASED ON 75'. 3. PIPE SIZING BASED ON PRESSURE AT METER OUTLET OF 14 INCHES WC. CONTRACTOR TO FIELD VERIFY OUTLET PRESSURE PRIOR TO STARTING WORK.					

MECHANICAL LEGEND					
NOT ALL ITEMS LISTED BELOW ARE USED ON THIS SET OF MECHANICAL DRAWINGS					
GENERAL					
SYMBOL	DESCRIPTION				
	REFERENCE BUBBLE				
	MECHANICAL/ELECTRICAL EQUIPMENT DESIGNATION				
	REMOVE EXISTING UNDERCUT DOOR				
	AIR FLOW				
	CONNECT NEW TO EXISTING				
DOUBLE LINE DUCTWORK					
SYMBOL	DESCRIPTION				
	RECTANGULAR SUPPLY AIR DUCT UP				
	RECTANGULAR SUPPLY AIR DUCT DOWN				
	RECTANGULAR RETURN AIR / EXHAUST DUCT UP				
	RECTANGULAR RETURN AIR / EXHAUST DUCT DOWN				
	ROUND DUCT UP				
	ROUND DUCT DOWN				
	BRANCH DUCT 45° TAKE-OFF				
	RECTANGULAR DUCT ELBOW WITH TURNING VANES				
	RADIUS ELBOW RECTANGULAR/ROUND DUCT				
	DUCT TRANSITION				
	FLEX CONNECTION				
SINGLE LINE DUCTWORK					
SYMBOL	DESCRIPTION				
	RECTANGULAR DUCT ELBOW WITH TURNING VANES				
	RADIUS ELBOW RECTANGULAR/ROUND DUCT				
	DUCT TRANSITION				
	CONICAL SPIN-IN FITTING				
	CONICAL SPIN-IN FITTING W/DAMPER				
	FLEXIBLE DUCT				
CONTROL DEVICES AND DAMPERS					
SYMBOL	DESCRIPTION				
	HUMIDISTAT				
	PRESSURE SENSOR				
	SENSOR				
	WALL MOUNTED THERMOSTAT				
	UNIT MOUNTED THERMOSTAT				
	SWITCH				
	FIRE DAMPER				
	RADIATION DAMPER				
	SMOKE DAMPER				
	COMBINATION FIRE AND SMOKE DAMPER				
	MANUAL VOLUME DAMPER W/LOCKING QUADRANT				
	MOTORIZED DAMPER				
PIPING					
SYMBOL	ABBV. DESCRIPTION				
	HS HOT WATER SUPPLY				
	HR HOT WATER RETURN				
	CWS CHILLED WATER SUPPLY				
	CWR CHILLED WATER RETURN				
	CS CONDENSER SUPPLY				
	CR CONDENSER RETURN				
	HPS HIGH PRESSURE STEAM				
	HPC HIGH PRESSURE CONDENSATE				
	PC PUMPED CONDENSATE				
	D EQUIPMENT DRAIN				
	RL REFRIGERANT LIQUID				
	RS REFRIGERANT SUCTION				
PIPING SYMBOLS					
SYMBOL	DESCRIPTION				
	ARROW IN LINE INDICATES DIRECTION OF FLOW				
	INDICATES PIPE SLOPE DOWN				
	BOTTOM PIPE CONNECTION				
	PIPING UP				
	PIPING DOWN				
	FIXTURE TRAP OR DRAIN TRAP				
	PIPING CAP OR PLUG				
	PUMP				
	BALANCING VALVE/ FLOW MEASURING DEVICE				
	CALIBRATED BALANCING VALVE				
	BALL VALVE				
	PLUG VALVE				
	GATE VALVE				
	CHECK VALVE				
	BUTTERFLY VALVE				
	FLOW SWITCH				
	SOLENOID VALVE				
	PRESSURE REDUCING VALVE				
	3-WAY TEMPERATURE CONTROL VALVE				
	2-WAY TEMPERATURE CONTROL VALVE				
	RELIEF VALVE				
	STRAINER				
	STRAINER WITH BLOW-OFF VALVE				
	UNION				
	PRESSURE GAUGE				
	THERMOMETER				
	PRESSURE AND TEMPERATURE TAP				
	CONCENTRIC REDUCER				
	ECCENTRIC REDUCER				
	FLEXIBLE CONNECTOR				
	HOSE END DRAIN VALVE				
	MANUAL AIR VENT				
ABBREVIATIONS					
AFF	ABOVE FINISHED FLOOR	MC	MECHANICAL CONTRACTOR	RA	RETURN AIR
AP	ACCESS PANEL	(N)	NEW	RE	REFER TO
C	COMMON	NC	NORMALLY CLOSED	SA	SUPPLY AIR
(E)	EXISTING	NC	NOT IN CONTRACT	SRV	SAFETY RELIEF VALVE
EC	ELECTRICAL CONTRACTOR	NO	NORMALLY OPEN	TCC	TEMPERATURE CONTROL CONTRACTOR
ELEV	ELEVATION	NTS	NOT TO SCALE		TYPICAL
EQ	EQUIPMENT	OA	OUTSIDE AIR		
GC	GENERAL CONTRACTOR	PRV	PRESSURE REDUCING VALVE		
NOTE:					
APPLICABLE CODE STANDARDS					
2018 INTERNATIONAL BUILDING CODE		2018 INTERNATIONAL MECHANICAL CODE		2018 INTERNATIONAL ENERGY CONSERVATION CODE	
2018 INTERNATIONAL FIRE CODE		2018 INTERNATIONAL PLUMBING CODE		2018 INTERNATIONAL FUEL GAS CODE	

GENERAL NOTES:

CONTRACTOR SHALL DESIGN THE SNOW MELT SYSTEM ZONES BASED ON UPONOR, OR EQUAL. CONTRACTOR SHALL SUBMIT SHOP DRAWINGS OF THE SNOW MELT ZONES FROM MANUFACTURER. SEE CIVIL PLANS FOR SNOW MELT ZONE LOCATIONS AND ADDITIONAL INFORMATION.



TORIAN PLUM SNOW MELT UPGRADES
STEAMBOAT SPRINGS, COLORADO




ISSUE DATE
CONSTRUCTION 11/10/23
DOCUMENTS


MECHANICAL
EQUIPMENT
SCHEDULES

MEP JOB: 22336
DESIGNED: MAB
CHECKED: KVB




M1.0





BOILER ROOM MECHANICAL DEMOLITION PLAN

SCALE: 1/4" = 1'-0"



BOILER ROOM MECHANICAL PLAN

SCALE: 1/4" = 1'-0"

DEMOLITION DRAWING NOTES

- EXISTING SNOW MELT GAS FIRED BOILER TO REMAIN. NO CHANGE.
- REMOVE EXISTING DAMAGED 8" SNOW MELT BOILER INTAKE FROM EXTERIOR WALL PENETRATION BACK TO BOILER CONNECTION. FIELD VERIFY.
- EXISTING BOILER FLUE DUCT UP THRU ROOF AND BACK TO BOILER TO REMAIN.
- EXISTING PUMP P-1 TO REMAIN. NO CHANGE.
- EXISTING HOT WATER SUPPLY AND RETURN PIPING TO SNOW MELT MANIFOLDS. FIELD VERIFY.
- EXISTING SNOW MELT SYSTEM MANIFOLD.
- EXISTING HOT WATER SUPPLY AND RETURN PIPING TO EXTERIOR SNOW MELT SYSTEM MANIFOLDS. FIELD VERIFY.
- EXISTING GLYCOL FEEDER ASSEMBLY TO REMAIN. NO CHANGE.
- EXISTING EXPANSION TANK TO REMAIN. NO CHANGE.
- EXISTING ELECTRIC BASEBOARD HEATER TO REMAIN.
- EXISTING GAS PIPING SERVING POOL/SPA EQUIPMENT TO REMAIN. FIELD VERIFY.
- EXISTING AIR SEPARATOR TO REMAIN.
- EXISTING POOL/SPA GAS FIRED HEATING EQUIPMENT TO REMAIN. FIELD VERIFY.
- EXISTING GAS METER. FIELD VERIFY.

DRAWING NOTES

- TERMINATE 8" COMBUSTION INTAKE PIPE THROUGH WALL WITH HOODED INTAKE CAP. CAP SHALL BE PROVIDED WITH BIRD SCREEN. TERMINATION SHALL BE 8 FT. ABOVE GRADE.
- TERMINATE 8" FLUE DUCTS WITH UL LISTED AND APPROVED VERTICAL VENT. TERMINATION, VENT PIPE SHALL BE AL29-4C POLYPRO MATERIAL. INSTALL PER MANUFACTURERS INSTALLATION INSTRUCTIONS. TERMINATION SHALL BE LOCATED AT LEAST 8 FT. FROM ADJACENT VERTICAL WALL.
- CONDENSATE DRAINS FROM BOILER SHALL BE ROUTED TO AN ACID NEUTRALIZING TANK BEFORE ENTERING THE PUBLIC SANITARY SEWER SYSTEM. ALL MATERIALS FROM BOILER TO NEUTRALIZATION TANK SHALL BE ACID RESISTANT. INSTALLING CONTRACTOR SHALL COORDINATE THE FINAL LOCATION OF ACID NEUTRALIZATION TANK WITH EQUIPMENT LAYOUT.
- PROVIDE EPO SWITCH FOR BOILER SHUT OFF COORDINATED WITH ELECTRICAL.
- EXTEND EXISTING CONCRETE PAD FOR NEW PUMP. MATCH EXISTING CONCRETE PAD.

TORIAN PLUM SNOW MELT UPGRADES
STEAMBOAT SPRINGS, COLORADO

ISSUE	DATE
CONSTRUCTION DOCUMENTS	11/10/23

MEP JOB: 22336
DESIGNED: MAB
CHECKED: KVB

MECHANICAL ROOM PLANS



M2.0

HYDRONIC SPECIALTIES

PART 1: GENERAL

1.01 WORK INCLUDED

- A. AIR VENT.

B. EXPANSION TANK.

C. AIR SEPARATOR.

D. RELIEF VALVE.

E. END SUCTION DIFFUSER.

F. PRESSURE REDUCING VALVE.

G. FLOW SWITCH.

1.02 SUBMITTALS

1. FURNISH MANUFACTURER'S SUBMITTAL DATA FOR:
1. AIR VENT.

2. EXPANSION TANK.

3. AIR SEPARATOR.

4. RELIEF VALVE.

5. PUMP INLET FLOW STRAIGHTENING FITTING.

6. PRESSURE REDUCING VALVE.

7. FLOW SWITCH.

PART 2: PRODUCTS

2.01 ACCEPTABLE MANUFACTURERS

- A. EXPANSION TANK

1. ARMSTRONG

2. AMTROL

3. BELL & GOSSETT

4. TACO

B. AIR SEPARATOR

1. AMTROL

2. ARMSTRONG

3. BELL & GOSSETT

4. TACO ACT

C. RELIEF VALVE

1. BELL & GOSSETT

2. MCCONNELL & MILLER, INC.

3. WATTS REGULATOR CO.

D. END SUCTION DIFFUSER

1. AMTROL

2. ARMSTRONG

3. BELL & GOSSETT

4. TACO

H. PRESSURE REDUCING VALVE

1. ARMSTRONG

2. BELL & GOSSETT

3. TACO

6. WATTS REGULATOR CO.

2.02 MANUAL AIR VENT

- A. COIN OR KEY OPERATED TYPE SIMILAR TO BELL & GOSSETT #4V.

2.03 AUTOMATIC AIR VENT

- A. FLOAT ACTUATED, CAST IRON BODY. POSITIVE SHUT-OFF AGAINST NEGATIVE PRESSURE. SUITABLE FOR MAXIMUM OPERATING PRESSURE OF 150 PSIG AND MAXIMUM OPERATING TEMPERATURE OF 250 F, SIMILAR TO BELL & GOSSETT MODEL 107A.

2.04 EXPANSION TANK

- A. CLOSED TYPE, WELDED STEEL RATED FOR WORKING PRESSURE OF 125 PSIG, CLEANED, PRIME COATED, SUPPLIED WITH STEEL SUPPORT SADDLES, TAPPINGS FOR INSTALLATION OF ACCESSORIES, GAUGE GLASS SET CONSISTING OF BRASS COMPRESSION STOPS AND GUARD.

2.05 AIR SEPARATOR

- A. TANGENTIAL AIR SEPARATOR: CAST IRON OR STEEL TANK, REMOVABLE GALVANIZED STEEL STRAINER, PERFORATED STAINLESS STEEL AIR COLLECTOR TUBE, ASME RATED FOR 125 PSIG WORKING PRESSURE.

2.06 END SUCTION DIFFUSER

- A. ANGLE TYPE CAST IRON BODY AND COVER WITH SUITABLE NPT, FLANGED, OR GROOVED PIPE CONNECTIONS, STRAIGHTENING VANES, ORIFICE CYLINDER, 16 MESH BRONZE START-UP STRAINER, AND EPDM O-RING SEALS. SUITABLE FOR 175 PSIG WORKING PRESSURE AND 300 F OPERATING TEMPERATURE. PROVIDE EXTRA SET OF O-RING SEALS FOR START-UP STRAINER REMOVAL.

2.07 PRESSURE REDUCING VALVE

- A. ALL BRONZE, SPRING AND DIAPHRAGM, MANUAL ADJUSTMENT FOR OUTLET WATER PRESSURE, INTEGRAL STRAINER, FEMALE THREAD CONNECTIONS, SIMILAR TO BELL & GOSSETT MODEL #12.

2.08 FLOW SWITCH

- A. SIMILAR TO MCCONNELL_MILLER NO. FS4_3.

PART 3: EXECUTION

3.01 AIR VENT

- A. PROVIDE 1/4" VALVES AT THE HIGH POINTS OF ALL MAINS AND RISERS FOR SYSTEM VENTING. PROVIDE 1/4" OVERFLOW TO NEAREST DRAIN.
- B. PROVIDE VENT TUBING TO NEAREST DRAIN FOR AUTOMATIC AIR VENTS AND AIR VENTS IN CONCEALED LOCATIONS.


3.02 END SUCTION DIFFUSER

- A. SUPPORT FITTINGS WITH FLOOR MOUNTED PIPE AND FLANGE SUPPORTS. REMOVE START-UP STRAINER AFTER 30 DAYS OPERATION.

3.03 FLOW SWITCH

- A. INSTALL IN HORIZONTAL SECTION OF PIPING.

MECHANICAL SPECIFICATIONS



DIVISION 230000 - MECHANICAL SNOW MELT SPECIFICATIONS

SNOW MELT SYSTEM REQUIREMENTS

- 1.01 WORK INCLUDED
- A. ALL LABOR, MATERIALS, TRANSPORTATION, EQUIPMENT, AND SERVICES TO INSTALL A HYDRONIC SNOW MELTING SYSTEM.
- 1.02 SUBMITTALS
- A. MANUFACTURER'S SUBMITTAL DATA SHALL CONSIST OF SHOP DRAWINGS, AND/OR DESCRIPTIONS OF MATERIALS, DETAILS OF INSTALLATION, CAPACITY RATINGS, AND CONTROL SEQUENCING.
- 1.03 SINGLE SOURCE RESPONSIBILITY
- A. COMPONENTS OF THE BURIED TUBING SYSTEM SHALL BE PROVIDED BY ONE MANUFACTURER, INCLUDING TUBE, FITTINGS, MANIFOLDS, CONTROLS, AND OTHER ANCILLARY ITEMS REQUIRED FOR A COMPLETE INSTALLATION.
- B. BOILERS, PUMP, EXPANSION TANK AIR SEPARATOR, ETC., SHALL BE APPROVED BY SYSTEM MANUFACTURER.
- 1.04 MANUFACTURER'S WARRANTY
- A. TUBE SHALL CARRY A TWENTY-FIVE (25) YEAR NON-PRORATED WARRANTY AGAINST FAILURE DUE TO DEFECT IN MATERIAL AND WORKMANSHIP OR EXPOSURE TO STRESS CRACKING AGENTS. MANIFOLDS AND OTHER ANCILLARY COMPONENTS SHALL BE WARRANTED FOR 24 MONTHS FROM DATE OF OWNER ACCEPTANCE OF PROJECT.
- 1.05 SCOPE OF WORK
- A. THE SNOWMELT SYSTEM CONTROL PANEL, OUTDOOR SENSOR, AND SNOWICE SENSOR SHALL BE FURNISHED BY THE SNOWMELT SYSTEM MANUFACTURER. THE BAS CONTRACTOR SHALL INSTALL THE COMPLETE SNOWMELT CONTROL SYSTEM AND SHALL FURNISH ALL CONTROL DEVICES, VALVES, WIRING, AND TUBING NOT FURNISHED BY THE SNOWMELT SYSTEM MANUFACTURER.

SNOW MELT SYSTEM PRODUCTS

- 2.01 TUBE
- A. TUBE SHALL BE CROSS-LINKED POLYETHYLENE, WITH MAXIMUM WORKING PRESSURE/TEMPERATURE OF 160 PSI AT 73.4 F, 100 PSI AT 180 F, 80 PSI AT 200 F.
- B. THE TUBE SHALL BE MANUFACTURED IN ACCORDANCE WITH ASTM STANDARD SPECIFICATION F876-01. THE TUBE SHALL BE LISTED TO ASTM BY INDEPENDENT THIRD PARTY TESTING LABORATORY.
- C. THE TUBE SHALL HAVE AN OXYGEN DIFFUSION BARRIER CAPABLE OF LIMITING OXYGEN DIFFUSION THROUGH THE TUBE TO NO GREATER THAN 0.10 g / M² / DAY AT 104 F WATER TEMPERATURE.
- D. THE TUBE SHALL BE A MAXIMUM OF 3/4" DIAMETER IN ACCORDANCE WITH ASTM STANDARD SPECIFICATION AS ABOVE.
- E. THE MINIMUM BEND RADIUS FOR COLD BENDING OF THE TUBE SHALL NOT BE LESS THAN SIX (6) TIMES THE OUTSIDE DIAMETER. BENDS WITH A RADIUS LESS THAN STATED SHALL REQUIRE THE USE OF A BEND SUPPORT AS SUPPLIED BY THE TUBE MANUFACTURER.
- 2.02 MANIFOLDS
- A. MULTIPLE CONNECTION MANIFOLDS SHALL BE OF CAST BRASS CONSTRUCTION, MANUFACTURED OF ALLOYS TO PREVENT DEZINICIFICATION, AND SHALL HAVE INTEGRAL CIRCUIT BALANCING VALVES. MANIFOLDS SHALL BE ABLE TO VENT AIR FROM THE SYSTEM AND SHALL BE PROVIDED WITH SUPPORT BRACKETS AND TUBE BEND SUPPORTS. MANIFOLD CIRCUITS SHALL BE ISOLATED FROM SUPPLY AND RETURN TUBING WITH VALVES THAT ARE SUITABLE FOR ISOLATION AND BALANCING.
- 2.03 FITTINGS
- A. FITTINGS SHALL BE MANUFACTURED OF DEZINICIFICATION RESISTANT BRASS. THESE FITTINGS SHALL BE SUPPLIED BY THE TUBE MANUFACTURER. THE FITTINGS SHALL CONSIST OF A COMPRESSION FITTING WITH INSERT COMPRESSION RING AND A COMPRESSION NUT.
- 2.04 ACCESS COVERS
- A. REMOVABLE ACCESS COVERS SHALL BE OF REINFORCED CONCRETE FORMED IN PLACE OR PRE-CAST CONCRETE OVER PIPE CONNECTIONS, FITTINGS, AND DISTRIBUTION MANIFOLDS. THEY SHALL BE BOTH INCONSPICUOUS AND HEAVY ENOUGH TO PREVENT UNAUTHORIZED REMOVAL. TAPERED FORMS FOR COVERS SHALL BE FURNISHED. COVERS SUBJECT TO VEHICULAR TRAFFIC SHALL BE TRAFFIC RATED.
- 2.05 SNOWMELT CONTROLS
- A. PROVIDE A MICROPROCESSOR BASED CONTROL PANEL THAT ACTIVATES THE SNOW MELTING SYSTEM BASED ON SIGNALS FROM A SNOW SENSOR AND AN OUTDOOR AIR TEMPERATURE SENSOR. THE CONTROL PANEL SHALL INCLUDE THE FOLLOWING FEATURES:
1. SELECTABLE LCD DISPLAY OF SLAB SURFACE TEMPERATURE, SURFACE TEMPERATURE SETTING, MELT SEQUENCE TIME REMAINING, ACCUMULATED HOURS OF USE, AND PERCENT HEAT OUTPUT. CONTROL PANEL SHALL BE CAPABLE OF ENABLING OR DISABLING THE SYSTEM AS NECESSARY.
2. STATUS LIGHTS INDICATING POWER ON, REMOTE ENABLE SIGNAL PRESENT, WARM WEATHER CUT-OFF, MELTING MODE ACTIVATED, WATER DETECTED, COLD WEATHER CUT-OFF, IDLING MODE ACTIVATED, PUMP ACTIVATED, SYSTEM MELTING, AND SENSOR FAULT.
3. SLAB SURFACE MELTING TEMPERATURE SETPOINT ADJUSTMENT.
4. SLAB SURFACE IDLING TEMPERATURE SETPOINT ADJUSTMENT.
5. MOISTURE SENSOR SENSITIVITY SETPOINT ADJUSTMENT.
6. MELTING SYSTEM MINIMUM ON TIME ADJUSTMENT.
7. COLD WEATHER CUT-OFF TEMPERATURE SETPOINT ADJUSTMENT.
8. TEST BUTTON TO INITIATE TEST SEQUENCE.
- B. PROVIDE AN OUTDOOR AIR TEMPERATURE SENSOR CONSISTING OF A 10,000 OHM THERMISTOR PROTECTED WITHIN A WHITE U.V. RESISTANT PVC PLASTIC ENCLOSURE.
- C. PROVIDE A SNOWICE SENSOR WHICH SITS FLUSH WITH THE SLAB SURFACE AFTER BEING MOUNTED INTO A SENSOR SOCKET. THE SENSOR SHALL MEASURE SLAB SURFACE TEMPERATURE AND SENSOR CORE TEMPERATURE AND SHALL DETECT MOISTURE ON THE SENSOR SURFACE. THE SENSOR SOCKET SHALL BE CONSTRUCTED OF DIE CAST BRASS.

SNOW MELT SYSTEM INSTALLATION

- 3.01 INSTALLATION
- A. HYDRONIC RADIANT HEAT TUBING LOOPS SHALL BE INSTALLED IN ACCORDANCE WITH THE MANUFACTURER'S WRITTEN INSTALLATION INSTRUCTIONS.
- B. ALL FITTINGS AND MANIFOLDS SHOULD BE ACCESSIBLE THROUGH ACCESS COVERS FOR MAINTENANCE. TUBING LOOPS SHALL BE INSTALLED WITHOUT SPLICES, AS A MINIMUM, FROM THE POINT AT WHICH THE TUBING ENTERS THE MANIFOLD TO THE POINT AT WHICH IT EXITS THE MANIFOLD.
- C. INSTALLATION SHALL FOLLOW THE MANUFACTURER'S SHOP DRAWINGS FOR TUBING LAYOUT, TUBE SPACING, MANIFOLD CONFIGURATION, MANIFOLD LOCATION, AND CONTROLS. ALL NOTES ON THE SHOP DRAWINGS SHALL BE FOLLOWED.
- D. DISTRIBUTION MANIFOLDS SHALL BE ATTACHED TO SUPPLY AND RETURN MAINS AT ACCESS COVER LOCATIONS. A MINIMUM OF ONE SUPPLY AND ONE RETURN MANIFOLD IS REQUIRED AND FOR ALTERNATE EXPANSION/CONSTRUCTION JOINTS.
- E. PIPING SHALL BE ATTACHED TO REINFORCING STEEL USING WIRE TIES. ALL LOOPS SHALL BE FORM A CONTINUOUS CONDUIT WITHOUT JOINTS FROM SUPPLY TO RETURN MANIFOLDS.
- F. NO PIPE SHALL EXTEND THROUGH EXPANSION, CONSTRUCTION, OR WORKING JOINTS IN CONCRETE SLAB. COORDINATE EXPANSION JOINTS INSTALLED DURING, OR CUT AFTER, CONCRETE POUR WITH TUBING LAYOUT.
- G. ALL PIPE CONNECTIONS, FITTINGS, AND DISTRIBUTION MANIFOLDS SHALL BE FREE OF CONCRETE AND ARRANGED TO BE EASILY SERVICED BY REMOVAL OF POURED-IN-PLACE CONCRETE ACCESS COVERS.
- H. COORDINATE SYSTEM FLUSHING AND GLYCOL FILL WORK WITH WATER TREATMENT CONTRACTOR.
- I. ALL PIPING CONNECTIONS SHALL BE FIELD WRAPPED WITH INSULATION. WRAP AND INSTALL PER MANUFACTURER'S RECOMMENDATIONS.
- 3.02 TESTING
- A. THE TUBING SYSTEM SHALL BE PRESSURIZED WITH WATER OR AIR TO A PRESSURE OF 60 PSIG 24 HOURS PRIOR TO ENCASEMENT IN THE CONCRETE SLAB. THE TUBING SYSTEM SHALL REMAIN AT THIS PRESSURE DURING THE SLAB INSTALLATION AND FOR A MINIMUM OF 24 HOURS THEREAFTER TO ENSURE SYSTEM INTEGRITY.
- 3.03 SYSTEM STARTUP
- A. AT STARTUP TIME, THE CONTRACTOR SHALL FOLLOW THE MANUFACTURER'S RECOMMENDATIONS FOR SYSTEM WATER AND TEMPERATURE BALANCING, RECORD BALANCE SETTINGS AT EACH MANIFOLD LOCATION, AND INCLUDE A COMPLETE RECORD OF THESE SETTINGS IN THE OPERATION AND MAINTENANCE MANUALS.
- B. VERIFY CONTROL OPERATION IS IN ACCORDANCE WITH SEQUENCE SPECIFIED.
- 3.04 SEQUENCE OF CONTROL
- A. SNOWMELT SYSTEM CONTROL
- B. THE SNOWMELT SYSTEM SHALL BE CONTROLLED BY A MICROPROCESSOR BASED CONTROL PANEL FURNISHED BY THE SNOWMELT SYSTEM MANUFACTURER. THE OUTDOOR TEMPERATURE SENSOR AND SNOWICE SENSOR SHALL ALSO BE FURNISHED BY THE SNOWMELT SYSTEM MANUFACTURER.
- C. THE CONTROL PANEL SHALL CONTINUOUSLY MONITOR THE SNOWICE SENSOR LOCATED IN THE SLAB. WHEN SNOW, ICE, OR WATER ARE DETECTED THE MELTING MODE SHALL BE INITIATED, UNLESS THE WARM WEATHER OR COLD WEATHER CUT-OFF CONTROLS HAVE BEEN ACTIVATED.
- D. IF THE OUTDOOR AIR TEMPERATURE IS ABOVE 40 deg F (ADJUSTABLE), THE SNOWMELT SYSTEM SHALL ENTER THE WARM WEATHER CUT-OFF MODE. IT SHALL REMAIN THERE UNTIL THE OUTDOOR AIR TEMPERATURE DROPS BELOW THE MELTING TEMPERATURE SETPOINT. THE WARM WEATHER CUT-OFF MODE SHALL DEACTIVATE THE SNOWMELT SYSTEM.
- E. THE MELTING MODE SHALL BE CAPABLE OF BEING ACTIVATED EITHER THROUGH THE SNOWICE SENSOR OR THROUGH A REMOTE ENABLE SIGNAL FROM THE BAS. WHEN THE MELTING MODE IS ACTIVATED, THE PUMP SHALL BE ENERGIZED AND THE HEAT RELAY SHALL CYCLE ON AND OFF, USING PULSE WIDTH MODULATION (PWM) CONTROL, TO MAINTAIN THE SLAB SURFACE AT THE MELTING TEMPERATURE SETPOINT.
- F. THE SLAB SHALL BE MAINTAINED AT AN IDLING TEMPERATURE WHEN THE SNOWMELT SYSTEM IS NOT IN THE MELTING MODE. CONTROL OPERATION IS SIMILAR TO THE MELTING MODE EXCEPT THE SLAB IS MAINTAINED AT A LOWER IDLING TEMPERATURE SETPOINT.
- G. IF A SENSOR FAULT OCCURS, A WARNING LIGHT SHALL BE ACTIVATED AT THE CONTROL PANEL.
- H. DESIRED SLAB SURFACE MELTING TEMPERATURE, SLAB SURFACE IDLING TEMPERATURE, AND COLD WEATHER CUT-OFF TEMPERATURE SETPOINTS SHALL BE ADJUSTABLE AT THE CONTROL PANEL.




TORIAN PLUM SNOW MELT UPGRADES
STEAMBOAT SPRINGS, COLORADO

ISSUE	DATE
CONSTRUCTION DOCUMENTS	11/10/23

MEP JOB:	22336
DESIGNED:	MAB
CHECKED:	KVB

MECHANICAL
SPECIFICATIONS




M3.2

EXISTING												
PANEL		"BP"		VOLTAGE		120 / 208 V		3 PH		4 W		
FLUSH		MAIN 4003		MLO								
SURFACE X		BUS 400A		FEED THRU				A.I.C. 10,000A				
TYPE	DESCRIPTION	BKR	CIR	LOAD (VA/PHASE)			CIR	BKR	DESCRIPTION	TYPE		
				A	B	C						
	SPARE	20/3	1	0	0			2	20/3	SPARE		
	-		3			0	0		4	-		
	-		5					0	0	6		
	SPARE	50/3	7	0	3867			8	50/3	SNOW MELT PUMP	M	
	-		9			0	3867		10	-	M	
	-		11				0	4867	12	-	MG	
G	BASEBOARD HEAT	20/2	13	1000	1000			14	20/2	BASEBOARD HEAT	G	
G	-		15			1000	500		16	-	G	
G	BOILER	20	17					500	50	18	20	
G	B-2	20	19	1344	500				20	20	BOILER EPO	
L	L - BOLLARDS	20	21			178	500		22	20	L - PLAZA	
G	FIREPIT - PLAZA	20	23					100	1176	24	20	
R	R - PLAZA	20	25	360	720				26	20	GLYCOL PUMP	
R	R - PLAZA	20	27			720	100		28	20	R - BOILER ROOM	
	SPARE	20	29				0	100	30	20	L - BOILER ROOM	
G	HEAT TAPE	40/2	31	2220	2200				32	40/2	HEAT TAPE	
G	-		33			2220	2200		34		G	
G	HEAT TAPE	30/2	35					1140	1140	36	30/2	
G	-		37	1140	1140				38	-	G	
G	LIGHTING CONTROL	20	39			200	500		40	20	L - POOL PERIMETER	
G	PLAZA	20	41					200	200	42	20	
	SPARE	20	43	0	0				44	20	HEAT TAPE CONTROL	
	SPARE	20	45			0	0		46	20	SPARE	
	SPARE	20	47				0	0	48	20	SPARE	
	SPARE	20	49	0	0				50	20	SPARE	
M	SNOW MELT PUMP P-2	60/3	51			3866	0		52		SPACE	
M	-		53				3866	0	54		SPACE	
M	-		55	3866	0				56		SPACE	
	SPACE		57			0	0		58		SPACE	
	SPACE		59					0	0	60	SPACE	
	SPACE		61	0	0				62		SPACE	
	SPACE		63			0	0		64		SPACE	
	SPACE		65					0	0	66	SPACE	
	SPACE		67	0	0				68		SPACE	
	SPACE		69			0	0		70		SPACE	
	SPACE		71					0	0	72	SPACE	
	SPACE		73	0	0				74		SPACE	
	SPACE		75			0	0		76		SPACE	
	SPACE		77				0	0	78		SPACE	
	SPACE		79	0	0				80		SPACE	
	SPACE		81			0	0		82		SPACE	
	SPACE		83					0	0	84	SPACE	
				19357	15851	13339						
LOAD TYPE		CONNECTED KVA			TOTAL		FACTOR		DEMAND KVA		TOTAL	
		A	B	C	ALL				A	B	C	ALL
LIGHTING/CONTINUOUS		0.5	1.3	0.1	1.9		125%		0.6	1.6	0.1	2.3
RECEPTACLE (10KVA OR LESS)		1.1	0.7	0.0	1.8		100%		1.1	0.7	0.0	1.8
RECEPTACLE (OVER 10KVA)		0.0	0.0	0.0	0.0		100%		0.0	0.0	0.0	0.0
HVAC/MOTOR		7.7	7.7	8.9	24.4		100%		7.7	7.7	8.9	24.4
MOTOR(LARGEST)		0.0	0.0	0.0	0.0		125%		0.0	0.0	0.0	0.0
KITCHEN EQUIPMENT		0.0	0.0	0.0	0.0		100%		0.0	0.0	0.0	0.0
MISCELLANEOUS		10.0	6.1	4.3	20.5		100%		10.0	6.1	4.3	20.5
TOTAL KVA		19.4	15.9	13.3	48.5				TOTAL KVA	19.5	16.2	13.4
								TOTAL AMPERES		162.4 134.8 111.4 162.4		
LEGEND		L = LIGHTING		R = RECEPTACLE		M = HVAC / MOTOR		K = KITCHEN		G = MISCELLANEOUS		

* CIRCUIT REVISED THIS CONTRACT.

** PROVIDE NEW SQUARE D BREAKER.

MECHANICAL EQUIPMENT SCHEDULE											
DESIGNATION	DESCRIPTION	VOLTAGE	PH	HP	KVA	FLA (MCA)	CONDUCTORS	CONDUIT	SWITCH	CB	FUSE SIZE/TYPE
B-1	BOILER	120	1	-	-	9.2	2-#12, 1-#12 GND	1/2"	STO	20/1	-
P-1	PUMP	208	3	10	-	-	3-#4, 1-#10 GND	1-1/4"	60/3	60/3	50A FRN-R



ONE-LINE DIAGRAM

SCALE: N.T.S.

NOTE: ALL CONDUCTORS ARE COPPER UNLESS NOTED OTHERWISE.


ELECTRICAL SYMBOLS LEGEND

ALL SYMBOLS INDICATED IN THE LEGEND MAY NOT NECESSARILY BE USED ON PLANS.

CIRCUITING		POWER SYMBOLS		LIGHTING SYMBOLS		FIRE ALARM SYMBOLS		ONE LINE DIAGRAM SYMBOLS			
SYMBOL	DESCRIPTION	SYMBOL	DESCRIPTION	SYMBOL	DESCRIPTION	SYMBOL	DESCRIPTION	SYMBOL	DESCRIPTION		
	CIRCUITING DESIGNATION - OPEN 7740V, SOLID 1000V; CIRCUITING - RUN CONCEALED IN WALL OR CEILING CIRCUITING - RUN CONCEALED IN FLOOR OR GRADE CONDUIT RISER - TURNED UP, TURNED DOWN CIRCUITING - CONTINUED AS DESIGNATED CIRCUITING - END CAP		FLOOR MOUNTED JUNCTION BOX JUNCTION BOX JUNCTION BOX W/ BLANK COVER SIMPLEX RECEPTACLE DUPLEX RECEPTACLE HALF SWITCHED DUPLEX RECEPTACLE DEDICATED DUPLEX RECEPTACLE CEILING MOUNTED DUPLEX RECEPTACLE FOURPLEX RECEPTACLE DEDICATED FOURPLEX RECEPTACLE C/G. MOUNTED FOURPLEX RECEPTACLE SPECIAL RECEPTACLE - SEE DRAWING NOTES FLOOR MOUNTED DEVICE FLUSH FLOOR COMBINATION FLOOR BOX NON FUSED DISCONNECT SWITCH FUSED DISCONNECT SWITCH MOTOR STARTER MOTOR ONE, TWO, AND THREE BUTTON PUSH SWITCH POWER POLE TIME CLOCK CONTACTOR METER PANEL BOARD CLOCK PULLBOX CURRENT TRANSFORMER TRANSFORMER WATER HEATER		RECESS MOUNTED FLUORESCENT STRIP SURFACE MOUNTED FLUORESCENT STRIP SURFACE MOUNTED 1 x 4 FLUORESCENT SURFACE MOUNTED 2 x 4 FLUORESCENT RECESS MOUNTED 2 x 4 FLUORESCENT RECESS MOUNTED 1 x 4 FLUORESCENT CEILING MOUNTED SINGLE FACE EXIT SIGN W/ "TROG EYE" CEILING MOUNTED EXIT SIGN WALL MOUNT (ANY FIXTURE TYPE) EMERGENCY BATTERY PACK, "TROG-EYE" EMERGENCY REMOTE HEAD, SINGLE & DOUBLE DOWNLIGHT/PENDANT FIXTURE WALL MOUNTED FIXTURE WALLWASH DOWNLIGHT PORCELAIN KEYLESS LAMPHOLDER TRACK LIGHTING TRACK LIGHTING HEAD SINGLE ARM SITE LIGHTING - ADDITIONAL KNOBS AS REQUIRED BUILDING EXTERIOR WALL MOUNTED		CEILING MOUNTED FIRE SPEAKER/STROBE CEILING MOUNTED STROBE CEILING MOUNTED FIRE SPEAKER REMOTE INDICATOR LAMP MANUAL PULL STATION FLOW SWITCH TAMPER SWITCH PRESSURE SWITCH CEILING/WALL MOUNTED STROBE FIRE HORN FIRE HORN WITH STROBE MAGNETIC DOOR HOLD OPEN FIRE ALARM CONTROL PANEL ANNUNCIATOR PANEL DUCT DETECTOR FIRE SMOKE DAMPER HEAT DETECTOR SMOKE DETECTOR FIREFIGHTER'S PHONE JACK WALL PHONE		PANEL BOARD CURRENT TRANSFORMER ENCLOSURE PULL BOX FUSED DISCONNECT SWITCH NON-FUSED DISCONNECT SWITCH TRANSFORMER (PLAN VIEW) PAD MOUNTED TRANSFORMER (ONE-LINE) TRANSFER SWITCH OVERHEAD POLE MOUNTED TRANSFORMER BANK		FUSED DISCONNECT SWITCH WITHIN SWITCHBOARD SPARE SWITCH WITHIN SWITCHBOARD SPACE WITHIN SWITCHBOARD CIRCUIT BREAKER SERVICE WEATHER HEAD CURRENT TRANSFORMER GROUNDING CONNECTION MOTOR GENERATOR METER
GENERAL		TELECOMMUNICATION SYMBOLS		MISCELLANEOUS SYMBOLS		ABBREVIATIONS					
SYMBOL	DESCRIPTION	SYMBOL	DESCRIPTION	SYMBOL	DESCRIPTION						
	REVISION DELTA DRAWING NOTE MECHANICAL EQUIPMENT HITCH EQUIPMENT		TELEPHONE OUTLET, SINGLE GANG BOX, 3/4\"/>		CARD READER REMOTE TEST SWITCH TIME CLOCK PHOTOCELL MUSIC OR PAGING SPEAKER THERMOSTAT, LINE VOLTAGE SECURITY MOTION SENSOR, WALL MOUNTED SECURITY MOTION SENSOR, CEILING MOUNTED EMERGENCY POWER OFF BELL DOORBELL BUZZER TELEVISION CABLE OUTLET SECURITY CAMERA INTERCOM PUSH BUTTON MICROPHONE JACK COMBINATION CLOCK/SPEAKER BOX						
AC	ABOVE COUNTER	C.W.P.	COLD WATER PIPE	EW	ELECTRIC WATER HEATER	IG	ISOLATED GROUND DEVICE	N.O.	NORMALLY OPEN	SM	SURFACE MOUNT
A.F.F.	ABOVE FINISHED FLOOR	(E)	EXISTING	FF	FLUSH FLOOR POKE THRU	MC	MECHANICAL CONTRACTOR	NTS	NOT TO SCALE	T/D	TELEPHONE AND DATA OUTLET
AFCI	ARC FAULT CIRCUIT INTERRUPTER	EPO	EMERGENCY POWER OFF	GC	GENERAL CONTRACTOR	(N)	NOT TO SCALE	(PART)	PARTIAL CIRCUIT	TYP	TYPICAL
BLDG.	BUILDING	EM	EMERGENCY POWER CIRCUIT	GND	GROUND	N.C.	NORMALLY CLOSED	RL	RELOCATED	UF	UNDER FLOOR
C/G.	CEILING MOUNTED	ENC	ELECTRIC WATER COOLER	GRD	GROUND FAULT CIRCUIT INTERRUPTER	N/C	NOT IN CONTRACT	RTS	REMOTE TEST SWITCH	WP	WEATHERPROOF - NEMA 3R
				GFCI/GFI		NL	NIGHT LIGHT			WF	WALL PHONE - 54\"/>
2018 INTERNATIONAL BUILDING CODE		2018 INTERNATIONAL ENERGY CONSERVATION CODE									
2018 INTERNATIONAL FIRE CODE		2023 NATIONAL ELECTRIC CODE									

Isc CALCULATION - 3 PHASE

Point #1 - At The Utility Transformer											
Isc =		24,400									
Point #2 - At the CT Compartment											
f =	[1.732	X	length	X	Isc(prev)]	/	[# runs	X	wire factor	X	voltage]
f =	1.732	X	190	X	24,400	/	2	X	13,923	X	208
f =	1.386										
M =	1/(1+f)										
M =	0.419										
Isc =	Isc(prev) x M										
Isc =	10,225										
Point #3 - At Panel "BP"											
f =	[1.732	X	length	X	Isc(prev)]	/	[# runs	X	wire factor	X	voltage]
f =	1.732	X	10	X	10,225	/	2	X	12,843	X	208
f =	0.033										
M =	1/(1+f)										
M =	0.968										
Isc =	Isc(prev) x M										
Isc =	9,897										
Point #4 - At Boiler "B-2"											
f =	[1.732	X	length	X	Isc(prev)]	/	[# runs	X	wire factor	X	voltage]
f =	1.732	X	25	X	9,897	/	1	X	617	X	480
f =	1.447										
M =	1/(1+f)										
M =	0.409										
Isc =	Isc(prev) x M										
Isc =	4,045										
Point #5 - At Pump "P-2"											
f =	[1.732	X	length	X	Isc(prev)]	/	[# runs	X	wire factor	X	voltage]
f =	1.732	X	35	X	9,897	/	1	X	981	X	480
f =	1.274										
M =	1/(1+f)										
M =	0.440										
Isc =	Isc(prev) x M										
Isc =	4,352										



- DRAWING NOTES**
1. RELOCATE EXISTING PUMP DISCONNECT TO MAINTAIN NEC REQUIRED WORKING CLEARANCES. EXTEND WIRE AND CONDUIT AS NECESSARY.
 2. CONNECT NEW BOILER TO EXISTING EMERGENCY POWER OFF (EPO) BUTTON.

TORIAN PLUM SNOW MELT UPGRADES
STEAMBOAT SPRINGS, COLORADO

ISSUE	DATE
CONSTRUCTION DOCUMENTS	11/10/23

MEP JOB: 22336
DESIGNED: KSP
CHECKED: RCC

**ELECTRICAL
BOILER ROOM
PLAN**



BOILER ROOM EQUIPMENT PLAN

SCALE: 1/4" = 1'-0"

BASIC ELECTRICAL REQUIREMENTS

PRIOR TO SUBMITTING BIDS, THE ELECTRICAL CONTRACTOR SHALL VISIT THE SITE TO VERIFY EXISTING ELECTRICAL EQUIPMENT CONDITIONS AND DIFFICULTIES THAT WILL AFFECT EXECUTION OF THE WORK. FIELD VERIFY QUANTITIES OF EXISTING LIGHT FIXTURES, ELECTRICAL DEVICES, CONDUIT, AND DEVICES. FIRE ALARM DEVICES, AND ELECTRICAL EQUIPMENT. NOTIFY THE ARCHITECT AND ENGINEER OF ANY EXISTING CONDITIONS, WHICH MODIFY THE SCOPE OF WORK AS SHOWN ON THE CONSTRUCTION DOCUMENTS. SUBMISSION OF A BID PROPOSAL WILL BE CONSTRUED AS EVIDENCE THAT SUCH AN EXAMINATION HAS BEEN MADE AND LATER CLAIMS FOR MOBILIZATION, LABOR, EQUIPMENT, AND/OR MATERIALS REQUIRED BECAUSE OF DIFFICULTIES ENCOUNTERED WILL NOT BE RECOGNIZED.

2. ELECTRICAL CONTRACTOR SHALL FULLY COORDINATE WITH OWNER REPRESENTATIVES. ALL ELECTRICAL WORK PERFORMED UNDER THIS CONTRACT SHALL CONFORM WITH LATEST EDITIONS OF THE NATIONAL ELECTRICAL CODE, UNIFORM BUILDING CODE OR INTERNATIONAL BUILDING CODE, LOCAL BUILDING AND FIRE DEPARTMENT REQUIREMENTS, PERFORM WORK IN ACCORDANCE WITH REQUIREMENTS OF OWNER REPRESENTATIVES.

3. ELECTRICAL CONTRACTOR SHALL MAINTAIN ON THE JOB AN UP TO DATE SET OF WORKING DRAWINGS, MARKED UP TO SHOW ELECTRICAL SYSTEMS AS INSTALLED. PROVIDE ARCHITECT WITH ONE SET OF REVISIONS. PROVIDE AS BUILT PROJECT RECORD AFTER COMPLETION OF PROJECT. INFORMATION CLEARLY INDICATED. INCLUDE DISCREPANCIES IN FEEDER SIZES, EQUIPMENT SIZES AND LOCATIONS, AND DEVICE TYPES AND LOCATIONS.

4. ELECTRICAL CONTRACTOR SHALL OBTAIN AND PAY FOR ALL LOCAL FEES, PERMITS, AND SERVICES OF INSPECTION AUTHORITIES REQUIRED BY ELECTRICAL WORK FOR THIS ELECTRICAL CONSTRUCTION.

5. REFER TO ARCHITECTURAL AND MECHANICAL EQUIPMENT DRAWINGS FOR EXACT LOCATIONS OF ELECTRICAL DEVICES AND LIGHT FIXTURES. DO NOT SCALE FROM THE ELECTRICAL PLANS. ADDITIONAL ELECTRICAL REQUIREMENTS ON ARCHITECTURAL PLANS, KITCHEN EQUIPMENT PLANS, AND MECHANICAL PLANS SHALL BE INCLUDED IN THE ELECTRICAL CONTRACTOR'S BID.

6. THE ELECTRICAL DRAWINGS ARE DIAGRAMMATIC AND INDICATE THE GENERAL ARRANGEMENT OF ELECTRICAL WORK. LOCATIONS ARE APPROXIMATE AND SHALL BE SUBJECT TO MINOR MODIFICATIONS AS DIRECTED BY THE GENERAL CONTRACTOR AND OWNER REPRESENTATIVES. ELECTRICAL CONTRACTORS SHALL BE BUILT TO PROJECT THE EXACT FITTING OF ALL MATERIALS, EQUIPMENT, ETC., IN THE BUILDING AND TENANT SPACE. ALL DIMENSIONS SHALL BE VERIFIED ON THE JOB. ELECTRICAL CONTRACTOR SHALL CUT, CHANNEL, CHASE, AND/OR DRILL FLOORS, WALLS, PARTITIONS, CEILING, OR OTHER SURFACES AS REQUIRED FOR INSTALLATION, SUPPORT, AND/OR ETC., ETC., ETC. PROVIDE X-RAY OF FLOOR PRIOR TO CORE DRILLS. THE GENERAL CONTRACTOR SHALL BE RESPONSIBLE FOR THE SUBSEQUENT PATCHING WORK.

7. EXISTING EQUIPMENT IS SHOWN FOR REFERENCE PURPOSES AND SHALL REMAIN. EXISTING EQUIPMENT NOT SHOWN SHALL ALSO REMAIN. EXISTING EQUIPMENT TO REMAIN SHALL BE PROTECTED FROM DAMAGE.

8. WORK SHOWN AS EXISTING CONDITIONS HAS TAKEN FROM OWNER FURNISHED DRAWINGS AND/OR VERIFIED DURING FIELD SURVEY. MEP IS NOT RESPONSIBLE FOR THE ACCURACY OF ANY INFORMATION OR THE ADEQUACY, SAFETY AND CONFORMANCE TO CURRENT PREVAILING CODES OF ANY WORK SHOWN AS EXISTING ON THESE DOCUMENTS.

9. IT IS THE INTENT OF THESE DOCUMENTS TO RESULT IN A COMPLETE ELECTRICAL INSTALLATION IN COMPLETE ACCORDANCE WITH APPLICABLE CODES AND ORDINANCES. THE DRAWINGS ARE DIAGRAMMATIC IN CHARACTER AND DO NOT NECESSARILY INDICATE EVERY REQUIRED JUNCTION BOX, RACEWAY, CONDUIT, OR CABLE. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE SPECIFICATION OR NOTED ON THE DRAWINGS, BUT WHICH ARE OBVIOUSLY NECESSARY TO MAKE A COMPLETE WORKING INSTALLATION, SHALL BE INCLUDED.

10. DRAWINGS AND SPECIFICATIONS ARE COMPLEMENTARY. WHATEVER IS CALLED FOR IN EITHER IS BINDING AS THOUGH CALLED FOR IN BOTH. THE MORE STRINGENT REQUIREMENTS SHALL GOVERN.

11. IF CONFLICTS ARE DISCOVERED IN CONTRACT DOCUMENTS AS WORK PROGRESSES, A SET OF PRINTS MARKED WITH RED PENCIL, SHOWING RECOMMENDED MODIFICATIONS SHALL BE SUBMITTED TO THE ENGINEER FOR APPROVAL PRIOR TO INSTALLATION.

12. IN THE EVENT THAT DISCREPANCIES EXIST OR DISCREPANCY ITEMS OR DETAILS HAVE BEEN OMITTED, NOTIFY THE ARCHITECT IN WRITING OF SUCH REQUIREMENT OR OMISSION AT LEAST THREE DAYS PRIOR TO BID DATE. FAILURE TO DO SO SHALL BE CONSTRUED AS WILLINGNESS TO SUPPLY NECESSARY MATERIALS AND LABOR REQUIRED FOR THE PROPER COMPLETION OF THIS WORK. FOR DISCREPANCIES WHICH ARE NOT REPORTED BY CONTRACTOR THE MOST STRINGENT REQUIREMENT SHALL APPLY.

13. IN THE EVENT THAT ADDITIONAL INFORMATION IS REQUIRED DURING CONSTRUCTION, REQUEST SUCH INFORMATION FROM THE ARCHITECT IN WRITING PRIOR TO PERFORMING RELATED WORK. THE REQUEST FOR INFORMATION SHALL INCLUDE AN EXPLANATION OF THE INFORMATION REQUIRED INCLUDING REFERENCES TO RELATED PORTIONS OF THE DOCUMENTS AND CONTRACTOR'S RECOMMENDATIONS.

14. THE TERM "PROVIDE" SHALL MEAN FURNISH AND INSTALL ITEMS OR SYSTEMS IN ACCORDANCE WITH PLANS AND SPECIFICATIONS.

15. INSTALL EQUIPMENT AND MATERIALS IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS UNLESS LOCAL CODES OR REGULATIONS TAKE PRECEDENCE.

16. PROVIDE APPURTENANCES AND CONSUMABLES AS REQUIRED.

17. WORK SHALL CONFORM TO BASE BUILDING SPECIFICATIONS EXCEPT AS AMENDED BY THESE SPECIFICATIONS. CONTRACTOR SHALL VERIFY EXISTING CIRCUITS PRIOR TO STARTING WORK.

18. COMPLY WITH THE LATEST EDITION OF NATIONAL ELECTRICAL CODE, APPLICABLE STATE AND LOCAL CODES, ORDINANCES AND OSHA REQUIREMENTS.

19. WHERE A CONFLICT EXISTS BETWEEN ANY PREVAILING CODES AND WORK INDICATED ON THESE DOCUMENTS, THE MORE STRINGENT REQUIREMENT SHALL GOVERN.

20. PAY FOR ALL ELECTRICAL PERMITS, LICENSES AND CONSTRUCTION FEES.

21. EXAMINE SITE AND PREMISES PRIOR TO SUBMISSION OF BID. NO ADDITIONAL COMPENSATION WILL BE MADE FOR EXTRA EXPENSE INCURRED DUE TO FAILURE TO EXAMINE EXISTING SITE CONDITIONS.

22. DEMOLITION OR ABANDONING ANY ELECTRICAL AND COMMUNICATIONS CONDUIT, WIRING, CABLEING, OR DEVICE MEANS TO REMOVE IN ITS ENTIRETY. REMOVE UNUSED CONDUITS FROM CEILING SPACES IN AREAS OF WORK. ABANDONED OUTLET JUNCTION BOXES ARE TO BE REMOVED AND COVERED WITH A REMOVED BOARD. ABANDONED POKE THRU OUTLETS SHALL HAVE COVER PLATES AND BE FILLED WITH FIRE RATED FOM SEALANT TO MAINTAIN FIRE RATINGS OF FLOOR.

23. ELECTRICAL CONTRACTOR SHALL RE-USE EXISTING BRANCH CIRCUIT CONDUIT AND WIRING WHERE POSSIBLE. RE-USE EXISTING PREFABRICATED LIGHTING SYSTEM CONDUIT AND WIRING WHERE POSSIBLE. RE-ROUTE AND EXTEND AS NECESSARY FOR THIS TENANT FINISH CONSTRUCTION. PROVIDE ADDITIONAL NEW CONDUIT, WIRING, COMPONENTS, AND CONNECTIONS AS REQUIRED FOR COMPLETE AND OPERATIONAL SYSTEMS, TYPICAL.

24. SCHEDULE SERVICE INTERRUPTIONS IN WRITING WITH OWNER AND BUILDING OCCUPANTS ONE (1) WEEK IN ADVANCE.

25. COORDINATE WORK AND POWER OUTAGES WITH BUILDING MANAGEMENT, AFFECTED TENANTS, AND OTHER TRADES.

26. COORDINATE BUILDING ELECTRICAL SERVICE REVISIONS AND ADDITIONS WITH LOCAL UTILITY COMPANY.

27. EQUIPMENT REMOVED IS THE PROPERTY OF THE OWNER AND SHALL BE RETURNED TO THE OWNER FOR DISPOSAL. SALVAGEABLE LABORATORY EQUIPMENT FOR OWNER AND THE OWNER DESIGNATED LOCATION. EQUIPMENT NOT RETAINED BY THE OWNER SHALL BE REMOVED FROM THE SITE BY THE CONTRACTOR.

28. ALL MATERIALS SHALL BE NEAT AND BEAR THE "UL" LABEL.

29. PROVIDE SUBMITTALS (ELECTRONIC PDF FORMAT) ON ALL PROPOSED MATERIALS. SUBMITTALS SHALL CLEARLY INDICATE COMPLETE MODEL NUMBERS OF MATERIALS OR EQUIPMENT PROPOSED. SUBMITTALS SHALL BE SUBMITTED WITHIN 10 DAYS IN ADVANCE OF CONTRACT FOR REVIEW. SUBMITTALS SHALL BE PROVIDED IN A TIMELY MANNER WITH LEAD TIMES FOR MATERIALS AND ADEQUATE TIME FOR ENGINEER REVIEW TAKEN INTO ACCOUNT. CONTRACTOR IS RESPONSIBLE FOR ANY ADDITIONAL COSTS ASSOCIATED WITH EXISTING MATERIAL DEFICIENCIES OR SUBSTITUTIONS OF MATERIALS FROM WHAT WAS SPECIFIED IN THE PLANS OR SPECIFICATIONS.

30. REMOVE ALL REFUSE AND WASTE MATERIAL FROM BUILDING DAILY.

31. LEFT OVER OR REMOVED EQUIPMENT REQUIRING HAZARDOUS WASTE REMOVAL SHALL BE REMOVED FROM THE SITE BY THE CONTRACTOR UPON COMPLETION OF THE CONSTRUCTION PROJECT AND DISPOSED PER EPA REQUIREMENTS.


32. PROVIDE TEST EQUIPMENT AND CONDUCT NECESSARY TESTING TO DETERMINE CONFORMITY WITH EQUIPMENT SPECIFICATIONS. PERFORM TESTS UNDER OBSERVATION OF OWNER'S REPRESENTATIVE. CORRECT DEFECTS AND RETEST. COMPLETE TESTS TO SATISFACTION OF OWNER'S REPRESENTATIVE.

33. PROVIDE UPDATED, COMPLETE AND ACCURATE TYPED PANELBOARD CIRCUIT DIRECTORIES AT THE PANELBOARD WORK. PROVIDE ALL CIRCUIT SIZES AND SPACES IN PENCIL. CLEAN EXPOSED DAMAGED SURFACES AND CHECK TIGHTNESS OF ALL ELECTRICAL CONNECTIONS. REPLACE DAMAGED CIRCUIT BREAKERS AS REQUIRED AND PROVIDE FILLER PLATES FOR VACANT SPACES.

6. PROVIDE UPDATED LABELING OF ALL NEW AND RELOCATED ELECTRICAL EQUIPMENT IN SCOPE OF WORK INCLUDING, BUT NOT LIMITED TO, ENGINE GENERATOR SYSTEMS, TRANSFER SWITCHES, TRANSFORMERS, SWITCHGEAR, SWITCHBOARDS, PANELBOARDS, MOTOR CONTROL CENTERS, AND DISCONNECTS TO INDICATE THE AMPERE RATING, VOLTAGE RATING, PHASE, CONDUCTOR COLOR CODING WITHIN THE EQUIPMENT AND APPLICABLE AIC RATING.
 35. GUARANTEE ELECTRICAL INSTALLATION AND ALL WORK UNDER THIS DIVISION (EXCLUDING LAMPS) FOR A PERIOD OF TWO YEARS FROM DATE OF FINAL ACCEPTANCE BY OWNER AGAINST ALL EVIDENCE OF IMPERFECT WORKMANSHIP, FAILURE OR MALFUNCTION OF MATERIALS AND EQUIPMENT. REPLACE WORK FOUND DEFECTIVE WITHIN THIS PERIOD PROMPTLY AT NO COST TO OWNER.
 36. GUARANTEE ELECTRICAL INSTALLATION AND ALL WORK UNDER THIS DIVISION (EXCLUDING LAMPS) FOR A PERIOD OF TWO YEARS FROM DATE OF FINAL ACCEPTANCE BY OWNER AGAINST ALL EVIDENCE OF IMPERFECT WORKMANSHIP, FAILURE OR MALFUNCTION OF MATERIALS AND EQUIPMENT. REPLACE WORK FOUND DEFECTIVE WITHIN THIS PERIOD PROMPTLY AT NO COST TO OWNER.
- ## MATERIALS AND EQUIPMENT
1. WIRE AND CABLE SHALL BE MINIMUM NUMBER 12 AWG COPPER WITH THIN OR THIN INSULATION, MINIMUM 20 AMPERE CIRCUITS EXCEPT FOR MOTOR CIRCUITS SHALL BE SOLID, LARGER WIRE AND MOTOR CIRCUIT FEEDERS SHALL BE STRANDED. MOTOR CONNECTIONS SHALL BE WITH STRANDED CONDUCTORS. WIRE AND CABLE SHALL BE AS MANUFACTURED BY SOUTHWIRE, OR APPROVED EQUIVALENT.
 2. ALL CONDUCTORS SHALL BE THIN/THIN INSULATED COPPER UNLESS OTHERWISE NOTED ON THE DRAWINGS. #12 AWG FOR 120 VOLT, 20 AMPERE CIRCUITS, 15 FEET OR LESS; #12 AWG FOR 277 VOLT, 20 AMPERE CIRCUITS, 15 FEET OR LESS; TO FIRST DEVICE, THIN OR THIN INSULATION PROVIDE WIRE COLOR CODING AS REQUIRED BY THE NATIONAL ELECTRICAL CODE. ALL WIRING SHALL BE RUN CONCEALED AND IN EMT CONDUIT. ALL HOMERUNS SHALL BE IN EMT CONDUIT. ALL EMPTY CONDUITS INDICATED ON THE DRAWINGS SHALL BE SUPPLIED WITH NYLON PULL LINES.
 3. ALL ELECTRICAL WIRING SHALL BE INSTALLED IN CONDUIT. WRITTEN APPROVAL FROM DESIGN ENGINEER AND PROPERTY MANAGEMENT FOR THE USE OF "MC" AND "AC" TYPE CABLING. IF APPROVED, "MC" AND "AC" TYPE CABLE SHALL BE PERMITTED FOR USE IN BRANCH CIRCUIT WIRING FROM JUNCTION BOXES TO DEVICES ONLY. ALL RUNS SHALL BE RUN IN CONDUIT. "MC" AND "AC" CABLING SHALL BE INSTALLED PER NATIONAL ELECTRICAL CODE AND LOCAL BUILDING DEPARTMENT REQUIREMENTS. USE APPROVED TYPE COUPLINGS AND CONNECTORS. PROVIDE CONDUIT SUPPORTS AS REQUIRED BY THE NATIONAL ELECTRICAL CODE AS A MINIMUM. PRE-MANUFACTURED CABLE ASSEMBLIES SHALL NOT BE PERMITTED.
 4. INTERIOR CONDUIT SHALL BE ELECTRICAL METALLIC TUBING WITH SET SCREEN FITTINGS.
 5. EXTERIOR CONDUIT SHALL BE RIGID METAL CONDUIT, GALVANIZED, WITH THREADED FITTINGS.
 6. CONDUIT IN AREAS SUBJECT TO MECHANICAL INJURY SHALL BE RIGID METAL CONDUIT, GALVANIZED, WITH THREADED FITTINGS.
 7. CONDUIT SUBJECT TO VIBRATION OR WHERE USED FOR MECHANICAL EQUIPMENT CONNECTIONS SHALL BE PVC JACKETED FLEXIBLE METAL CONDUIT.
 8. OUTLET AND JUNCTION BOXES SHALL BE OF PRESSURED STEEL AND AS MANUFACTURED BY STEEL CITY, APPLETON, OR RACO. OUTLET BOXES SHALL BE DOUBLE GANG BOX WITH SINGLE OR DOUBLE GANG TRIM RINGS AS REQUIRED.
 9. WIRING DEVICES SHALL BE SPECIFICATION GRADE; 20 AMP FOR GENERAL APPLICATION, 20 AMP OR GREATER FOR DEDICATED CIRCUITS AND AS REQUIRED BY CURRENT LOAD. LEVITON #5362 RECEPTACLES, 5362-16 (ORANGE) ISOLATED GROUND RECEPTACLES, AND #1221 SWITCHES (OR EQUIVALENT) TO MATCH EXISTING BUILDING STANDARD OR PROVIDE (WHITZ) UNLESS OTHERWISE NOTED.
 10. FIRE RESISTING WALLS AND OPENINGS MAY HAVE OPENINGS FOR STEEL ELECTRICAL OUTLET BOXES NOT EXCEEDING 16 SQUARE INCHES IN AREA, PROVIDED THE AGGREGATE AREA OF SUCH OPENINGS IS NOT MORE THAN 100 SQUARE INCHES FOR ANY 100 SQUARE FEET OF WALL, TYPICAL.
 11. ALL 15 AMPERE AND 20 AMPERE, 125 VOLT AND 250 VOLT NON-LOCKING RECEPTACLES INSTALLED IN DAMP OR WET LOCATIONS SHALL BE LISTED AS WEATHER-RESISTANT PER 2011 NEC, ARTICLE 406.9 (A) AND (B). ALL RECEPTACLES MOUNTED IN WET LOCATIONS AS REFERENCED ABOVE SHALL HAVE AN "IN-USE" SINGLE PHASE/POWDER COVER.
 12. ALL 125 VOLT, SINGLE PHASE, 15 AND 20 AMPERE RECEPTACLES SHALL HAVE GFCI PROTECTION FOR PERSONNEL IN THE FOLLOWING AREAS: BATHROOMS, KITCHENS (AREAS WITH A SINK AND PERMANENT FACILITIES FOR FOOD PREPARATION AND COOKING), ROOFTOPS, OUTDOORS AND WITHIN 6 FEET FROM THE OUTSIDE EDGE OF SINKS.
 13. EQUIPMENT SHALL BE GROUNDED IN ACCORDANCE WITH NATIONAL ELECTRICAL CODE. A SEPARATE EQUIPMENT GROUNDING CONDUIT SHALL BE INSTALLED WITH ALL FEEDER AND BRANCH CIRCUITS CONDUCTORS. GROUND WIRES SHALL BE COPPER.
 14. FUSES SHALL BE AS INDICATED AND AS MANUFACTURED BY COOPER-BUSSMANN.
 15. CIRCUIT BREAKERS SHALL BE THERMAL-MAGNETIC, QUICK-MAKE, QUICK-BREAK, TRIP-FREE AND TRIP INDICATING. MULTI-POLE CIRCUIT BREAKERS SHALL BE EQUIPPED WITH AN INTERNAL COMMON TRIP MECHANISM. CIRCUIT BREAKERS SHALL BE OF SAME MANUFACTURER AS PANELBOARD AND DISCONNECTING DEVICE.
 16. MOTOR AND CIRCUIT DISCONNECTS SHALL BE HEAVY DUTY, FUSIBLE OR NON-FUSIBLE AS INDICATED.

1. ELECTRICAL CONTRACTOR SHALL USE #10 AWG CU WIRE WHEN LENGTH OF CONDUCTOR EXCEEDS 150 FEET FOR 120 VOLT, 20 AMP CIRCUITS AND 150 FEET FOR 277 VOLT, 20 AMP CIRCUITS. SIZE CONDUCTORS FOR MINIMUM VOLTAGE DROP ALLOWED PER THE NATIONAL ELECTRICAL CODE.
2. ELECTRICAL CONTRACTOR SHALL USE #8 AWG CU WIRE WHEN LENGTH OF CONDUCTOR EXCEEDS 150 FEET FOR 120 VOLT, 20 AMP CIRCUITS AND 300 FEET FOR 277 VOLT, 20 AMP CIRCUITS. SIZE CONDUCTORS FOR MINIMUM VOLTAGE DROP ALLOWED PER THE NATIONAL ELECTRICAL CODE.
3. NEUTRALS, RACEWAYS, AND NON-CURRENT CARRYING PARTS OF ELECTRICAL EQUIPMENT AND ASSOCIATED ENCLOSURES SHALL BE GROUNDED IN FULL ACCORDANCE WITH THE NATIONAL ELECTRICAL CODE. RELOCATE HARD WIRED GROUND CONNECTIONS TO DEVICES AND SEPARATE INSULATED GROUND WIRE CONTINUOUS IN EACH CIRCUIT (#12 AWG CU MINIMUM "GREEN" TRACER GROUND).
4. ALL FLOOR AND WALL PENETRATIONS WHERE ELECTRICAL DEVICES AND RACEWAY HAVE BEEN REMOVED MUST BE REPAIRED AND SEALED TO MAINTAIN THE REQUIRED FIRE RATING. CONDUITS PENETRATING FIRE RATED WALLS OR CEILING SHALL BE FIRE STOPPED WITH A U.L. LISTED FIRE STOPPING COMPOUND SEALANT TO MAINTAIN THE REQUIRED FIRE RATING. FIRE RATED FLOOR AND WALL PENETRATIONS IMMEDIATELY.
5. ELECTRICAL CONTRACTOR SHALL PROVIDE PRODUCT LITERATURE INFORMATION ON SITE FOR FIELD INSPECTOR REGARDING FIRE RATING OF FLOOR BOXES AND POKE THRU DEVICES.
6. ALL CONDUITS PENETRATING A ONE HOUR FIRE RATED WALL OR CEILING SHALL BE FIRE STOPPED WITH A U.L. LISTED FIRE STOPPING COMPOUND SEALANT.
7. ELECTRICAL CONTRACTOR SHALL COORDINATE EXACT LOCATIONS OF LIGHTING FIXTURES IN MECHANICAL ROOMS/SPACES WITH MECHANICAL DUCT WORK INSTALLER PRIOR TO ROUGH-IN. LOCATE BELOW DUCT WORK (8'-0" A.F.F. MIN) CENTERED IN ROOM AS MUCH AS POSSIBLE. ELECTRICAL CONTRACTOR SHALL FIELD VERIFY ALL MECHANICAL EQUIPMENT LOCATIONS AND REQUIREMENTS WITH MECHANICAL PLANS. ELECTRICAL CONTRACTOR AND ACTUAL MECHANICAL EQUIPMENT SUPPLIED. INCLUDE ALL REQUIRED OUTLETS, HEAVY DUTY DISCONNECT SWITCHES, FUSES, CONTROLS, CONTROL WIRING AND ALL CONNECTIONS IN THE ELECTRICAL BID.
8. COORDINATE ALL INTERCONNECTIONS TO AND BETWEEN NEW AND EXISTING SYSTEMS INCLUDING, BUT NOT LIMITED TO: POWER, LIGHTING, FIRE ALARM AND DETECTION, TELEPHONE AND INTERCOM.
9. COORDINATE LOCATIONS OF DEVICES WITH ARCHITECT PRIOR TO ROUGH-IN.
10. COORDINATE WITH MECHANICAL CONTRACTOR FOR LOCATIONS OF EQUIPMENT CONNECTIONS PRIOR TO ROUGH-IN.
11. ALL NEW LIGHT SWITCHES, RECEPTACLE OUTLETS, TELEPHONE OUTLETS, FIRE ALARM DEVICES, AND COMMUNICATION/DATA OUTLETS SHALL MEET THE REQUIREMENTS FOR AMERICANS WITH DISABILITIES (A.D.A.) AND ANSI A117.1 REQUIREMENTS FOR MOUNTING HEIGHTS AND ORIENTATIONS, TYPICAL UNLESS OTHERWISE NOTED. SWITCHES SHALL BE A MINIMUM OF 48" A.F.F. AT BOTTOM OF DEVICE AND SWITCHES A MAXIMUM OF 48" A.F.F. AT TOP OF DEVICE, TYPICAL UNLESS OTHERWISE NOTED.
12. COORDINATE LOCATIONS OF MECHANICAL EQUIPMENT CONTROL PANELS WITH DIVISION 23. CIRCUITS FOR CONTROL PANEL POWER IS INDICATED ON PANELBOARD SCHEDULES.
13. REMOVE CONDUITS AND CONDUIT BACK TO SOURCE FOR EQUIPMENT WHICH IS TO BE REMOVED UNLESS EXISTING WIRING AND CONDUIT CAN BE REMOVED TO ACCESS THE JUNCTION BOX AT THE CONTRACTORS OPTION TO REUSE EQUIPMENT. MAINTAIN CIRCUIT CONTINUITY OF REMAINING DEVICES AND EQUIPMENT. CONTRACTOR IS TO PHASE WORK TO MAINTAIN CONTINUITY OF CIRCUITS IN AREAS WHICH ARE IN ANOTHER PHASE.
14. EXTEND EXISTING CIRCUITRY TO RECONNECT TO RELOCATED ITEMS AS INDICATED OR UNLESS OTHERWISE NOTED.
15. PROVIDE BLANK COVER PLATES ON WALLS TO REMAIN FOR REMOVED OR RELOCATED DEVICES. COVER PLATES SHALL MATCH EXISTING.

16. ALL JUNCTION BOX COVERS SHALL BE INDENTIFIY LABELLED WITH PANEL DESIGNATION AND BRANCH CIRCUIT NUMBER OF EACH WIRE WITHIN THE JUNCTION BOX.
17. CONDUIT SHALL BE CONCEALED WHERE LOCATED IN FINISHED AREAS, OR ON EXTERIOR OF BUILDING. CONDUITS IN UNFINISHED OR UTILITY AREAS MAY BE EXPOSED.
18. DO NOT DRILL OR SHOOT CONCRETE ANCHORS INTO THE BOTTOM OF CONCRETE STRUCTURAL TEES.
19. MINIMUM WORKING CLEARANCES PER THE LATEST EDITION OF THE NATIONAL ELECTRICAL CODE SHALL BE PROVIDED AROUND AND IN FRONT OF ALL ELECTRICAL EQUIPMENT.
20. ALL CIRCUIT BREAKER LUGS SHALL BE RATED FOR A MINIMUM OF 75 DEGREE CELSIUS.
21. ALL NEW AND MODIFIED ELECTRICAL EQUIPMENT, SUCH AS SWITCHBOARDS, PANELBOARDS, INDUSTRIAL CONTROL PANELS, METER SOCKET ENCLOSURES, AND MOTOR CONTROL CENTERS THAT ARE LIKELY TO REQUIRE EXAMINATION, ADJUSTMENT, SERVICING, OR MAINTENANCE WHILE ENERGIZED SHALL BE FIELD MARKED TO WARN QUALIFIED PERSONS OF POTENTIAL ELECTRIC ARC FLASH HAZARD. THE FIELD LOCATION SHALL BE CLEARLY VISIBLE TO QUALIFIED PERSONS BEFORE EXAMINATION, ADJUSTMENT, SERVICING, OR MAINTENANCE OF THE EQUIPMENT.



ISSUE	DATE
CONSTRUCTION DOCUMENTS	11/10/23
MEP JOB:	22336
DESIGNED:	KSP
CHECKED:	RCC

E3.0

STRUCTURAL NOTES

Governing Codes and Standards:

- A. 2018 International Building Code (and local amendments)
- B. "Minimum Design Loads for Buildings and Other Structures" - ASCE 7-16
- C. "Steel Construction Manual" - AISC Fourteenth Edition
- D. "Building Code Requirements for Structural Concrete" - ACI318-14

Design Loads

1. Building Risk Category:

A. II

2. Handrail Load:

- A. Point Load 200 lb
- B. Distributed Load 50 lb/ft

Project General Notes

A. Material and design specifications cited herein shall be those conforming with the version of the applicable specification or code most recently adopted by the permitting authorities. These structural notes are to be used as a supplement to the specifications, unless noted otherwise.

B. Refer to the architectural documents for all dimensions not shown on the structural contract documents. Do no scale the structural contract documents.

C. The general contractor shall verify all dimensions, elevations, and conditions with architectural, mechanical, electrical, plumbing, and civil drawings and notify the architect/engineer of any discrepancies or inconsistencies.

D. The size, weights and locations of all equipment pads, roof mounted mechanical units, and penetrations required for mechanical, electrical, and plumbing work shall be verified by the contractor. All penetrations are subject to approval by the architect/engineer.

E. Any contractor inducing loads on the structure not specified on the contract documents must obtain approval from the architect/engineer prior to erection. Field alterations for any structural member shall not be executed without approval from the architect/engineer

F. Architect/engineer's approval shall be secured for all substitutions.

G. The structure and all of its parts must be adequately braced against wind, lateral earth, and seismic forces until the permanent lateral-force resisting systems have been constructed and all of its parts have been installed.

H. Shop drawings, vendor drawings, or any material prepared and submitted by the contractor or subcontractor are not considered part of the structural contract documents. Any engineering design provided by others and submitted for review shall bear the seal of an engineer registered in the state where the project is being built.

I. During construction the contractor may encounter existing conditions which were not known during design or are at variance with the project documentation. Such conditions may interfere with new construction, require protection and/or support of existing work, or may consist of damaged or deterioration of structural materials/components which could jeopardize the structural integrity of the building. The contractor shall notify the engineer of record of all discoveries he believes may interfere with proper execution of the work or jeopardize the integrity of the building prior to proceeding with work related to such discoveries.

J. The structural engineer shall not have control or charge of and shall not be responsible for construction means, methods, techniques, sequences, procedures, nor site safety.

K. The structural drawings have been prepared using available information regarding the existing conditions. No attempt has been made to verify any existing conditions against information provided by others. The contractor shall compare the existing documents and notify the architect of any differences before proceeding with work.

L. Items, in the opinion of the contractor, that appear to be deficiencies, omissions, contradictions, or ambiguities in the plans and / or specifications shall be brought to the attention of the structural engineer. Plans and / or specifications will be corrected or written interpretations of the alleged deficiency, omission, contradiction or ambiguity will be made by the structural engineer. Work shall not proceed in these areas before a response is received from the structural engineer.

M. All products and materials used by the contractor shall be installed in strict accordance with the manufacturer's instructions.

N. The general contractor shall determine from the local building official when the permit is obtained whether any letters of construction compliance will be requested from the structural engineer; if so, the contractor shall notify the engineer in writing before the start of construction.

O. Exterior roofs, flashing, ledges, concrete, & other surfaces shall slope min. 1/4"12 to prevent water ponding. Landings shall also slope max. 1/4"12 to prevent slipping. Covered garages or carports floor surface shall slope min. 1/8"12 to provide positive drainage to drain, unless surfaced with asphalt.

P. All work connected with this project by any trade involved shall be of the highest quality attainable in accordance with the professional practice of the trade.

Concrete – Cast-in-Place

A. Structural concrete shall be type I, and have a minimum 28 day strength of 4,000 psi, exterior concrete slabs shall be type I and have a minimum 28 day strength of 5,000 psi. All concrete shall have a min 6% (+/- 1.5%) entrained air for durability and a 4" (+/- 1") slump. The maximum aggregate size shall be 3/4". Concrete shall not be placed on frozen ground and shall be protected from freezing for a minimum of 7 days. During cold weather the methods and specifications set forth in ACI318-14 shall be followed to prevent frost damage.

B. All concrete work shall conform to the requirements of ACI318-14 and 301, latest edition.

C. All exposed edges shall have a 3/4" chamfer.

D. Concrete shall be adequately consolidated/vibrated during placement to ensure it is thoroughly placed around all reinforcing steel and embedded fixtures.

E. Unless noted otherwise, slabs, footings, and walls shall not have any horizontal 'cold joints.' All construction joints shall be detailed or reviewed by the engineer of record.

F. Interior concrete slab finish shall be steel trowel finished and exterior concrete slabs shall be broom finished.

G. All concrete shall be normal weight aggregate unless noted otherwise.

H. Concrete topping for metal decks shall not include any add mixtures containing chloride salts.

I. All lightweight aggregate concrete shall have a maximum unit weight of 110 pcf.

Concrete Reinforcing Steel:

A. Reinforcing bars shall conform to ASTM spec. A615-79 and shall be grade 60.

B. At splices, lap bars a minimum of 3B diameters. At corners and intersections, make horizontal continuous or provide matching corner bars. Around openings in walls and slabs, provide (2) #5 bars extending a minimum of 2 feet beyond the edge of any openings in concrete walls and slabs which are greater than 1'-6" in any direction. Continuous top bars in walls shall be spliced at mid-span. Continuous bottom bars in walls shall be spliced at supports.

C. Welded wire fabric shall conform to ASTM 185 and shall be lapped one full mesh at splices and tied together.

D. Concrete reinforcing steel shall conform with ASTM A615 deformed grade 60 (weldable reinforcement shall be ASTM A706, grade 60) unless noted otherwise.

E. Place 2'-0" x 2'-0" bars at corners and intersections for walls and foundations equal in size and number to horizontal reinforcing, unless notes otherwise.

F. All reinforcing steel shall be detailed, fabricated and placed in accordance with ACI detailing manual 315.

G. All reinforcing steel shall be accurately and securely placed.

H. Minimum cover from concrete surfaces to reinforcing steel shall conform to ACI318-14, 7.7 unless a greater cover is required and shall be:

- 1. 3" to bottom of footing/grade beams cast against earth
- 2. 2" to earth face or exposed face of wall for No. 6 bar & greater
- 3. 1 1/2" to earth face or exposed face of wall for No. 5 bar & smaller
- 4. 1 1/2" to inside face of wall
- 5. 1 1/2" to inside faces of main beams and columns
- 6. 1" to top and bottom of concrete slab surfaces of slab-on-grade

I. Start first rebar 3" in from the edge, where slab rebar is called out as On-Center (O.C.) spacing.

J. All welded wire fabric shall maintain a minimum lap splice of 6".

K. Install rebar chairs with appropriate material for anticipated concrete exposure.

L. Concrete foundation walls shall be dampproofed on the exterior surface with either bituminous material, acrylic modified cement (3 lb/sq. yard), or surface-bonding mortar (1/8" thick), per IBC 1805.2.2

Post-Installed Anchors

A. Expansion anchors shall be ICC-approved (zinc plated in accordance with ASTM B633, hot-dipped galvanized in accordance with ASTM A153, AISI 304 stainless steel) and conform with F5-S-325, group II, type 4, class 1.

B. Expansion bolts called for on the drawings shall be Simpson "Weg-All", "Strong-Bolt 2" or approved wedge type anchors with the following minimum embedment's: 3/4" diameter bolts - 3 3/4", 1/2" diameter bolts - 2 3/4", 1/2" diameter bolts - 2 1/4".

C. Adhesive anchors shall be ICC-approved and shall consist of all-thread anchor rod, nut, washer and adhesive capsule. Anchor rods shall comply with ASTM A307. (not used at PT slabs).

D. All epoxy shall be Simpson "Set-XP" and shall be installed per the "Anchoring and Fastening Systems for Concrete and Masonry" Simpson Catalog #C-A-2018 by a qualified personnel.

E. Heavy duty screw anchors shall be stainless steel: Simpson Titen HD or approved equal.

Structural Steel and Miscellaneous Iron

A. Structural steel shall be detailed and fabricated in accordance with the latest version of the AISC manual of steel construction.

B. All bolts, including anchor bolts, shall conform to ASTM spec. A307.

C. Structural steel rolled shapes, including plates and angles, shall be ASTM spec. A570, gr. 50ksi.

D. Field welded connections must be inspected by the engineer of record.

E. Fillet welds indicated on the plans shall be of E70xx electrodes and shall be the minimum size specified in the AISC manual of steel construction, table J2.4. All other welds shall be made with E70xx electrodes.

F. All welding shall conform to AWS specifications and shall be performed by a certified welder under AWS specifications.

G. Steel shall be thoroughly cleaned of mill scale prior to application of the primer in accordance with SSPC SP-3.

H. All steel plates and angles in contact with concrete and exposed to weather shall have a protective coating

I. Shop and erection drawings shall be submitted for engineers review prior to fabrication. Fabricator proceeds at his own risk without receipt of above review.

J. The contractor shall coordinate with the mechanical location of all openings

K. All fabrication, erection, identification and painting of structural steel shall conform to AISC specifications.

L. Anchor rods are to be located by means of a template. Do not hand set or wet set.

M. Anchor rods and embedded items shall be set in accordance with the code of standard, practice section 7.5.

N. All bolts shall be snug tight, unless noted otherwise on the plans.

O. Anchor bolts shall conform with ASTM A307 or F1554 and shall be provided with plate washers and heavy hex nuts. Bolts in contact w/ pressure treated material or are exterior bolts shall be galvanized in accordance with ASTM A153, class C. Nuts shall be over-tapped to class 2A fit before galvanizing, in accordance with ASTM A563. Bolt heads or nuts bearing on sloping flanges shall be equipped with beveled washers.

STRUCTURAL SHEET SCHEDULE	
SHEET	CONTENTS
S-0	STRUCTURAL NOTES
S-1	SITE PLAN & VICINITY MAP
S-2	TYPICAL RAILING SECTIONS & ELEVATIONS

ABBREVIATIONS LIST			
ABV	ABOVE	MAX	MAXIMUM
ALT	ALTERNATE/ALTERNATING	MECH	MECHANICAL
ARCH	ARCHITECT/ARCHITECTURAL	MIN	MINIMUM
BO	BOTTOM OF	OC	ON CENTER
BOT	BOTTOM	OSB	ORIENTED STRAND LUMBER
C	CENTER LINE	PERP	PERPENDICULAR
CMU	CONCRETE MASONRY UNIT	P	PLATE
COL	COLUMN	PLUM	PLUMBING
CONC	CONCRETE	PLYWD	PLYWOOD
CONT	CONTINUOUS	PSL	PARALLEL STRAND LUMBER
DBL	DOUBLE	REINF	REINFORCEMENT/REINFORCING
DF	DOUGLAS FIR	REQ	REQUIRED
DIA	DIAMETER	SBW	STEP BOTTOM OF WALL
Ø	DIAMETER	SCH	SCHEDULE
DWG	DRAWING	SCHED	SCHEDULE
EA	EACH	SIM	SIMILAR
ELEV	ELEVATION	SPF	SPRUCE-PINE-FIR
EOR	ENGINEER OF RECORD	STRUCT	STRUCTURE/STRUCTURAL
EW	EACH WAY	T&B	TOP AND BOTTOM
EXT	EXTERIOR	T&G	TONGUE AND GROOVE
FTG	FOOTING	THRU	THROUGH
GL	GLUE-LAMINATED BEAM	TRTD	PRESERVATIVE TREATED
GT	GIRDER TRUSS	TYP	TYPICAL
IBC	INTERNATIONAL BUILDING CODE	UNO	UNLESS NOTED OTHERWISE
IRC	INTERNATIONAL RESIDENTIAL CODE	VIF	VERIFY IN FIELD
INT	INTERIOR	w/	WITH
LSL	LAMINATED STRAND LUMBER	WD	WOOD
LVL	LAMINATED VENEER LUMBER	WWF	WELDED WIRE FABRIC

WELD LEGEND	
	= WELD ALL AROUND
	= FIELD WELD
	= FILLET WELD
	= FLARE BEVEL WELD
	= BEVEL WELD (FULL PENETRATION OR COMPLETE PENETRATION WELD)



ISSUE DATES		
12	. 21 . 22	CONCEPTUAL DESIGN
01	. 06 . 23	COORDINATION SET
01	. 16 . 23	100% DESIGN SET
02	. 08 . 23	BID DOCUMENTS

DRAWN BY: RPM
REVIEWED BY: JEM
PROJECT # 22084

STRUCTURAL
NOTES

S-0

SITE PLAN NOTES

1. NOT A CERTIFIED PLAT - BASED ON A SURVEY BY BASELINE ENGINEERING DATED: 12.20.22

2. Re: BASELINE ENGINEERING PLANS FOR FULL SITE PLAN DRAWINGS

3. CONTRACTOR IS RESPONSIBLE FOR PROVIDING SHOP DRAWINGS BASED ON CONDITIONS PRESENT IN FIELD FOR SEAD APPROVAL PRIOR TO FABRICATION OF RAILINGS

GUARDRAIL PAINTING NOTES


1. NO FIELD WELDING OF RAILING AFTER FINISHES ARE APPLIED.

2. COLOR OF NEW RAILING SHALL MATCH EXISTING RAILING PRESENT @ TORIAN PLUM



3. STEEL RAILING SHALL BE COATED WITH A MINIMUM OF 2.0 MILS OF APPROVED CARDINAL PAINT PRIMER PRIOR TO FINISH COATING, SEAD TO APPROVE ALL SUBSTITUTIONS

4. STEEL TOP COATING SHALL BE MINIMUM 2.5 MILS OF APPROVED CARDINAL PAINT, SEAD TO APPROVE ALL SUBSTITUTIONS

5. FOLLOW ALL INSTRUCTIONS ON CARDINAL PAINT PRODUCT TECHNICAL DATA SHEETS & INDUSTRY BEST PRACTICES



NOTE:
CONTRACTOR IS RESPONSIBLE FOR PROVIDING SHOP DRAWINGS TO SEAD FOR APPROVAL PRIOR TO FABRICATION OF RAILINGS FOR ALL PANEL SECTIONS



SEAD

STEAMBOAT ENGINEERING AND DESIGN, INC.

2740 Acre Lane Suite 'E' Steamboat Springs, CO 80487
Phone: 970.871.9101 Fax: 970.871.9089
E-mail: Jake@seadinc.com

SKI TIME TURNAROUND

SKI TIME SQUARE DRIVE
STEAMBOAT SPRINGS, COLORADO

A HANDRAIL DESIGN FOR:
CITY OF STEAMBOAT SPRINGS

ISSUE DATES	
12 . 21 . 22	CONCEPTUAL DESIGN SET
01 . 06 . 23	COORDINATION SET
01 . 16 . 23	100% DESIGN SET
02 . 08 . 23	BID DOCUMENTS

DRAWN BY: RPM
REVIEWED BY: JEM
PROJECT # 22084

SITE PLAN &
VICINITY MAP

GUARDRAIL PAINTING NOTES


1. NO FIELD WELDING OF RAILING AFTER FINISHES ARE APPLIED.

2. COLOR OF NEW RAILING SHALL MATCH EXISTING RAILING PRESENT @ TORIAN PLUM

3. STEEL RAILING SHALL BE COATED WITH A MINIMUM OF 2.0 MILS OF APPROVED CARDINAL PAINT PRIMER PRIOR TO FINISH COATING, SEAD TO APPROVE ALL SUBSTITUTIONS

4. STEEL TOP COATING SHALL BE MINIMUM 2.5 MILS OF APPROVED CARDINAL PAINT, SEAD TO APPROVE ALL SUBSTITUTIONS

5. FOLLOW ALL INSTRUCTIONS ON CARDINAL PAINT PRODUCT TECHNICAL DATA SHEETS & INDUSTRY BEST PRACTICES



3

TYPICAL POST BASE PLATE

CONTRACTOR TO VERIFY QUANTITY IN FIELD
PROVIDE 3/8" Ø HOLES FOR 3/8" Ø BOLTS
1/4" THICK STEEL PLATE


SCALE: 1 1/2" = 1'-0"



4

PROPOSED RAILING COLOR

SCALE: N.T.S.



1

TYPICAL RAILING SECTION

SCALE: 1 1/2" = 1'-0"

NOTE:
CONTRACTOR IS RESPONSIBLE FOR PROVIDING SHOP DRAWINGS TO SEAD FOR APPROVAL PRIOR TO FABRICATION OF RAILINGS FOR ALL PANEL SECTIONS

2

TYPICAL RAILING ELEVATION

NOTE: THIS ELEVATION IS TYPICAL FOR ALL PANEL SECTIONS

SCALE: 1 1/2" = 1'-0"



SEAD

STEAMBOAT ENGINEERING AND DESIGN, INC.

2740 Acre Lane Suite 'E' Steamboat Springs, CO 80487
Phone: 970.871.9101 Fax: 970.871.9089
E-mail: Jake@seadinc.com

SKI TIME TURNAROUND

SKI TIME SQUARE DRIVE
STEAMBOAT SPRINGS, COLORADO

A HANDRAIL DESIGN FOR:
CITY OF STEAMBOAT SPRINGS

ISSUE DATES		
12 . 21 . 22	CONCEPTUAL DESIGN SET	
01 . 06 . 23	COORDINATION SET	
01 . 16 . 23	100% DESIGN SET	
02 . 08 . 23	BID DOCUMENTS	

DRAWN BY: RPM
REVIEWED BY: JEM
PROJECT # 22084
TYPICAL RAILING SECTIONS & ELEVATIONS

S-2