

Proudly Serving Rural Routt County * City of Steamboat Springs * Town of Hayden * Town of Oak Creek * Town of Yampa * Routt County School

Date: 08/11/2021

Number of Stories: 2

Occupant Load: <10

Type of Construction: Type V-B

08/11/2021

✓ Items noted below do not require a response or comment back during the Plan Review in order for us to approve this permit. The Items below are required and will be checked by field inspectors. Please take time to review these items in advance of starting any work to ensure your project is ready for inspection.

- 1. Separate Electrical Plumbing Permits must be applied for and obtained prior to any work being done within these trades. Note Electrical and Plumbing trades are protected by the State, Licensed Contractors must apply and perform this work on all Commercial Properties, and additionally their employees working on these projects must be registered or licensed with the State of Colorado and work directly under Licensed Individual managing the project.
 - On Residential Properties owners are allowed to apply for the permit and perform their own Electrical and Plumbing work if this is their primary residence and they sign and complete our Home Owner Agreement form.
- 2. Separate Mechanical Permits must be applied for and obtained prior to any work being done within this trade. Mechanical Contractors must be registered and approved by the Routt County Regional Building Department.
- 3. The adopted codes in Routt County are the 2018 ICC model codes to include APPENDIX F

RADON CONTROL METHODS. The components of a passive submembrane depressurization system shall be installed during construction but this does not mean you have to install the full system, just through the Soil-gas-retarder.

- 4. Deferred Submittal: In buildings with crawl space foundations, the crawl space must be sealed in a deferred submittal provide additional information on how the Crawl Space area will meet Section R408 of the IRC. Please resubmit information on how you intend to meet this section.
- 5. Deferred Submittal Required: Heat Load Calculations and heating information for the new construction must be submitted prior to Electrical, Plumbing, and Mechanical Permits being issued.
- 6. Deferred Submittal Required: Stamped Truss Drawings to be provided for review and approval by RCRBD prior to trusses being set and inspections being done.
- 7. Deferred Submittal: Applicant to provide information on how Whole House Ventilation requirements will be met in accordance with IEEC R403.6 and 403.6.1 and IRC M1507.3.
- 8. Deferred Blower Door Test Certificate of Compliance: The building or dwelling unit (except within the Town of Hayden) must complete a Blower Door Test with a passing score of Equal/Less than 3 air changes per hour (3ACH), this certificate must be present for our Inspectors prior to approval of a Temporary Certificate of Occupancy/ Certificate of Occupancy. Please also upload this Blower Door Certificate to the Building Department Permit Record, or email this to our staff and they will upload the document.
- 9. The Routt County Building Department has developed the Residential Private Garage Floor Drain Policy. This Policy outlines the regulations per Jurisdiction on private residential garage floor drains throughout Routt County, ask Routt County personnel for policy.
- 10. Anchored masonry veneer installed over a backing of wood or cold-formed steel shall meet the requirements of Section R703.8., see attached handout. Adhered masonry veneer shall be installed in accordance with the requirements of Section R703.12, see R703.7.2.1 Weep screeds and R703.7.3 Water-resistive barriers.
- 11. <u>R308 Glazing</u>. Except as indicated in Section R308.1.1, each pane of glazing installed in hazardous locations as defined in SectionR308.4 shall be provided with a manufacturer's or installer's label, designating the type and thickness of glass and the safety glazing standard with which it complies, which is visible in the final installation. The label shall be acid etched, sandblasted, ceramic-fired, embossed mark, or shall be of a type which once applied cannot be removed without being destroyed. Exceptions: Tempered spandrel glass may be identified by the manufacturer with a removable paper label.
- 12. Fenestration U-factors windows and doors less than or equal to 0.30 will be required. This will apply for all glazing in windows and doors. The builder shall leave the National Fenestration Rating Council (NFRC) labels on all windows and doors with glazing at time of rough inspections so inspectors can verify the glazing requirements.
- 13. Bath Exhaust ducts if ran in unconditioned space must be done in insulated duct.
- 14. <u>R321.1 Premises identification</u>. Approved numbers or addresses shall be provided for all new buildings in such a position as to be plainly visible and legible from the street or road fronting the property.
- 15. While there are exceptions, floor assemblies that are not required elsewhere in this code to be fire-resistance rated, shall be provided with a 1/2-inch (12.7 mm) gypsum wallboard membrane, 5/8-inch (16 mm) wood structural panel membrane, or equivalent on the underside

of the floor framing member. Penetrations or openings for ducts, vents, electrical outlets, lighting, devices, luminaires, wires, speakers, drainage, piping and similar openings or penetrations shall be permitted as per R302.13 Fire protection of floors.

- 16. R316.4 Thermal barrier. Unless otherwise allowed in Section R316.5, foam plastic shall be separated from the interior of a building by an approved thermal barrier of not less than 1/2-inch (12.7 mm) gypsum wallboard, 23/32-inch (18.2 mm) wood structural panel or a material that is tested in accordance with and meets the acceptance criteria of both the Temperature Transmission Fire Test and the Integrity Fire Test of NFPA 275.
- 17. R316.5.4 Crawl spaces. The thermal barrier specified in Section R316.4 is not required where all of the following apply:
 - 1. Crawl space access is required by Section R408.4.
 - 2. Entry is made only for purposes of repairs or maintenance.

3. The foam plastic insulation has been tested in accordance with Section R316.6 or the foam plastic insulation is protected against ignition using one of the following ignition barrier materials:

- 3.1. 1 1/2-inch-thick (38 mm) mineral fiber insulation;.
- 3.2. 1/4-inch-thick (6.4 mm) wood structural panels;.
- 3.3. 3/8-inch (9.5 mm) particleboard;.
- 3.4. 1/4-inch (6.4 mm) hardboard;.
- 3.5. 3/8-inch (9.5 mm) gypsum board; or.
- 3.6. Corrosion-resistant steel having a base metal thickness of 0.016 inch (0.406 mm).

3.7. 1/4-inch (6.4 mm) fiber-cement panel, soffit or backer board.

Similarly, the ignition barrier is not required in attics where the foam plastic insulation has been tested in accordance with Section R316.6.

18. SECTION R314 SMOKE ALARMS

R314.1 General. Smoke alarms shall comply with NFPA 72 and Section R314.

R314.1.1 Listings. Smoke alarms shall be listed in accordance with UL 217. Combination smoke and carbon mon-oxide alarms shall be listed in accordance with UL 217 and UL 2034.

R314.2 Where required. Smoke alarms shall be provided in accordance with this section.

R314.2.1 New construction. Smoke alarms shall be pro-vided in dwelling units.

R314.3 Location. Smoke alarms shall be installed in the following locations:

- 1. In each sleeping room.
- 2. outside each separate sleeping area in the immediate vicinity of the bedrooms.

3. on each additional story of the dwelling, including basements and habitable attics and not including crawl spaces and uninhabitable attics. In dwellings or dwelling units with split levels and without an intervening door between the adjacent levels, a smoke alarm installed on the upper level shall suffice for the adjacent lower level provided that the lower level is less than one full story below the upper level.

4. Smoke alarms shall be installed not less than 3 feet (914 mm) horizontally from the door or opening of a bathroom that contains a bathtub or shower unless this would prevent placement of a smoke alarm required by Section R314.3.

SECTION R315

CARBON MONOXIDE ALARMS

R315.1 General. Carbon monoxide alarms shall comply with Section R315.

R315.1.1 Listings. Carbon monoxide alarms shall be listed in accordance with UL 2034. Combination carbon monoxide and smoke alarms shall be listed in accordance with UL 2034 and UL 217.

R315.2 Where required. Carbon monoxide alarms shall be provided in accordance with Sections R315.2.1 and R315.2.2.

R315.2.1 New construction. For new construction, car-bon monoxide alarms shall be provided in dwelling units where either or both of the following conditions exist.

1. The dwelling unit contains a fuel-fired appliance.

2. The dwelling unit has an attached garage with an opening that communicates with the dwelling unit.

R315.3 Location. Carbon monoxide alarms in dwelling units shall be installed outside of each separate sleeping area in the immediate vicinity of the bedrooms. Where a fuel-burning appliance is located within a bedroom or its attached bath-room, a carbon monoxide alarm shall be installed within the bedroom.

R315.4 Combination alarms. Combination carbon monoxide and smoke alarms shall be permitted to be used in lieu of carbon monoxide alarms.

R315.5 Power source. Carbon monoxide alarms shall receive their primary power from the building wiring where such wiring is served from a commercial source and, where primary power is interrupted, shall receive power from a battery. Wiring shall be permanent and without a disconnecting switch other than those required for overcurrent protection. Exceptions:

1. Carbon monoxide alarms shall be permitted to be battery operated where installed in buildings without commercial power.

2. Carbon monoxide alarms installed in accordance with Section R315.2.2 shall be permitted to be battery powered.

Reviewed by: <u>Ted Allen</u> Date: August 11, 2021



Proudly Serving Rural Routt County * City of Steamboat Springs * Town of Hayden * Town of Oak Creek * Town of Yampa * Routt County School Districts

Exterior Walls (Lath and Veneer Substrate) 2015 – IRC Section 703 - residential 2015 – IBC Section 1405 - commercial

<u>R703.1 General</u>. Exterior walls shall provide the building with a weather-resistant exterior wall envelope. The exterior wall envelope shall include flashing as described in Section R703.4. **Exception:** Log walls designed in accordance with provisions of ICC 400.

<u>R703.1.1 Water Resistance</u> The exterior wall envelope shall be designed and constructed in a manner that prevents the accumulation of water within the wall assembly by providing a water-resistant barrier behind the exterior cladding as required by Section R703.2 and a means of draining to the exterior water that penetrates the exterior cladding.

<u>R703.7 Exterior plaster (stucco)</u>.Installation of exterior plaster shall be in compliance with ASTM C 926 and ASTM C 1063 and the provisions of this code.

<u>R703.7.1 Lath</u>. Lath and lath attachments shall be of corrosion-resistant materials. Expanded metal or woven wire lath shall be attached with a 1 ½ inch-long (38mm) 11-gage nails having a 7/16 - inch (11.1 mm) head, or 7/8 inch long (22.2 mm), 16-gage staples, spaced not more than 6 inches (152mm) or as otherwise approved .

Exception: Lath is not required over masonry, cast-in-place concrete, precast concrete or stone substrates prepared in accordance with ASTM 1063

<u>R703.7.2 Plaster</u>. Plastering with cement plaster shall be in accordance with ASTM C926. Cement materials shall be in accordance with one of the following:

- 1. Masonry cement conforming to ASTM C91 Type M,S or N
- 2. Portland cement conforming to ASTM C150 Type I,II or III
- 3. Blended hydraulic cement conforming to ASTM C595 Type IP, IS (<70), IL, or IT (S<70)
- 4. Hydraulic cement conforming to ASTM C1157 Type GU, HE, MS, HS, or MH
- 5. Plastic (stucco) cement conforming to ASTM C1328

Plaster shall be not less than three coats where applied over metal or wire lath and shall be not less than two coats where applied over masonry, concrete, pressure-preservative-treated wood or decay-resistant wood as specified in R317.1 or gypsum backing If the plaster surface is completely covered by veneer or other facing material or is completely concealed, plaster application need only be two coats, provided the total thickness is as set forth in Table R702.1(1).

On wood-frame construction with an on-grade floor slab system, exterior plaster shall be applied to cover, but not extend below, lath, paper and screen.

ROUTT County Regional Building Department

136 6th Street, Ste 201, Steamboat Springs, CO 80487 PH: 970-870-5566 Fax 970-870-5489 Email: Building@co.routt.co.us

Exterior Walls (Lath and Veneer Substrate) 2015 – IRC Section 703 - residential 2015 – IBC Section 1405 - commercial

R703.8.3 Lintels. As per local amendment, masonry veneer shall not support any vertical load other than the dead load of the veneer above. Veneer above openings shall be supported on lintels of noncombustible materials. The lintels shall have a length of bearing not less than 4 inches (102mm). Steel lintels over openings or steel lintels that are less than 4 inches (102mm) above finished grade shall be shop coated with a rust-inhibitive pain, except for lintels made of corrosion resistance steel or steel treated with coating to provide corrosion resistance. Construction of openings shall comply with either Section R703.8.3.1 or 703.8.3.2.

R703.8 Anchored stone and masonry veneer, general. Anchored Stone and masonry veneer shall be installed in accordance with Chapter 7, Table R703.3(1) and figure R703.8 These veneers installed over a backing of wood or cold framed steel shall be limited to the first story above grade plane and not exceed 5 inches (127mm) in thickness. See section R602.10 for wall bracing requirements for masonry veneer for wood framed construction and Section R603.9.5 for wall bracing requirements for masonry veneer for cold-framed construction.



Figure R703.8 Typical Masonry Veneer Wall Details

Exterior Walls (Lath and Veneer Substrate)

2015 – IRC Section 703 - residential 2015 – IBC Section 1405 - commercial



Figure R703.8 Typical Masonry Veneer Wall Details

Exterior Walls (Lath and Veneer Substrate) 2015 – IRC Section 703 - residential 2015 – IBC Section 1405 - commercial

IBC Section 2510.6 Water Resistive Barriers Water resistive barriers shall be installed as required in section 1404.2 and, where applied over wood-based sheathing, shall include a water-resistive vapor-permeable barrier with a performance at least equivalent to two layers of water resistive barrier complying with ASTM E2556, Type I. The individual layers shall be installed independently such that each layer provides a separate continuous plane and any flashing (installed in accordance with 1405.4) intended to drain to the water resistive barrier is directed between the layers

IBC Section 1404.4 Flashing. Flashing shall be installed in such a manner so as to prevent moisture from entering the wall or to redirect that moisture to the exterior. Flashing shall be installed at the perimeters of exterior door and window assembly, penetrations and terminations of exterior wall assemblies, exterior wall intersections with roofs, chimneys, porches, decks, balconies and similar projections and at built-in gutters and similar locations where moisture can enter the wall. Flashing with projecting flanges shall be installed on both sides and the ends of copings, under sills and continuously above projecting trim. Where self-adhered membranes are used as flashings of fenestration in wall assemblies, those self-adhered flashings shall comply with AAMA 711. Where fluid applied membranes are used as flashing for exterior wall openings, those fluid membrane flashings shall comply with AAMA 714

IBC 1404.10 Adhered masonry veneer. Adhered masonry veneer shall comply with the applicable requirements in IBC Section 1405.10.1 and Sections 12.1 and 12.3 of TMS 402/ACI 530/ASCE 5.

*NOTE - RCRBD finds these requirements to be similar to cement plaster (stucco) applied to exterior walls and shall conform to similar requirements specified in Chapter 25.

*NOTE - Figure R703.8 (shown) illustrates a similar drainage system to include a weep screen at the bottom of exterior walls to permit the moisture to escape to the exterior of the building.



Figure R703.6(3) SCREED FOR EXTERIOR PLASTER ON STUD WALL AT SLAB (136 6th Street, Ste 201, Steamboat Springs, CO 80487 PH: 970-870-5566 Fax 970-870-5489 Email: <u>Building@co.routt.co.us</u>



т 4	EAGLES VISTA SUBDIVIS PROJECT DATA TABLE LO	T 4	steamboat Springs, CO 80487
	ZONE DISTRICT RN-2	PROPOSED PLAN	RCHITE 7/17/2/ 970.846.1700
	6,000sf Min	10,052 SF	Structural Engineer
	35% Max	2,773sf/10,052 = 27.6%	PCPRD Pecord Set
	NO LIMIT FOR RN-2	NA	KCKBD Record Set
	AVERAGE PLATE HEIGHT: 28.0' MAX HEIGHT: 40.0'	AVERAGE PLATE HEIGHT: VARIES MAX HEIGHT: 34.5'	I.A.
	15' MINIMUM / 20' GARAGE	40.0 PRINCIPAL, 25.09' GARAGE	
	10' MINIMUM	11.2' SOUTH LINE, 12.77 NORTH	
	10' MINIMUM	11.67'	00/11/2021
	ONE WITH 10,000 SF	1 PROPOSED	





1 CRAWLSPACE FLOOR PLAN



1863 RIVER QUEEN LLC

1863 RIVER QUEEN LN STEAMBOAT SPRINGS COLORADO

REV. DATE:	REV. NAME:	REV. NO.:

CRAWLSPACE FLOOR PLAN

date: 17 JULY 2021 scale: 1/4" = 1'-0"





(1) (A3.3)











1 UPPER LEVEL FLOOR PLAN A2.2 2272sf FINISHED 656sf COVERED DECK





1863 RIVER QUEEN LN STEAMBOAT SPRINGS COLORADO

REV. DATE:	REV. NAME:	REV. NO.

MAIN FLOOR PLAN

date: 17 JULY 2021 scale: 1/4" = 1'-0"





A A4.1

PROJECT NORTH







SECTION LOOKING WEST

1/4" =1'- 0"



1863 RIVER QUEEN LLC

1863 RIVER QUEEN LN STEAMBOAT SPRINGS COLORADO

REVISIONS :		
REV. DATE:	REV. NAME:	REV. NO.:
NOTES:		

SECTIONS

date: 17 JULY 2021 scale: 1/4" = 1'-0"

A3.1

















1863 RIVER QUEEN LLC

1863 RIVER QUEEN LN STEAMBOAT SPRINGS COLORADO

REV. DATE:	REV. NAME:	REV. NO
NOTES:		
SECI	IONS	
	V 2021	







1 1/2" =1'- 0"



	SCOTT MYLLER C-5015 SED ARCHITES	נכסיד איז
BE RIER DED NE INSUL	 - 3/4" FLOOR FINISH - RADIANT HEAT TUBE — 3/4" PLYWD SUBFLR — FOIL FACED R13 FIBERGLASS INSUL 	
FLOOR TYPE N	1 1/2" =1'- 0"	1863 RIVER QUEEN LLC
		1863 RIVER QUEEN LN STEAMBOAT SPRINGS COLORADO REVISIONS: REV. DATE: REV. NAME: REV. DATE: REV. NAME:
	DERTY LINE	
		SECTIONS date: 17 JULY 2021 scale: 1/4" = 1'-0"
		A3.4



PAD	SIZE	THICKNESS	REBAR	BEARING PLATE	CONNECTOR
Α	30 X 30	18	#4 @ 8" EA WAY DOUBLE MATT	E	
В					
С					
D					
Е					
F					
G					
н					
I					
J					
К					
L					
Μ					
Ν					
0					
Ρ					
Q					

S2

LOWER LEVEL FLOOR FRAMING PLAN

1/4" =1'- 0"

S2

STEAMBOAT SPRINGS COLORADO

REV. NO.:

LOWER FLOOR FRAMING PLAN

date: 17 JULY 2021 *scale*: VARIES

C

GENERAL STRUCTURAL NOTES - 2018 INTERNATIONAL RESIDENTIAL CODE

- **DESIGN LIVE & SNOW LOADS** a. ROOF, UNCOVERED DECK...75 psf snow
- b. FLOORS.....40 psf LL
- c. COVERED DECK.....60 psf LL
- c. WIND.....115 mph, Exp B
- d. SEISMIC.....SDS=0.33g S1=0.13g Group I Category II

FOUNDATION DESIGN

- a. Foundation design based on spread footings with a soil bearing pressure of 3000psf and a 700psf minimum dead load per NWCC soils report 17-10640 dated 9/5/2017. Retaining wall design based on equivualent fluid pressure of 55 pcf for onsite
- materials. Refer to soils report for additional recommendations.
- b. The owner should review the soils report for limitations and risks. All issues involving soils, settlement, drainage, & slope stability should be addressed to the soils engineer.
- c. The structural design is for the house and permanenent foundation only. Detached retaining walls including rock retaining walls are by others. The structural engineer is not responsible for slope stability, excavation, shoring, drainage, soils issues, or construction methods. The structural
- engineer's duties are limited to design only and is not project engineer.
- d. Not used
- e. The foundtion design & details depicted are conceptual in nature and show general structural requirements. Actual conditions will vary based on excavation and soils conditions encountered, as well as fit up of beams, beam pockets columns, and baseplates. Complete construction details are not part of this package. Contractor to provide concrete, rebar placement & steel shop shop drawings to engineer for approval depicting actual construction details.

(4) LL358

4'-5 ¹"

6'-0"

CANT

STRUCTURAL WOOD FRAMING

- a. Except where noted otherwise all lumber shall be
- Douglas Fir-Larch No. 2 or better.
- b. Except as noted otherwise minimum nailing shall be provided as specified in Table R602.3(1) Fastener Schedule of the IRC 2018 edition.
- c. Floor and roof sheathing shall be APA rated with exterior
- glue and graded in accordance with APA Standards.
- FLAT ROOF: 3/4" 48/24 8d@6 edge nail 8d@12 field nail SLOPED ROOF: 5/8" 40/20 8d@6 edge nail 8d@12 field nail
- FLOOR: 3/4"T&G 48/24 8d@6 edge nail 8d@12 field nail
- SHEAR WALL: 1/2" 24/10 8d@4 edge nail 8d@12 field nail d. Where light gage framing anchors are shown or required they shall be Simpson "Strong Tie" or equal ICBO approved connectors and shall be
- installed with the number and type of nails recommended by the manufacturer to develop the rated capacity. e. Glue laminated timber shall be of such stress grade to provide glue laminated
- beams with combination symbol 24F-V4. Beams in cantilevered or reverse bending shall be 24F-V8.
- f. Floor joists shall be plant fabricated I series with LVL wood flanges and plywood or OSB webs and carry ICBO approval for the composite section. Joists shall be designed to carry the full dead load and live loads of the floor and any other superimposed
- loads. Bridging and blocking shall be installed according to the fabricator's requirements. g. All timber logs to be Spruce-Fir-Pine No.2 or better per TPI (Timber Product Inspection
- Inc) Log Program Technical Guide dated 2/1/08. h. All microlam to be LVL 1.9E WS or equal, allowable bending stress 2600 psi
- and an allowable shear stress 285 psi. Nail 2 or 3 LVL's with 3 rows 16d @ 12, thru bolt 4 or more LVL's with 2 rows 1/2"@24, UNO.
- i. All rim board to be Timber Strand LSL 1 1/4" x 11 7/8" Grade 1.3 with allowable bending stress of 1700 psi and allowable shear stress of 400 psi parallel to grain.
- All Timber Strand LSL beams & rafters to be Grade 1.55 with allowable bending stress of 2325 psi and allowable shear stress of 310 psi parallel to grain.
- j. All Parrallam beams are PSL 2.0E to have allowable bending stress of 2900 psi and allowable shear stress of 290 psi.

k. All unlisted headers to be 2-2x8.

Parrallam columns are PSL 1.8E to have allowable compressive stress of 2500 psi parallel to grain.

CONCRETE

- a. Concrete to have a minimum compressive strength of 3000 psi and be
- reinforced with Grade 60 bar as noted on drawing.
- b. All bars continuous unless noted. Additional lap splices permitted with written approval only. All splices to be a minimum of 38 bar diameters.

BACKFILLING

a. Do not backfill against basement or retaining walls until supporting slabs and floor framing are in place and securely anchored.

STRUCTURAL STEEL

- a. All bolts, including anchor bolts, shall conform to ASTM Specification A307.
- b. Structural steel rolled shapes, including plates and angles shall be ASTM A36.
- Tube shapes shall conform to ASTM A500 Grade B, 46 ksi yield. Pipe shapes shall conform to ASTM A53 Grade B. c. Except as noted, expansion bolts shall be "WEG-IT", "RED HEAD", or approved wedge type with
- the following minimum embedments: 5/8" dia: 2", 1/2" dia: 1-1/2".
- d. Except as noted, all Type "HD" tiedowns to concrete shall be secured with 5/8"x10"
- e. Special Inspection by the structural engineer is required for all field welds.
- galvanized anchor bolts.

GENERAL

The contract structural drawings and specifications represent the finished structure. They do not indicate the method of construction. The contractor shall provide all measures necessary to protect the structure during construction. Such measures shall include, but not be limited to bracing and shoring for loads due to excavation, sliding soil, or construction equipment. Observation visits to the site by the structural engineer shall not include inspection of the above items, nor will the structural engineer be responsible for the contractor's means, methods, techniques, sequences for procedure of construction, or the safety precautions and the programs incident thereto.

THE STRUCTURAL DESIGN IS FOR THE HOUSE AND PERMANENT FOUNDATION ONLY. STABILITY OF THE HILLSIDE, BOTH LONG TERM AND DURING CONSTRUCTION IS BY OTHERS. CONTACT THE SOILS ENGINEER REGARDING SLOPE STABILITY PRIOR TO EXCAVATION. THE SOILS ENGINEER SHALL VERIFY THAT ALL CONCRETE IS PLACED ON ADEQUATE BEARING MATERIAL. ALL TEMPORARY OR PERMANENT SHORING IS BY OTHERS.

UPPER LEVEL FLOOR FRAMING PLAN

S3

HEADER SCHEDULE

A	(2) 2X10	SINGLE 2X6 TRIMMER
В	(3) 2X10	SINGLE 2X6 TRIMMER
\bigcirc	(2) 9 1/2 LVL	SINGLE 2X6 TRIMMER
D	(3) 9 1/2 LVL	DOUBLE 2X6 TRIMMER
E	(2) 11 7/8 LVL	DOUBLE 2X6 TRIMMER
F	(3) 11 7/8 LVL	DOUBLE 2X6 TRIMMER
G	(3) 14" LVL	TRIPLE 2X6 TRIMMER & DOUBLE 2X6 KINGS

1/4" =1'- 0"

date: 17 JULY 2021 scale: VARIES

(2) 2X10
(3) 2X10
(2) 9 1/2 LVL
(3) 9 1/2 LVL
(2) 11 7/8 LVL
(3) 11 7/8 LVL
(3) 14" LVL

SUBSOIL AND FOUNDATION INVESTIGATION LOCKHART SUBDIVISION AMA Eagles Visto RIVER QUEEN LANE STEAMBOAT SPRINGS, COLORADO

Prepared by

NWCC, Inc. 2580 Copper Ridge Drive Steamboat Springs, CO 80487

Prepared for

Kokee Kokee, LLC Ty Lockhart 830 Lincoln Avenue Steamboat Springs, CO 80847

NWCC Project NO. 17-10640

September 5, 2017

TABLE OF CONTENTS

1.0	CONCLUSIONS 1
2.0	PURPOSE AND SCOPE OF WORK1
3.0	PROPOSED CONSTRUCTION1
4.0	SITE CONDITIONS1
5.0	FIELD INVESTIGATION2
6.0	LABORATORY INVESTIGATION 2
7.0	SUBSURFACE CONDITONS 2
8.0	FOUNDATION RECOMMENDATIONS3
9.0	FLOOR SLAB RECOMMENDATIONS 4
10.0	PERIMETER DRAINAGE SYSTEM RECOMMENDATIONS6
11.0	FOUNDATION WALL AND RETAINING STRUCTURE RECOMMENDATIONS 6
12.0	SITE DRAINAGE RECOMMENDATIONS7
13.0	SITE GRADING RECOMMENDATIONS
14.0	PAVEMENT RECOMMENDATIONS8
15.0	LIMITATIONS10

List of Figures, Tables and Appendices.

Figure #1	Vicinity Map
Figure #2	Site Plan/Test Pit Locations
Figures #3 & #4	Logs of Exploratory Test Pits with Legend and Notes
Figures #5 - #7	Swell-Consolidation Test Results
Figure #8	Bearing Capacity Chart
Figure #9	Hung Partition Wall Detail
Figure #10	Perimeter/Underdrain Detail
Table 1	Summary of Laboratory Test Results

1.0 CONCLUSIONS

Based on results of the field and laboratory investigations, NWCC, Inc. (NWCC) recommends the proposed single-family residences and garages to be constructed within this subdivision be founded on footings placed on the natural sands and clays and/or natural sands and gravels encountered beneath the existing fill materials and the topsoil and organic materials.

2.0 PURPOSE AND SCOPE OF WORK

This report presents the results of the Subsoil and Foundation Investigation completed for the Lockhart Subdivision to be constructed within a vacant parcel of land located at the southwest end of River Queen Lane in Steamboat Springs, Colorado. The approximate location of the project site is shown in Figure #1.

The scope of our work included obtaining data from a visual inspection of the site; the excavation of seven (7) test pits; sampling of the soils and the laboratory testing of the samples obtained. This report summarizes the results of the field investigation and the laboratory test results, as well as our recommendations for foundation design, floor slabs, foundation walls, site grading and pavement sections based on the proposed construction and the subsurface conditions encountered.

3.0 PROPOSED CONSTRUCTION

NWCC understands the proposed construction will consist of six (6) single family residences within the subdivision. The lot sizes will range from 0.23 to 0.48 acres in size. NWCC has assumed the residences will consist of 1 to 2 story wood framed structures constructed with attached garages and walkout basement levels. NWCC has assumed the lower levels of the residences and garages will be constructed with concrete slab-on-grade floor systems. We have assumed the loads generated by the proposed building structures will be variable and range from light to moderate, typical of this type of residential construction.

Some overlot site grading, roadway and utility construction will be required. The majority of the grading will occur at the end of the existing cul-de-sac; at the west end of the property for the water quality detention pad; and cut and fill placement within a majority of the lot entrances. NWCC has assumed that the remaining cuts and fills constructed within each of the individual lots will be on the order of 5 to 15 feet or less to bring the sites to the finish grades.

4.0 SITE CONDITIONS

The project site is located at the southwest end of River Queen Lane in Steamboat Springs, Colorado. The site is bordered on the north, south and west by developed single and multi-family homes and on the east by existing townhomes.

Subsoil and Foundation Investigation	NWCC Job No. 17-10640
Lockhart Subdivision	September 5, 2017
Steamboat Springs, Colorado	Page 2 of 11

A majority of the site consists of vacant, undisturbed land that is vegetated with native grasses, weeds, scrub oaks and sage brush. Previous site grading, which appears to consist of fill placement on the order of 5 to 10 feet in depth, has occurred at and around the existing cul-de-sac.

The topography of the project site is variable and the central portion of the lot, where the road and pond will be constructed, sits on a ridgeline that slopes gently to strongly down to the west. The remainder of the property, proposed building lots and greenbelt area, generally slope moderately to steeply down to the south, southwest and northwest at 5 to 25 percent. Steeper natural slopes, greater than 30%, are situated along the southern and northern edges of the property. A maximum elevation difference of approximately 25 to 60 feet appears to exist at each of the lots.

5.0 FIELD INVESTIGATION

The field investigation for this project was conducted on August 18, 2017. Seven (7) test pits were advanced at the approximate locations shown in Figure #2. The test pits were excavated with a PC 138 trackhoe. The test pits were logged and samples were obtained at the time of excavation by an engineer from NWCC. Graphic logs of the exploratory test pits are shown in Figure #3 and #4 along with the associated Legend and Notes.

6.0 LABORATORY INVESTIGATION

Samples obtained from the test pits were examined and classified in the laboratory by the project engineer. Laboratory testing included standard index property tests including natural densities and moisture contents, dry unit weights, grain size analyses and liquid and plastic limits. Swell-consolidation testing was also conducted on relatively undisturbed samples of the natural sands and clays. Swell-consolidation test results are shown in Figures #5 to #7 and the results are discussed in the following section. The results of the laboratory testing are summarized in the Table #1 that follows the figures. Laboratory testing was conducted in general accordance with applicable ASTM specifications.

7.0 SUBSURFACE CONDITIONS

The subsurface conditions encountered in the test pits excavated across the proposed subdivision were highly variable and generally consisted of a layer of natural topsoil and organic materials or existing fill materials overlying natural sands and clays or sands and gravels to the maximum depth investigated, 12 feet beneath existing ground surface (bgs).

Natural topsoil and organic materials were encountered at the ground surface or beneath the existing fill materials in all of the test pits. The layers of topsoil and organic materials were approximately $1\frac{1}{2}$ to 3 feet in thickness. The natural topsoil and organic materials were silty dry to moist and dark brown to black in color.

Subsoil and Foundation Investigation	NWCC Job No. 17-10640
Lockhart Subdivision	September 5, 2017
Steamboat Springs, Colorado	Page 3 of 11

Sand and gravel fill materials were encountered at the ground surface in the central portion of the site (Test Pits 3 and 4) and beneath the proposed roadway and pond. The fill materials ranged from 4 ½ to 9 feet in thickness. The sand and gravel fill materials were silty to clayey, fine to coarse grained with cobbles and boulders, non to very low plastic, medium dense, slightly moist and brown in color. Samples of the fill materials classified as SM and GM soils in accordance with the Unified Soil Classification System (USCS).

Natural sands and clays were encountered below the natural topsoil and organic material and natural sands and gravels in all but two of the test pits. The sands and clays were fine to coarse grained with gravels, low plastic, very stiff to dense, moist to slightly moist and brown in color. Samples of the natural sands and clays classified as SC to CL soils in accordance with the USCS.

Sands and gravels were also encountered below the natural topsoil and organic materials and existing fill materials. The sands and gravels were clayey, fine to coarse grained with cobbles and boulders, low plastic, dense, dry to moist and brown to gray in color.

Swell-consolidation testing conducted on relatively undisturbed samples of the natural sands and clays indicate that the materials tested will exhibited a low swell potential when wetted under a constant load. The swell-consolidation test results are shown in Figures #5 through #7, and all of the other test results are summarized in the associated Table 1.

Groundwater seepage was not encountered in any of the test pits at the time of excavation and no signs of a seasonal high groundwater table were observed. It should be noted that the groundwater conditions at this site can be expected to fluctuate with precipitation and seasonal runoff.

Based on the subsurface conditions encountered at the site, the laboratory test results and our review of the available literature, NWCC recommends that a Site Class C be used for the foundation designs in accordance with Table 20.3-1 in Chapter 20 of ASCE 7-10.

8.0 FOUNDATION RECOMMENDATIONS

ς.

Based on the subsurface conditions encountered in the test pits, the results of the field and laboratory investigations and our assumptions regarding the proposed building construction, NWCC believes an economically feasible and safe type of foundation system is spread footings or individual pads with grade beams founded on the natural sand and clays and/or sands and gravels encountered below the topsoil and organic materials and any existing fill materials. The precautions and recommendations itemized below will not prevent the movement beneath the foundation if the underlying sands and clays swell. However, they should reduce the amount of differential movement beneath the foundation system.

1) Footings placed on the undisturbed natural sands and clays and/or sands and gravels should be designed using an allowable soil bearing pressure of 3,000 psf. Based on the swell-potential of

Subsoil and Foundation Investigation	NWCC Job No. 17-10640
Lockhart Subdivision	September 5, 2017
Steamboat Springs, Colorado	Page 4 of 11

the natural sands and clays, the footings should also be designed for a minimum dead load pressure of at least 700 psf. Increasing minimum dead load pressures will help reduce differential foundation movement if the sands and clays become wetted and swell.

- 2) Footings or pad sizes should be computed using the above soil pressures and placed on the natural undisturbed sands and clays and/or sands and gravels found beneath the existing topsoil and fill materials and any fill materials.
- 3) Any topsoil, as well as any existing fill materials or loose and soft natural soils encountered within the foundation excavations should be removed and the excavations extended to competent natural soils prior to concrete placement. The footings may have to be narrow or interrupted to maintain the minimum dead load. The foundation design should be closely checked to assure that it distributes the loads per the allowable pressures given.
- 4) Foundation walls should be designed and reinforced to span an unsupported distance of 10 feet or the length between pads, whichever is greater.
- 5) Footings or pads should be placed well enough below final backfill grades to protect them from frost heave. Forty-eight (48) inches is typical for this location considering normal snow cover and other winter factors.
- 6) Based on experience, we estimate the total settlement for footings and pads designed and constructed as discussed in this section will be approximately 1 inch. Additional bearing capacity values along with the associated settlements are presented in Figure #8.
- 7) We strongly recommend that the client retain NWCC to observe the foundation excavations when they are near completion to identify the bearing soils and confirm the recommendations in this report.

9.0 FLOOR SLAB RECOMMENDATIONS

NWCC has assumed the proposed residences and garages will be constructed with concrete slab-ongrade floor systems placed at varying depths across the site. The on-site soils, apart from the existing topsoil and organic materials, are capable of supporting slab-on-grade construction. However, floor slabs present a very difficult problem where swelling materials are present near floor slab elevation because sufficient dead load cannot be imposed on them to resist the uplift pressure generated when the materials are wetted and expand. Based on the moisture-volume change characteristics of the sands and clays encountered at this site, we recommend that structural floor systems over well-ventilated crawlspaces or void form be used in the proposed residences. .

If the client elects to construct concrete slab-on-grade floor systems, we recommend the following special design and construction precautions be followed so that the amount of movement in the floor slabs can be reduced, if the sands and clays become wetted.

- 1) Floor slabs should be separated from all bearing walls, columns and their foundation supports with a positive slip joint. We recommend the use of ½-inch thick cellotex or impregnated felt.
- 2) Interior non-bearing partition walls resting on the floor slabs should be provided with a slip joint, preferably at the bottom, so that in the event the floor slab moves, this movement is not transmitted to the upper structure. This detail is also important for wallboard and doorframes and is shown in Figure #9.
- 3) A minimum 6-inch gravel layer should be provided beneath all floor slabs to act as a capillary break and to help distribute pressures. Prior to placing the gravel, the excavation should be shaped so that if water does get under the slab, it will flow to the low point of the excavation. In addition, all of the topsoil and organic materials should be removed prior to placement of the underslab gravels or new structural fill materials.
- 4) Floor slabs should be provided with control joints placed a maximum of 12 feet on center in each direction to help control shrinkage cracking. The location of the joints should be carefully checked to assure that the natural, unavoidable cracking will be controlled. The depth of the control joints should be a minimum of ¼ the thickness of the slab.
- 5) Underslab soils should be kept as close as possible to their in-situ moisture content. Excessive wetting or drying of these soils prior to placement of the floor slab could result in differential movement after the slabs are constructed.
- 6) It has been our experience that the risk of floor slab movement can be reduced by removing at least 2 feet of the expansive materials and replacing them with a well compacted, non-expansive fill. If this is done, or if fills are required to bring the underslab soils to the desired grade, the fill should consist of non-expansive, granular materials. The fill should be uniformly placed and compacted in 6 to 8 inch lifts to at least 95% of the maximum standard Proctor density at or near the optimum moisture content, as determined by ASTM D-698/AASHTO T-99.

The above precautions and recommendations will not prevent floor slab movement in the event the sands and clays beneath the floor slabs undergo moisture changes. However, they should reduce the amount of damage if such movement occurs. The only way to eliminate the risk of all floor slab movement is to construct a structural floor over a well-vented crawl space or void form materials.

10.0 PERIMETER DRAINAGE SYSTEM RECOMMENDATIONS

Any floor levels or crawl space areas constructed below the existing or finished ground surfaces and the foundations should be protected by underdrain systems to help reduce the problems associated with surface and subsurface drainage during high runoff periods.

Localized perched water or runoff can infiltrate the lower levels of the structures at the foundation levels. This water can be one of the primary causes of differential foundation and slab movement. Especially, when expansive soils are encountered. Excessive moisture in crawl space areas or lower levels can also lead to rotting and mildewing of wooden structural members and the formation of mold and mold spores. Formation of mold and mold spores could have detrimental effects on the air quality in these areas, which in turn can lead to potential adverse health effects.

Drains should be located around entire perimeter of the lower levels and be placed and at least 12 inches below any floor slab or crawl space levels and at least 6 inches below the foundation voids and bottom of the foundation walls or footings. NWCC recommends the use of perforated PVC pipe for the drainpipe, which meets or exceeds ASTM D-3034/SDR 35 requirements, to minimize potential for pipe crushing during backfill operations. Holes in the drainpipe should be oriented down between 4 o'clock and 8 o'clock to promote rapid runoff of water. Drainpipe should be surrounded with at least 12 inches of free draining gravel and should be protected from contamination by a filter covering of Mirafi 140N subsurface drainage fabric or an equivalent product. Drains should have a minimum slope of 1/8 inch per foot and be daylighted at positive outfalls protected from freezing, or be led to sumps from which water can be pumped. The use of interior laterals, multiple daylights or sumps may be required for the proposed structure. Caution should be taken when backfilling so as not to damage or disturb the installed underdrains. NWCC recommends the drainage systems include a cleanout every 100 feet, be protected against intrusion by animals at outfalls and be tested prior to backfilling. NWCC also recommends the client retain our firm to observe the underdrain systems during construction to verify that they are being installed in accordance with recommendations provided in this report and observe a flow test prior to backfilling the system.

In addition, NWCC recommends an impervious barrier be constructed to keep water from infiltrating through the voided areas and/or under the foundation footings. Barrier should be constructed of an impervious material, which is approved by this office and placed below the perimeter drain and up against the sides of the foundation walls. A typical perimeter/underdrain detail is shown in Figure #10.

Placement of and impervious membrane and/or properly compacted clays in crawl space areas to the top of the footings or at least 12 inches above the top of the foundation voids or bottom of the foundation walls should help reduce the moisture problems in these areas.

11.0 FOUNDATIONS WALLS AND RETAINING STRUCTURE RECOMMENDATIONS

Foundation walls and retaining structures, which are laterally supported and can be expected to undergo only a moderate amount of deflection (at rest), may be designed for a lateral earth pressure computed on the basis of an equivalent fluid unit weight of 45 pcf for imported, free draining granular backfill and 55 pcf for the on-site soils.

Cantilevered retaining structures on the site can be expected to deflect sufficiently to mobilize the full active earth pressure condition. Therefore, cantilevered structures may be designed for a lateral earth pressure computed on the basis of an equivalent fluid unit weight of 35 pcf for imported, free draining granular backfill and 45 pcf for the on-site soils.

Foundation walls and retaining structures should be designed for appropriate hydrostatic and surcharge pressures such as adjacent buildings, traffic and construction materials. An upward sloping backfill and/or natural slope will also increase the earth pressures on foundation walls and retaining structures.

NWCC recommends imported granular soils for backfilling foundation walls and retaining structures because their use results in lower lateral earth pressures. The imported granular materials should be placed to within 2 to 3 feet of the ground surface. Imported granular soils should be free draining and have less than 7 percent passing the No. 200 sieve. The granular soils behind foundation and retaining walls should be sloped from the base of the wall at an angle of at least 45 degrees from the vertical. The upper 2 to 3 feet of fill should be a relatively impervious soil or pavement structure to prevent surface water infiltration into the backfill.

Wall backfill should be carefully placed in uniform lifts and compacted to at least 95 % of the maximum standard Proctor density and within 2% of the optimum moisture content. Care should be taken not to overcompact the backfill since this could cause excessive lateral pressure on the walls. Some settlement of deep foundation wall backfill materials will occur even if the material is placed correctly.

12.0 SITE DRAINAGE RECOMMENDATIONS

Proper surface drainage at these lots is of paramount importance for minimizing the infiltration of surface drainage into the wall backfill and bearing soils, which could result in increased wall pressures, differential foundation and slab movement. The following drainage precautions should be observed during construction and at all times after the structures have been completed:

- 1) Ground surface surrounding the structures should be sloped (minimum of 1.0 inch per foot) to drain away from the structure in all directions to a minimum of 10 feet. Ponding must be avoided. If necessary, raising the top of foundation walls to achieve a better surface grade is advisable.
- 2) Non-structural backfill placed around the structures should be compacted to at least 95% of the maximum standard Proctor density at or near the optimum moisture content in order to minimize future settlement of the fill. Backfill should be placed immediately after the braced foundation walls are able to structurally support the fill. Puddling or sluicing must be avoided.
- 3) Top 2 to 3 feet of soil placed within 10 feet of the foundations should be impervious in nature to minimize infiltration of surface water into the wall backfill.

NWCC, Inc.

- 4) Roof downspouts and drains should discharge well beyond the limits of all backfill. Roof overhangs, which project two to three feet beyond the foundations, should be considered if gutters are not used.
- 5) Landscaping, which requires excessive watering and lawn sprinkler heads, should be located a minimum of 10 feet from the foundation walls of the structures.
- 6) Plastic membranes should not be used to cover the ground surface adjacent to foundation walls.

13.0 SITE GRADING RECOMMENDATIONS

All fill materials placed beneath the interior floor slabs, exterior flat work, pavement areas, underground utilities and within the proposed pond should be compacted to at least 95 percent of the maximum standard Proctor density and within 2 percent of the optimum moisture content as determined in accordance with ASTM D698/AASHTO T99. The fills placed in these areas should not contain boulders, topsoil, organics or other deleterious substances. The fill materials placed in the landscaped areas should be compacted to at least 90 percent of the maximum standard Proctor density. The materials not suitable for use under the buildings and pavement areas should be placed in the bottom of the fills in landscaped areas, where some settlement can be tolerated.

Site grading should be carefully planned to provide positive surface drainage away from all the buildings and pavement areas. The buildings and pavement areas should be placed as high as possible on the sites so that positive drainage away from these structures can be provided. Surface diversion features should be provided around the paved areas to prevent surface runoff from flowing across the paved surfaces.

Although site grading plans for each of the lots were not available at the time of this report, we have assumed that cuts and fills of up to 5 to 15 feet in depth may be required to develop the individual lots. We recommend that the final fill slopes not exceed 2 (H) to 1 (V) configuration if they are properly compacted and drained. Positive surface drainage should be provided around all permanent cut and fill slopes to direct surface drainage away from the slope faces. All cut and fill slopes and other stripped areas should be protected against erosion by revegetation or other methods.

14.0 PAVEMENT RECOMMENDATIONS

Pavement section alternatives presented below are based on laboratory test results, assumed traffic loadings indicated below, pavement design procedures presented in the AASHTO Guide for Design of Pavement Structures and our experience with similar sites and conditions in the Steamboat Springs area. AASHTO pavement design procedures have been adopted and are used by the Colorado Department of Transportation (CDOT).

Based on the results of the field and laboratory investigations and our understanding of the proposed construction, it appears the materials to be encountered at proposed pavement subgrade elevations along

Subsoil and Foundation Investigation	NWCC Job No. 17-10640
Lockhart Subdivision	September 5, 2017
Steamboat Springs, Colorado	Page 9 of 11

River Queen Lane will likely consist of existing sand and gravel fill materials. These materials generally classified as SC to GC soils in accordance with the Unified Soil classification system and as A-4 to A-6 soils in accordance with the AASHTO classification system. These materials are generally considered to provide adequate to fair support for pavement structures. Using these classifications and our experience with similar soils, NWCC has correlated the soil classification to a modulus of subgrade reaction of 3,750 psi, which was used in the pavement design calculations.

NWCC recommends the pavement areas subjected to both automobile and truck traffic, such as the new along River Queen Lane be constructed with a composite pavement section consisting of at least 4 inches of asphalt placed over 4 inches of Class 6 aggregate base course and 8 inches of subbase materials consisting of Class 2 aggregate base course. Pavements for driveways and other areas subjected to automobile traffic only should receive a composite pavement section consisting of at least 3 inches of asphalt placed over 4 inches of Class 6 aggregate base course and 8 inches of at least 3 inches of asphalt placed over 4 inches of Class 6 aggregate base course and 8 inches of subbase materials.

NWCC recommends the areas subjected to heavy truck traffic turning movements, such as in the apron areas in front of the trash dumpster approach areas be paved with a rigid pavement section consisting of at least 7 inches of Portland cement concrete (PCC). Sidewalks subjected to pedestrian traffic should be paved using at least 4 inches of PCC and 5 inches in areas where occasional emergency or snow removal vehicle traffic is anticipated.

Prior to placement of subbase materials, NWCC recommends the exposed subgrade soils be uniformly mixed, moisture treated to within 2 % of the optimum moisture content and then be recompacted to at least 95 % of the maximum standard Proctor density. Depending on the time of year when subgrade preparation is considered, moisture conditioning including drying and/or moistening of subgrade materials will most likely be required in order to attain uniform compaction. NWCC also recommends that the properly moisture conditioned and recompacted subgrade soils be proofrolled with a loaded tandem dump truck prior to placing the subbase gravels. Areas exhibiting deflection and rutting will most likely require deeper stabilization. The depth and type of stabilization should be determined at the time of construction.

NWCC recommends the asphalt pavement material consist of an approved "Superpave" mix designed by a qualified, registered engineer. The mix design should be designed using the SX gradation and mixed with PG 58-28 oil or other performance graded asphaltic materials. The mix should be produced and placed by a qualified contractor and should be compacted to between 92 and 96 percent of the maximum theoretical (Rice) density. Quality control activities should be conducted on paving materials at the time of placement.

Base course materials should consist of a well-graded aggregate base course material that meets CDOT Class 6 ABC grading and durability requirements. Base course and subbase materials (Class 2 ABC) should be uniformly placed and compacted in 4 to 6-inch loose lifts to at least 95 % of the maximum modified Proctor density and within \pm 2% of the optimum moisture content as determined by ASTM D1557.

Subsoil and Foundation Investigation	NWCC Job No. 17-10640
Lockhart Subdivision	September 5, 2017
Steamboat Springs, Colorado	Page 10 of 11

Concrete pavement materials shall be based on a mix design established by a qualified engineer. Concrete should have a minimum 28-day compressive strength of 4,500 psi, be air entrained with approximately 6 percent air and have a maximum water/cement ratio of 0.42. Concrete should have a maximum slump of 4 inches and should contain control joints not greater than 12 feet on centers. The depth of the control joints should be at least ¼ of the slab thickness.

The collection and diversion of surface and subsurface drainage away from the paved areas is extremely important to satisfactory performance of the pavement. The design of the surface and subsurface drainage features should be carefully considered to remove all water from paved areas and to prevent ponding of water on and adjacent to paved areas. NWCC recommends subgrade areas be graded to drain if feasible so that surface runoff is not allowed to pond on the subgrade surface.

15.0 LIMITATIONS

The recommendations given in this report are based on the subsurface conditions encountered in the test pits advanced across the project site, our assumptions regarding the proposed construction and the behavior of structures at neighboring, similar sites. We believe that this information gives a high degree of reliability for anticipating the behavior of the proposed structures; however, our recommendations are professional opinions and cannot control nature, nor can they assure the soils profiles beneath those or adjacent to those observed. No warranties expressed or implied are given on the content of this report.

Swelling soils were encountered throughout the subdivision. These soils are stable at their natural moisture content but can shrink or swell with changes in moisture. The behavior of swelling soils is not fully understood. The swell potential of any particular site can change erratically both in lateral and vertical extent. Moisture changes also occur erratically, resulting in conditions, which cannot always be predicted. The recommendations presented in this report are based on the current state of the art for foundations and floor slabs on swelling soils. The owner should be aware that there is a risk in construction on these types of soil. Performance of the structures will depend on following the recommendations and in proper maintenance after construction is complete. As water is the main cause for volume change in these soils, it is necessary that the changes in moisture content be kept to a minimum. This requires judicious irrigation and providing positive surface drainage away from the structures. Any distress noted in the structures should be brought to the attention of this office.

This report is based on the investigation at the described site and on the specific anticipated construction as stated herein. If either of these conditions is changed, the results would also most likely change. Therefore, we strongly recommend that our firm be contacted prior to finalizing the construction plans so that we can verify that our recommendations are being properly incorporated into the construction plans. Man-made or natural changes in the conditions of a property can also occur over a period of time. In addition, changes in requirements due to state of the art knowledge and/or legislation do from time to time occur. As a result, the findings of this report may become invalid due to these changes. Therefore, this report is subject to review and not considered valid after a period of 3 years or if conditions as stated above are altered. It is the responsibility of the owner or his representative to insure that the information in this report is incorporated into the plans and/or specifications and construction of the project. It is

Subsoil and Foundation Investigation	NWCC Job No. 17-10640
Lockhart Subdivision	September 5, 2017
Steamboat Springs, Colorado	Page 11 of 11

advisable that a contractor familiar with construction details typically used to dealing with the local subsoils and climatic conditions be retained to build the structures.

If you have any questions regarding this report or if we may be of further service, please do not besitate to contact us.

Reviewed by Timothy S. Travis, P.E. Sr. Project Engineer

cc: Erik Griepentrog - Landmark Consultants

SOIL DESCRIPTION: Sandy Clay (CL) SAMPLE LOCATION: Test Pit 4 @ 9 Feet LIQUID LIMIT = 35 %PLASTICITY INDEX = 20 % PERCENT PASSING NO. 200 SIEVE = 83 NATURAL DRY UNIT WEIGHT = 101.5 per NATURAL MOISTURE CONTENT = 19.5 % б 4 3 2 SWELL 1 EXPANSION UNDER CONSTANT PRESSURE UPON ADDING MOISTURE 1 $CONSOLIDATION - (\pi)$ 0 1 2 3 4 5 6 0.1 1.0 10 20 APPLIED PRESSURE (ksf) Title: Date: SWELL-CONSOLIDATION TEST RESULTS 9/5/17 Job Name: Job No. 17-10640 Lockhart Subdivision (310)219-7133 - Fax (776)219-7291 2533 Copper Ridge DAw Stanzon Spings, Colorsto K1437 Location: River Queen Lane, Steamboat Springs, CO

Figure

#6

SOIL DESCRIPTION: Slightly Sandy Clay (CL) SAMPLE LOCATION: Test Pit 6 @ 6 Feet LIQUID LIMIT = 25 % PLASTICITY INDEX = 10 % PERCENT PASSING NO. 200 SIEVE = 90 NATURAL DRY UNIT WEIGHT = 108.8 pcf NATURAL MOISTURE CONTENT = 8.7 % 5 4 3 2 SWELL 1 EXPANSION UNDER CONSTANT PRESSURE UPON ADDING MOISTURE 1 CONSOLIDATION - (%)0 1 2 3 4 5 6 0.1 1.0 10 20 APPLIED PRESSURE (ksf) Title: Dater SWELL-CONSOLIDATION TEST RESULTS 9/5/17 Job No. 17-10640 Job Name: Lockhart Subdivision (310)/179-7855 + Fax (770)/179-7851 1583 Copper Ridge DA.o Stear-Boat Springs, Colorado 20457 Location: River Queen Lane, Steamboat Springs, CO Figure #7

6000 Allowable Bearing Capacity (psf) 4500 3000 1500 0 0 1.0 1.5 0.5 2,0 Estimated Settlement (inches)

货

Note: These values are based on footing widths of 1 to 4 feet. If the footing width is to be greater than 4 feet in width, then we should be notified to re-evaluate these recommendations.

THUE BEARING CAPACITY CHART	Date: 9/5/17	lo.	In West Colorate Consultante Inc.
Job Name: Lockhart Subdivision	Job No. 17-10640		within I Environments Engineering - Determine Teeting
Location: River Queen Lane, Steamboat Springs, CO	^{Figure} #8	1	2550 Copper Ridge Orke Skanboat Springs, Colorado 60451

NWCC, Inc.

TABLE 1

SUMMARY OF LABORATORY TEST RESULTS

TINTETED	SOIL. CLASS.	sc	SC	GM	NS	IJ	5	ฮ	sc
	DESCRIPTION	Gravelly Clayey Sand	Gravelly Clayey Sand	Silty Sand and Gravel	Silty Sand and Gravel Fill	Sandy Clay	Sandy Clay	Slightly Sandy Clay	Gravelly Clayey Sand
	UNCONFINED COMPRESSIVE STRENGTH (psf)								
	PERCENT PASSING No. 200 SIEVE	38	31	20	17	83	76	96	26
ATION	SAND (%)	42	48	39	47	14	54	10	53
GRAD	GRAVEL (Z)	20	21	41	36	ø	0	0	21
SC LIMITS	PLASTICITY INDEX (%)	15	11	5	đ	50	19	10	5
ATTERBER	LIQUID LIMIT (Z)	 28	24	21	đ	35	32	25	20
110000	DENSITY DENSITY (pef)	110.1				101.5		108.8	
	MOISTURE MOISTURE CONTENT (Z)	8.7	10.3	4.0	5.3	19.5	10.8	8.7	5.3
OCATION	DEPTH (feet)	g	5	1-2	2-3	\$	ę	9	8
SAMPLE I	TEST PIT	1	থ	æ	4	4	5	ę	2

JOB NUMBER: 17-10640

.