GENERAL NOTES

DESIGN LOAD

a. Header designed for dead load of wall and existing veneer.

STEEL STUD INFORMATON

a. Exterior studs are to be 600S162-43 as manufactured by Clark Dietrich (or equal).

NOTE:

- 1. LOCATION OF HEADER BASED ON ARCHITECTURAL PLANS.
- 2. ALL EXISTING FRAMING MEMBER SIZES SHOWN SHALL BE FIELD VERIFIED BY CONTRACTOR AT TIME OF CONSTRUCTION. ALL DIMENSIONS SHOWN SHALL BE FIELD VERIFIED BY CONTRACTOR AT TIME OF CONSTRUCTION. CONTRACTOR SHALL NOTIFY ENGINEER OF DISCREPANCIES BETWEEN FIELD CONDITIONS AND THOSE SHOWN ON DRAWINGS PRIOR TO CONSTRUCTION.

CRIPPLE STUDS-

AT 16" o.c.

(1) #10–16 SCREW TYP. EA FLANGE

(2) #10-16 SCREWS-

UNPUNCHED STUDS

HEADER TRACKS -

(2) 600S162-43, 33 KSI

LS543, 33 KSI SWIFT CLIP-

Reviewed for Code Compliance 02/02/2022 EXISTING WALL BRICK VENEER PER ARCH. PRECAST CONCRETE LINTEL 600S162-43, 33 KSI BOX HEADER W/ WEB STIFFENERS AT 16" o.c. MAX ∠6"x4"x5/16" MIN. ATTACH TO BOX HEADER W/ #12 TEK SCREWS AT 16" o.c. 4" MIN BEARING AT EA END OF STEEL ANGLE 600S162-43, 33 KSI JAMB 6" LONG SECTION OF STUD ATTACHED TO JAMB W/ (4) #10-16 SCREWS TRACK HEADER CONNECTION W/ LS543, 33 KSI SWIFT CLIP CAP OPENING SIDE OF JAMB W/ TRACK ATTACHED W/ (1) #10-16 SCREW @16" o.c.



| HEADER | DETAIL |
|--------------|--------|
| 1/2" = 1'-0" | |

| FOREVER FIT | DATE PROJECT | 1/20/22 #21–105 | Λ | SHEET |
|--|-----------------|--------------------------------------|----------------------------|--------|
| RESIDENTIAL REMODEL RESIDENTIAL UNIT | | SAT | ALPENGLOW | S-1 |
| 345 LINCOLN AVENUE #205 STEAMBOAT SPRINGS, COLORADO 80487 | FILE SCALE | ForeverFit_21105.dwg 1/2" = 1'-0" | ENGINEERING SOLUTIONS, INC | 1 OF 1 |