

Darby Enterprises, Inc. - Construction Site Management Plan

- This plan shall be kept on site at all time and updated to reflect any changes.
- Contractor is responsible for sediment control measures during construction to prevent release of pollutants from the project site.
- Control measures shall be inspected daily and after any precipitation event.
- Control measures shall be used, modified and maintained whenever necessary to reflect current conditions.
- Contractor shall promptly remove all sediment, mud, and construction debris that may accumulate in the right of way, private property or water ways as a result of construction activities.
- Debris or material from construction shall not be permitted to enter state waters.
- Emergency and ADA access must be kept obstacle free and passable at all times.
- Sidewalks adjacent to construction site shall be maintained, for public use, by the contractor.
- In areas where construction is taking place next to the sidewalk and overhead hazards are possible, site is responsible for installing and maintaining sidewalk protection.
- Site map indicating staging areas, dumpsters, sanitary facilities and loading/unloading areas shall be accompanied with this construction site management plan.
- Building permit shall be accompanied with this construction site management plan.
- Work will be in accordance with manufacturer published details, local building codes and state building codes.