2. CITY OF STEAMBOAT SPRINGS PLAN REVIEW AND APPROVAL IS ONLY FOR GENERAL CONFORMANCE WITH CITY DESIGN CRITERIA AND THE

CITY CODE. THE CITY IS NOT RESPONSIBLE FOR THE COMPLETENESS, ACCURACY AND ADEQUACY OF THE DRAWINGS. DESIGN, DIMENSIONS,

3. ONE COPY OF THE APPROVED CONSTRUCTION PLANS AND SPECIFICATIONS SHALL BE KEPT ON THE JOB SITE AT ALL TIMES. PRIOR TO THE START OF CONSTRUCTION, VERIFY WITH PROJECT ENGINEER THE LATEST REVISION DATE OF THE APPROVED CONSTRUCTION PLANS.

AND ELEVATIONS SHALL BE CONFIRMED AND CORRELATED AT THE JOB SITE.

- 4. ALL MATERIALS, WORKMANSHIP, AND CONSTRUCTION OF PUBLIC IMPROVEMENTS SHALL MEET OR EXCEED THE STANDARDS AND SPECIFICATIONS SET FORTH IN THE CITY OF STEAMBOAT SPRINGS TECHNICAL SPECIFICATIONS (MARCH, 2018 EDITION), THE "STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION" BY THE COLORADO DEPARTMENT OF TRANSPORTATION (2017 EDITION) AND APPLICABLE STATE AND FEDERAL REGULATIONS. WHERE THERE IS A DIRECT CONFLICT BETWEEN THESE PLANS AND THE SPECIFICATIONS. OR ANY APPLICABLE STANDARDS, THE MOST RESTRICTIVE STANDARD SHALL APPLY.
- 5. ALL WATER AND SANITARY SEWER CONSTRUCTION AND RELATED WORK SHALL CONFORM TO THE MOUNT WERNER WATER STANDARD SPECIFICATIONS FOR WATER AND WASTEWATER UTILITIES, CURRENT EDITION STANDARDS AND SPECIFICATIONS.
- 6. ALL NECESSARY PERMITS AND APPROVALS FROM ALL APPLICABLE AGENCIES AS REQUIRED MUST BE OBTAINED IN ORDER TO PERFORM THE WORK. THIS INCLUDES, BUT IS NOT LIMITED TO, RIGHT-OF-WAY PERMIT, GRADING AND EXCAVATION PERMIT, CONSTRUCTION DEWATERING PERMIT, STORM WATER QUALITY PERMIT, ARMY CORP OF ENGINEER PERMIT, ETC. IT IS THE APPLICABLE CONTRACTOR'S RESPONSIBILITY TO OBTAIN A COPY OF ALL APPLICABLE CODES, LICENSES, SPECIFICATIONS, AND STANDARDS NECESSARY TO PERFORM THE WORK, AND BE FAMILIAR WITH THEIR CONTENTS PRIOR TO COMMENCING ANY WORK
- PRIOR TO ANY WORK IN THE CITY RIGHT-OF-WAY INCLUDING STREET CUTS, CONTACT THE CITY OF STEAMBOAT SPRINGS STREET DEPARTMENT AT 970.879.1807 FOR PERMIT REQUIREMENTS. NO WORK SHALL OCCUR IN THE ROW BETWEEN NOVEMBER 1 - APRIL 1 UNLESS A WRITTEN VARIANCE HAS BEEN APPROVED AND ISSUED BY THE CITY PUBLIC WORKS DIRECTOR.
- 8. PRIOR TO CLOSURE OF ANY STREET OR PART OF STREET, AN APPROVED OBSTRUCTION PERMIT MUST BE ISSUED BY CITY CONSTRUCTION SERVICES FOREMAN.
- 9. PRIOR TO START OF CONSTRUCTION A PRE-CONSTRUCTION MEETING SHALL BE SCHEDULED WITH THE APPROPRIATE CONTRACTORS, ENGINEER, SURVEYOR, TESTING COMPANY, AFFECTED AGENCIES AND KEY SUBCONTRACTORS A MINIMUM OF 48-HOURS PRIOR TO THE START
- 10. THE LOCAL ENTITY AND ENGINEER SHALL BE NOTIFIED AT LEAST 2 WORKING DAYS PRIOR TO THE START OF ANY EARTH DISTURBING ACTIVITY, OR CONSTRUCTION ON ANY AND ALL PUBLIC IMPROVEMENTS. THE LOCAL ENTITY RESERVES THE RIGHT NOT TO ACCEPT THE IMPROVEMENTS IF SUBSEQUENT TESTING REVEALS AN IMPROPER INSTALLATION
- 11. COORDINATE WITH THE PROJECT ENGINEER TO IDENTIFY PROJECT INSPECTION AND TESTING REQUIREMENTS. PROVIDE FOR INSPECTIONS AND TESTING AT AN ADEQUATE FREQUENCY FOR THE PROJECT ENGINEER TO DOCUMENT THAT PROJECT IS CONSTRUCTED IN CONFORMANCE WITH THE APPROVED PLANS AND SPECIFICATIONS. PRIOR TO MAKING ANY CHANGES TO THE APPROVED PLANS, IT IS THE
- 12. PROVIDE THE OWNER, ENGINEER, THEIR CONSULTANTS, INDEPENDENT TESTING LABORATORIES, ANY GOVERNMENTAL AGENCIES WITH JURISDICTIONAL INTERESTS, OTHER REPRESENTATIVES AND PERSONNEL, ACCESS TO THE SITE AND THE WORK AT REASONABLE TIMES FOR THEIR OBSERVATION, INSPECTING, AND TESTING, PROVIDE THEM PROPER AND SAFE CONDITIONS FOR SUCH ACCESS AND ADVISE THEM OF THE DEVELOPER'S SITE SAFETY PROCEDURES AND PROGRAMS SO THAT THEY MAY COMPLY THEREWITH AS IS APPLICABLE. COORDINATE WITH THE PROJECT ENGINEER SO THAT INSPECTING AND TESTING ARE PROVIDED AT AN ADEQUATE FREQUENCY FOR THE PROJECT ENGINEER TO AFFIRM THAT WORK WAS COMPLETED IN SUBSTANTIAL CONFORMANCE WITH THESE APPROVED PLANS.

APPROPRIATE CONTRACTOR'S RESPONSIBILITY TO COORDINATE WITH THE PROJECT ENGINEER.

- 13. NO WORK MAY COMMENCE WITHIN ANY IMPROVED PUBLIC RIGHT-OF-WAY UNTIL A RIGHT-OF-WAY PERMIT OR APPROPRIATE CONSTRUCTION PERMIT IS OBTAINED. IF APPLICABLE, SUBMIT A CONSTRUCTION TRAFFIC CONTROL PLAN, IN ACCORDANCE WITH MUTCD. TO THE APPROPRIATE RIGHT-OF-WAY AUTHORITY, (LOCAL ENTITY, COUNTY OR STATE), FOR APPROVAL, PRIOR TO ANY CONSTRUCTION ACTIVITIES WITHIN, OR AFFECTING, THE RIGHT-OF-WAY. PROVIDE ANY AND ALL TRAFFIC CONTROL DEVICES AS MAY BE REQUIRED BY THE CONSTRUCTION
- 14. SUBMIT A CONSTRUCTION SITE MANAGEMENT PLAN (CSMP) FOR REVIEW AND APPROVAL BY THE CITY CONSTRUCTION SERVICES FOREMAN PRIOR TO START OF CONSTRUCTION. THE CSMP MUST BE MAINTAINED ON-SITE AND UPDATED AS NEEDED TO REFLECT CURRENT
- 15. ALL CONTRACTORS ARE SPECIFICALLY CAUTIONED THAT THE LOCATION AND/OR ELEVATION OF EXISTING UTILITIES, AS SHOWN ON THESE PLANS, IS BASED ON RECORDS OF THE VARIOUS UTILITY COMPANIES AND, WHERE POSSIBLE, MEASUREMENTS TAKEN IN THE FIELD. THE INFORMATION IS NOT TO BE RELIED UPON AS BEING EXACT OR COMPLETE. CONTACT THE UTILITY NOTIFICATION CENTER OF COLORADO UNCC) AT 1-800-922-1987. AT LEAST 2 WORKING DAYS PRIOR TO BEGINNING EXCAVATION OR GRADING. TO HAVE ALL REGISTERED UTILITY LOCATIONS MARKED. OTHER UNREGISTERED UTILITY ENTITIES (I.E. DITCH / IRRIGATION COMPANY) ARE TO BE LOCATED BY CONTACTING THE RESPECTIVE REPRESENTATIVE, UTILITY SERVICE LATERALS ARE ALSO TO BE LOCATED PRIOR TO BEGINNING EXCAVATION OR GRADING. THE TYPE, SIZE, LOCATION AND NUMBER OF ALL KNOWN UNDERGROUND UTILITIES ARE APPROXIMATE WHEN SHOWN ON THE DRAWINGS. VERIFY THE EXISTENCE AND LOCATION OF ALL UNDERGROUND UTILITIES ALONG THE ROUTE OF THE WORK BEFORE COMMENCING NEW CONSTRUCTION. THE CONTRACTOR SHALL NOTIFY THE ENGINEER OF ALL EXISTING UTILITIES THAT CONFLICT WITH THE PROPOSED IMPROVEMENTS SHOWN ON THESE PLANS.
- 16. FIELD LOCATE AND VERIFY ELEVATIONS OF ALL EXISTING SEWER MAINS, WATER MAINS, CURBS, GUTTERS AND OTHER UTILITIES AT THE POINTS OF CONNECTION SHOWN ON THE PLANS, AND AT ANY UTILITY CROSSINGS PRIOR TO INSTALLING ANY OF THE NEW IMPROVEMENTS. IF A CONFLICT EXISTS AND/OR A DESIGN MODIFICATION IS REQUIRED, COORDINATE WITH THE ENGINEER TO MODIFY THE DESIGN. DESIGN MODIFICATION(S) MUST BE APPROVED BY THE LOCAL ENTITY PRIOR TO BEGINNING CONSTRUCTION.
- 17. ALL UTILITY INSTALLATIONS WITHIN OR ACROSS THE ROADBED OR OTHER PAVED AREAS MUST BE COMPLETED PRIOR TO THE FINAL STAGES OF ROAD CONSTRUCTION. FOR THE PURPOSES OF THESE STANDARDS, ANY WORK INCLUDING, GRAVELS. PAVEMENTS, CURB AND GUTTER PROPERTY LINES AND MARKED SO AS TO REDUCE THE EXCAVATION NECESSARY FOR BUILDING CONNECTIONS.
- 18. COORDINATE AND COOPERATE WITH THE LOCAL ENTITY, AND ALL UTILITY COMPANIES INVOLVED, WITH REGARD TO RELOCATIONS, ADJUSTMENTS, EXTENSIONS AND REARRANGEMENTS OF EXISTING UTILITIES DURING CONSTRUCTION, AND TO ASSURE THAT THE WORK IS ACCOMPLISHED IN A TIMELY FASHION AND WITH A MINIMUM DISRUPTION OF SERVICE. CONTACT, IN ADVANCE, ALL PARTIES AFFECTED BY ANY DISRUPTION OF ANY UTILITY SERVICE AS WELL AS THE UTILITY COMPANIES.
- 19. NO WORK MAY COMMENCE WITHIN ANY PUBLIC STORM WATER, SANITARY SEWER OR POTABLE WATER SYSTEM UNTIL THE UTILITY PROVIDERS ARE NOTIFIED. NOTIFICATION SHALL BE A MINIMUM OF TWO (2) WORKING DAYS PRIOR TO COMMENCEMENT OF ANY WORK. AT THE DISCRETION OF THE WATER UTILITY PROVIDER, A PRE-CONSTRUCTION MEETING MAY BE REQUIRED PRIOR TO COMMENCEMENT OF ANY WORK.
- 20. PROTECT ALL UTILITIES DURING CONSTRUCTION AND FOR COORDINATE WITH THE APPROPRIATE UTILITY COMPANY FOR ANY UTILITY
- 21. WHEN APPLICABLE, THE DEVELOPER AND/OR CONTRACTOR SHALL HAVE ONSITE AT ALL TIMES, EACH OF THE FOLLOWING:
- BEST MANAGEMENT PRACTICES (BMP) MAINTENANCE FOLDER UP TO DATE STORMWATER MANAGEMENT PLAN (SWMP) THAT ACCURATELY REPRESENTS CURRENT FIELD CONDITIONS
- ONE (1) SIGNED COPY OF THE APPROVED PLANS
- ONE (1) COPY OF THE APPROPRIATE STANDARDS AND SPECIFICATIONS
- A COPY OF ANY PERMITS AND EXTENSION AGREEMENTS NEEDED FOR THE JOB.
- 23. IF, DURING THE CONSTRUCTION PROCESS, CONDITIONS ARE ENCOUNTERED WHICH COULD INDICATE A SITUATION THAT IS NOT IDENTIFIED IN THE PLANS OR SPECIFICATIONS, CONTACT THE DESIGNER AND THE LOCAL ENTITY ENGINEER IMMEDIATELY.
- 24. ALL REFERENCES TO ANY PUBLISHED STANDARDS SHALL REFER TO THE LATEST REVISION OF SAID STANDARD, UNLESS SPECIFICALLY
- 25. PROVIDE ALL LABOR AND MATERIALS NECESSARY FOR THE COMPLETION OF THE INTENDED IMPROVEMENTS SHOWN ON THESE DRAWINGS, OR DESIGNATED TO BE PROVIDED, INSTALLED, OR CONSTRUCTED, UNLESS SPECIFICALLY NOTED OTHERWISE.
- 26. THE CONTRACTOR SHALL BE RESPONSIBLE FOR RECORDING AS-BUILT INFORMATION ON A SET OF RECORD DRAWINGS KEPT ON THE CONSTRUCTION SITE, AND AVAILABLE TO THE LOCAL ENTITY'S INSPECTOR AT ALL TIMES.
- 27. DIMENSIONS FOR LAYOUT AND CONSTRUCTION ARE NOT TO BE SCALED FROM ANY DRAWING. IF PERTINENT DIMENSIONS OR ELEVATIONS ARE NOT SHOWN, CONTACT THE DESIGNER FOR CLARIFICATION, AND ANNOTATE THE PROVIDED DIMENSION ON THE AS-BUILT RECORD DRAWINGS. CONTOURS ARE NOT SUITABLE FOR CONSTRUCTION LAYOUT.
- 28. SEQUENCE INSTALLATION OF UTILITIES IN SUCH A MANNER AS TO MINIMIZE POTENTIAL UTILITY CONFLICTS. IN GENERAL, GRADE RESTRICTED UTILITIES SUCH AS STORM SEWER AND SANITARY SEWER, SHOULD BE CONSTRUCTED PRIOR TO INSTALLATION OF THE WATER LINES AND DRY
- 29. EXISTING FENCES, TREES, STREETS, SIDEWALKS, CURBS AND GUTTERS, LANDSCAPING, STRUCTURES, AND IMPROVEMENTS DESTROYED, DAMAGED OR REMOVED DUE TO CONSTRUCTION OF THIS PROJECT SHALL BE REPLACED OR RESTORED IN LIKE KIND AT THE CONTRACTOR'S EXPENSE, UNLESS OTHERWISE INDICATED ON THESE PLANS.
- 30. THESE CONSTRUCTION PLANS SHALL BE VALID FOR A PERIOD OF THREE YEARS FROM THE DATE OF APPROVAL BY THE AHJ. USE OF THESE PLANS AFTER THE EXPIRATION DATE WILL REQUIRE A NEW REVIEW AND APPROVAL PROCESS BY THE LOCAL ENTITY PRIOR TO COMMENCEMENT OF ANY WORK SHOWN IN THESE PLANS.
- 31. ALL CONSTRUCTION IN AREAS DESIGNATED AS WILD FIRE HAZARD AREAS SHALL BE DONE IN ACCORDANCE WITH THE CONSTRUCTION CRITERIA AS ESTABLISHED IN THE WILD FIRE HAZARD AREA MITIGATION REGULATIONS IN FORCE AT THE TIME OF CONSTRUCTION.
- 32. THE CONTRACTOR AGREES THAT BY COMMENCING CONSTRUCTION THAT HE SHALL ASSUME SOLE AND COMPLETE RESPONSIBILITY FOR JOB SITE CONDITIONS DURING THE CONSTRUCTION OF THE PROJECT, INCLUDING, BUT NOT LIMITED TO THE SAFETY OF ALL PERSONS AND PROPERTY: THAT THIS REQUIREMENT SHALL APPLY CONTINUOUSLY AND NOT BE LIMITED TO NORMAL WORKING HOURS: AND THAT THE CONTRACTOR SHALL DEFEND, INDEMNIFY AND HOLD T THE ENGINEER, AND THE GOVERNING AGENCIES AND THE OFFICERS, DIRECTORS, PARTNERS, EMPLOYEES, AGENTS AND OTHER CONSULTANTS OF EACH AND ANY OF THEM HARMLESS FROM ANY AND ALL LIABILITY, REAL OR ALLEGED, IN CONNECTION WITH THE PERFORMANCE OF WORK ON THIS PROJECT, EXCEPT FOR LIABILITY ARISING FROM THE NEGLIGENCE OF THE OWNER, THE ENGINEER, OR THE GOVERNING AGENCIES.
- 33. NOTIFY THE ENGINEER IMMEDIATELY UPON DISCOVERING ANY CONFLICTS OR OTHER PROBLEMS IN CONFORMING TO THE APPROVED CONSTRUCTION DRAWINGS, SPECIFICATIONS OR DETAILS FOR ANY ELEMENT OF THE PROPOSED IMPROVEMENTS PRIOR TO PROCEEDING
- 34. COORDINATE THE INSTALLATION OR RELOCATION OF THE DRY UTILITY COMPANY'S FACILITIES. COST OF THE DRY UTILITY WORK SHALL BE BORNE BY THE OWNER, EXCEPT AS INDICATED IN THE PLANS AND SPECIFICATIONS.

- 35. PRESERVE PRIVATE AND PUBLIC PROPERTY AND PROTECT IT FROM DAMAGE THAT MAY RESULT FROM CONSTRUCTING THESE PROPOSED
- 36. ACCESS TO ALL ADJACENT PROPERTIES AND FACILITIES SHALL BE MAINTAINED AT ALL TIMES. REQUIRED INTERRUPTION OF ACCESS SHALL BE COORDINATED WITH THE PROPERTY AND PROJECT OWNERS.
- 37. IF HAZARDOUS MATERIAL OR SUSPECT MATERIAL IS ENCOUNTERED NOTIFY THE OWNER AND ENGINEER BEFORE CONTINUING WORK. HAZARDOUS MATERIALS SHALL BE REMOVED AS REQUIRED.
- 38. THE APPROPRIATE CONTRACTOR SHALL BE RESPONSIBLE FOR THE SOURCE OF CONSTRUCTION WATER FOR USE ON THIS PROJECT.
- 39. EXCESS MATERIAL SHALL BE REMOVED FROM SITE AND HANDLED IN ACCORDANCE TO ALL RULES AND REQUIREMENTS. A SEPARATE PERMIT MAY BE REQUIRED AND SHALL BE COORDINATED WITH THE AUTHORITY HAVING JURISDICTION.
- 40. OFFSITE AND ADJACENT SITE DATA IS FOR REFERENCE PURPOSES ONLY.
- 41. ALL LANDSCAPING, REVEGETATION AND WETLANDS REQUIREMENTS DESIGN BY OTHERS. ALL DISTURBED AREAS ARE TO BE REVEGETATED
- 42. ENSURE THAT WORK FOR THIS PROJECT BE PERFORMED BY CONTRACTORS (INCLUDING CONTRACTOR'S EMPLOYEES AND AGENTS) POSSESSING THE SKILLS, EXPERTISE AND UNDERSTANDING OF ALL APPLICABLE CODES, SPECIFICATIONS, STANDARDS AND MANUFACTURER REQUIREMENTS. BY COMMENCING WORK, THE CONTRACTORS REPRESENT THAT THEY UNDERSTAND AND ACCEPT THIS REQUIREMENT.
- 43. ALL CONSTRUCTION ACTIVITIES AND DISTURBANCES SHALL OCCUR WITHIN THE PROPERTY LIMITS. WHERE OFF-SITE WORK IS APPROVED, WRITTEN PERMISSION OF THE ADJACENT PROPERTY OWNER MUST BE OBTAINED PRIOR TO ANY OFF-SITE GRADING OR CONSTRUCTION.

#### **CONSTRUCTION NOTES**

#### A.GRADING AND DRAINAGE

- 44. NO WORK SHALL OCCUR IN WETLANDS OR FLOODPLAINS WITHOUT PERMITS. ANY WORK SHALL BE IN ACCORDANCE WITH ISSUED PERMITS.
- 45. VEGETATED SLOPES GREATER THAN 3:1 REQUIRE SOIL STABILIZATION.
- 46. CLEAN ALL INSTALLED CULVERTS AND STORM SEWERS PRIOR TO SUBSTANTIAL COMPLETION INSPECTIONS.
- 47. LENGTHS SHOWN ON PLANS ARE HORIZONTAL LENGTHS FROM CENTER OF MANHOLE TO CENTER OF MANHOLE OR TO THE END OF THE FLARED END SECTIONS, ACTUAL LENGTHS MAY VARY.
- 48. SLOPES ARE CALCULATED FROM INSIDE EDGE OF MANHOLE/STRUCTURE TO INSIDE EDGE OF MANHOLE/STRUCTURE.
- 49. IMPERVIOUS CLAY DAMS ARE REQUIRED IN TRENCH AT 50-FT INTERVALS AND AT CHANGES IN PIPE DIRECTION AND/OR AT PIPE JUNCTIONS FOR ALL DRAINAGE STRUCTURES.
- 50. MINIMUM RECOMMENDATIONS (TO BE CONFIRMED OR REPLACED BY GEOTECHNICAL ENGINEER): PROPOSED FILL AREAS WHERE PAVEMENT OR SITE CONCRETE IS ANTICIPATED SHOULD BE PREPARED BY STRIPPING EXISTING TOPSOIL AND ORGANIC MATERIALS. SCARIFICATION TO A DEPTH OF AT LEAST 8 INCHES AND COMPACTION TO MINIMUM VALUES GIVEN BELOW. MOISTURE CONDITIONING MAY BE REQUIRED TO ATTAIN STABILITY AND MINIMUM COMPACTION.

SITE FILLS AND TRENCH BACKFILL SHOULD CONSIST OF APPROVED ON-SITE OR IMPORTED MATERIALS. FILLS SHOULD BE UNIFORMLY PLACED AND COMPACTED IN 6 TO 8 INCH LOOSE LIFTS TO AT LEAST 95 PERCENT OF THE MAXIMUM STANDARD PROCTOR DENSITY AND WITHIN 2 PERCENT OF THE OPTIMUM MOISTURE CONTENT (ASTM D698). MOISTURE CONDITIONING OF FILL MATERIALS MAY BE REQUIRED TO ATTAIN MINIMUM COMPACTION AND STABILITY REQUIREMENTS

51. A GEOTECHNICAL REPORT FOR THIS PROJECT WAS PREPARED BY NORTHWEST COLORADO CONSULTANTS, INC. (NWCC) TITLED "SUBSOIL AND FOUNDATION INVESTIGATION. CHRISTIE PEAK EXPRESS LIFT. STEAMBOAT SKI RESORT, STEAMBOAT SPRINGS, COLORADO" DATED DECEMBER 6, 2021, AND THEIR RECOMMENDATIONS ARE HEREBY INCORPORATED HEREIN. IF A CONFLICT OR DISCREPANCY OCCURS, NOTIFY 🚶 THE ENGINEER IMMEDIATELY UPON DISCOVERY. ADDITIONAL RECOMMENDATIONS MAY BE REQUIRED BASED ON THE MODIFIED LOCATION OF THE LOWER TERMINAL.

### **B. CONSTRUCTION SITE AND STORMWATER MANAGEMENT**

- 52. CONTRACTOR SHALL SUBMIT A CONSTRUCTION SITE MANAGEMENT PLAN TO THE CITY FOR APPROVAL PRIOR TO BUILDING PERMIT ISSUANCE.
- WHEN REQUIRED THE CONTRACTOR SHALL PREPARE A STORMWATER MANAGEMENT PLAN. THE STORMWATER MANAGEMENT PLAN SHALL BE PREPARED BY A QUALIFIED INDIVIDUAL WITH KNOWLEDGE IN THE PRINCIPLES AND PRACTICES OF EROSION AND SEDIMENT CONTROL AND POLLUTION PREVENTION. THIS INDIVIDUAL SHOULD BE RESPONSIBLE FOR DEVELOPING, IMPLEMENTING, MAINTAINING, AND REVISING THE STORMWATER MANAGEMENT PLAN FOR THE DURATION OF THE PROJECT
- 54. THE STORMWATER MANAGEMENT PLAN SHOULD ADDRESS INSTALLATION, INSPECTION AND MAINTENANCE OF ALL NECESSARY EROSION AND SEDIMENT CONTROL DURING CONSTRUCTION AND REMOVE EROSION CONTROL WHEN PROJECT IS COMPLETE AND VEGETATION IS ESTABLISHED. WHEN TEMPORARY EROSION CONTROL MEASURES ARE REMOVED, CLEAN UP AND REMOVE ALL SEDIMENT AND DEBRIS FROM ALL DRAINAGE INFRASTRUCTURE AND OTHER PUBLIC FACILITIES.
- 55. ALL REQUIRED PERIMETER SILT AND CONSTRUCTION FENCING SHALL BE INSTALLED PRIOR TO ANY LAND DISTURBING ACTIVITY (STOCKPILING, STRIPPING, GRADING, ETC). ALL OTHER REQUIRED EROSION CONTROL MEASURES SHALL BE INSTALLED AT THE APPROPRIATE TIME IN THE CONSTRUCTION SEQUENCE AS INDICATED IN THE APPROVED PROJECT SCHEDULE, CONSTRUCTION PLANS, AND STORMWATER MANAGEMENT
- E. ENSURE THAT NO MUD OR DEBRIS SHALL BE TRACKED ONTO THE EXISTING PUBLIC STREET SYSTEM. MUD AND DEBRIS MUST BE REMOVED BY THE END OF EACH WORKING DAY BY AN APPROPRIATE MECHANICAL METHOD (I.E. MACHINE BROOM SWEEP, LIGHT DUTY FRONT-END LOADER, ETC.) OR AS APPROVED BY THE LOCAL ENTITY STREET INSPECTOR.
- 57. ALL STRUCTURAL EROSION CONTROL MEASURES SHALL BE INSTALLED AT THE LIMITS OF CONSTRUCTION AND AT AREAS WITH DISTURBED SOIL, ON- OR OFF-SITE, PRIOR TO ANY OTHER GROUND-DISTURBING ACTIVITY, ALL EROSION CONTROL MEASURES SHALL BE MAINTAINED IN GOOD REPAIR, UNTIL SUCH TIME AS THE ENTIRE DISTURBED AREAS IS STABILIZED WITH HARD SURFACE OR LANDSCAPING. TO MITIGATE EROSION. UTILIZE STANDARD EROSION CONTROL TECHNIQUES DESCRIBED IN THE URBAN STORM DRAINAGE CRITERIA MANUAL, VOLUME 3 -BEST MANAGEMENT PRACTICES, AS PUBLISHED BY THE URBAN DRAINAGE AND FLOOD CONTROL DISTRICT (UDFCD).
- 58. PRE-DISTURBANCE VEGETATION SHALL BE PROTECTED AND RETAINED WHEREVER POSSIBLE. REMOVAL OR DISTURBANCE OF EXISTING VEGETATION SHALL BE LIMITED TO THE AREA(S) REQUIRED FOR IMMEDIATE CONSTRUCTION OPERATIONS, AND FOR THE SHORTEST
- 59. IMMEDIATELY CLEAN UP ANY CONSTRUCTION MATERIALS INADVERTENTLY DEPOSITED ON EXISTING STREETS, SIDEWALKS, OR OTHER PUBLIC RIGHTS OF WAY, AND MAKE SURE STREETS AND WALKWAYS ARE CLEANED AT THE END OF EACH WORKING DAY.
- 60. ALL RETAINED SEDIMENTS, PARTICULARLY THOSE ON PAVED ROADWAY SURFACES, SHALL BE REMOVED AND DISPOSED OF IN A MANNER AND LOCATION SO AS NOT TO CAUSE THEIR RELEASE INTO ANY WATERS OF THE UNITED STATES.
- 61. THE STORMWATER VOLUME CAPACITY OF DETENTION PONDS WILL BE RESTORED AND STORM SEWER LINES WILL BE CLEANED UPON COMPLETION OF THE PROJECT.
- 62. THE COLORADO DISCHARGE PERMIT SYSTEM (CDPS) REQUIREMENTS MAKE IT UNLAWFUL TO DISCHARGE OR ALLOW THE DISCHARGE OF ANY POLLUTANT OR CONTAMINATED WATER FROM CONSTRUCTION SITES. POLLUTANTS INCLUDE, BUT ARE NOT LIMITED TO DISCARDED BUILDING MATERIALS, CONCRETE TRUCK WASHOUT, CHEMICALS, OIL AND GAS PRODUCTS, LITTER, AND SANITARY WASTE. TAKE WHATEVER MEASURES ARE NECESSARY TO ASSURE THE PROPER CONTAINMENT AND DISPOSAL OF POLLUTANTS ON THE SITE IN ACCORDANCE WITH ANY AND ALL APPLICABLE LOCAL, STATE, AND FEDERAL REGULATIONS.

## D. WATER AND SEWER NOTES:

(THERE ARE NO ANTICIPATED WATER OR SEWER IMPROVEMENTS FOR THIS PROJECT. THE REFERENCES AND NOTES BELOW ARE PROVIDED IN THE EVENT THAT CONSTRUCTION ACTIVITY OCCURS NEAR EXISTING WATER/SEWER FACILITIES THAT MAY REQUIRE COORDINATION.)

- 63. ALL WATER AND SEWER CONSTRUCTION SHALL BE PER MT. WERNER WATER OR THE CITY OF STEAMBOAT SPRINGS WATER & SEWER STANDARD SPECIFICATIONS, LATEST EDITION, AS APPLICABLE.
- 64. MAINTAIN 10' HORIZONTAL AND 18" VERTICAL MINIMUM SEPARATION BETWEEN ALL SANITARY SEWER MAINS, WATER MAINS & SERVICES.
- 65. MANHOLES LOCATED OUTSIDE OF THE ROADWAY SHALL PROTRUDE 1' ABOVE EXISTING GRADE TO REDUCE INFILTRATION. GRADE SURFACE TO DRAIN AROUND/AWAY FROM MANHOLE RIMS.
- 66. ALL MANHOLES LOCATED IN THE ROADWAY SHALL HAVE RIM ELEVATIONS ADJUSTED TO  $\frac{1}{2}$ " BELOW FINISHED GRADE. IF NECESSARY, CONE SECTIONS SHALL BE ROTATED TO PREVENT LIDS BEING LOCATED WITHIN VEHICLE OR BICYCLE WHEEL PATHS.
- 67. SEWER SERVICE SHALL HAVE A MINIMUM OF 4-FT OF COVER.
- 68. WATER SERVICE SHALL HAVE A MINIMUM OF 7-FT OF COVER.
- 69. ALL WATER PIPE SHALL BE INSTALLED WITH A #10 SOLID COPPER WIRE COATED WITH 45 MIL POLYETHYLENE FOR LOCATING PURPOSES. "GLENN TEST STATIONS" BY VALVCO, INC TRACER WIRE TEST STATIONS SHALL BE INSTALLED ADJACENT TO ALL FIRE HYDRANTS. ADDITIONAL LOCATIONS MAY BE REQUIRED.
- 70. THE PARTICLE SIZE OF BEDDING AND SHADING MATERIAL SHALL BE 3/4 INCH WASHED OR SCREENED ROCK (NOT ROAD BASE OR CLASS 6) AND SHALL EXTEND THE FULL WIDTH OF THE TRENCH.

- 71. ALL MATERIALS USED FOR BACKFILL SHALL BE FREE FROM REFUSE ORGANIC MATERIAL, COBBLES, BOULDERS, LARGE ROCKS OR STONES OR FROZEN SOILS GREATER THAN 6-INCHES IN DIAMETER.
- 72. ALL TRENCHES SHALL BE COMPACTED TO 95% AS DETERMINED BY ASTM D698 (STANDARD PROCTOR) OR AS SPECIFIED BY GEOTECHNICAL

### PROJECT NOTES:

- 73. AN AUTOCAD COMPATIBLE FILE WILL BE PROVIDED FOR CONSTRUCTION STAKING PURPOSES, UPON ACCEPTANCE OF LANDMARK'S CAD
- 74. IF THESE DRAWINGS ARE PRESENTED IN A FORMAT OTHER THAN 24" X 36", THE GRAPHIC SCALE SHOULD NOT BE USED.
- 75. THE CONTRACTOR ACKNOWLEDGES AND UNDERSTANDS THAT THE CONTRACT DOCUMENTS MAY REPRESENT IMPERFECT DATA AND MAY CONTAIN ERRORS, OMISSIONS, CONFLICTS, INCONSISTENCIES, CODE VIOLATIONS AND IMPROPER USE OF MATERIALS, SUCH DEFICIENCIES WILL BE CORRECTED WHEN IDENTIFIED. THE CONTRACTOR AGREES TO CAREFULLY STUDY AND COMPARE THE INDIVIDUAL CONTRACT DOCUMENTS AND REPORT AT ONCE IN WRITING T THE OWNER ANY DEFICIENCIES THE CONTRACTOR MAY DISCOVER. THE CONTRACTOR FURTHER AGREES TO REQUIRE EACH SUBCONTRACTOR TO LIKEWISE STUDY THE DOCUMENTS AND REPORT AT ONCE ANY DEFICIENCIES DISCOVERED.
  - THE CONTRACTOR SHALL RESOLVE ALL REPORTED APPLICABLE DEFICIENCIES WITH LANDMARK PRIOR TO AWARDING ANY SUBCONTRACTS OR STARTING ANY WORK WITH THE CONTRACTOR'S OWN EMPLOYEES. IF ANY DEFICIENCIES CANNOT BE RESOLVED BY THE CONTRACTOR WITHOUT ADDITIONAL TIME OR ADDITIONAL EXPENSES, THE CONTRACTOR SHALL SO INFORM THE OWNER IN WRITING. ANY SUCH ADDITIONAL WORK PERFORMED PRIOR TO RECEIPT OF INSTRUCTIONS FROM THE OWNER WILL BE DONE AT THE CONTRACTOR'S RISK.

#### **CONSTRUCTION PHASE SERVICES:**

IT IS LINDERSTOOD AND AGREED THAT LANDMARK DOES NOT HAVE AN OBLIGATION TO CONDUCT CONSTRUCTION OBSERVATION OR REVIEW OF THE CONTRACTOR'S PERFORMANCE OR ANY OTHER CONSTRUCTION PHASE SERVICES. AND THAT SUCH SERVICES WILL BE PROVIDED FOR BY THE OWNER AS MAY BE REQUIRED BY THE AUTHORITY HAVING JURISDICTION. THE OWNER ASSUMES ALL RESPONSIBILITY FOR INTERPRETATION OF THESE CONSTRUCTION DOCUMENTS AND FOR CONSTRUCTION OBSERVATION AND THE OWNER WAIVES ANY CLAIMS AGAINST LANDMARK THAT MAY BE IN ANY WAY CONNECTED THERETO.

IN ADDITION, THE OWNER AGREES, TO THE FULLEST EXTENT PERMITTED BY LAW, TO INDEMNIFY AND HOLD HARMLESS LANDMARK, ITS OFFICERS, DIRECTORS, EMPLOYEES AND SUBCONSULTANTS (COLLECTIVELY, LANDMARK) AGAINST ALL DAMAGES, LIABILITIES OR COSTS. INCLUDING REASONABLE ATTORNEYS' FEES AND DEFENSE COSTS. ARISING OUT OF OR IN ANY WAY CONNECTED WITH THE PERFORMANCE OF SUCH SERVICES BY OTHER PERSONS OR ENTITIES AND FROM ANY AND ALL CLAIMS ARISING FROM MODIFICATIONS, CLARIFICATIONS, INTERPRETATIONS, ADJUSTMENTS OR CHANGES MADE TO THESE CONSTRUCTION DOCUMENTS TO REFLECT CHANGED FIELD OR OTHER CONDITIONS. EXCEPT FOR CLAIMS ARISING FROM THE SOLE NEGLIGENCE OR WILLFUL MISCONDUCT OF LANDMARK.

ADA

APR

BOT

EOP

LBS

OFF

AMERICAN'S WITH DISABILITIES ACT APPROXIMATE BEST MANAGEMENT PRACTICE **BVCS** BEGIN VERTICAL CURVE STATION **BVCE** BEGIN VERTICAL CURVE ELEVATION

BW OR BOW BOTTOM OF WALL C&C CUT & CAPPED CAP CORRUGATED ALUMINUM PIPE CIP CAST-IN-PLACE

CENTERLINE CMP CORRUGATED METAL PIPE C.O. CLEAN OUT CP CONCRETE PIPE CSP CORRUGATED STEEL PIPE DIA DIAMETER

DUCTILE IRON PIPE EXISTING GROUND FI EVATION EOA OR EA EDGE OF ASPHALT EOC EDGE OF CONCRETE

**EVCE** END VERTICAL CURVE ELEVATION **EVCS** END VERTICAL CURVE STATION EXISTING F&G FRAME & GRATE FRAME & COVER FLARED END SECTION FES

EDGE OF PAVEMENT

FFE FINISH FLOOR ELEVATION FIRE HYDRANT FH FLOW LINE

FINISH GRADE FINISH GRADE AT BOTTOM OF WALL GB GRADE BREAK

**GFFE** GARAGE FINISH FLOOR ELEVATION GTD GRADE TO DRAIN HDPE HIGH DENSITY POLYETHYLENE PIPE INV INVERT

POUNDS

LOD LIMITS OF DISTURBANCE M/E/P MECHANICAL, ELECTRIC, AND PLUMBING MAX MAXIMUM MATCH EXISTING

MANHOLE

MIN MINIMUM MECHANICAL JOINT NAP OR N.A.P. NOT A PART (NOT INCLUDED IN SCOPE) NTS NOT TO SCALE

OFFSET

POINT OF CURVE POINT OF INTERSECTION POINT OF CONCAVE CURVE PLDP POROUS LANDSCAPE DETENTION POND POINT OF REVERSE CURVE POINT OF TANGENT PVC POINT OF VERTICAL CURVE

PVC POLYVINYL CHLORIDE PIPE POINT OF VERTICAL INTERSECTION PVT POINT OF VERTICAL TANGENT REINFORCED CONCRETE PIPE

REQ REQUIRED ROW RIGHT OF WAY STA STATION THRUST BLOCK TO BE REMOVED TOP OF GRATE TOP OF PIPE TAPERED TO GRADE TW OR TOW TOP OF WALL

TYP TYPICAL VITRIFIED CLAY PIPE VOL VOLUME

CALL UTILITY NOTIFICATION CENTER OF

Know what's **below**.

Call before you dig.

LL 2 BUSINESS DAYS IN ADVANCE BEFORE YOU DIG. GRADE, OR EXCAVATE FOR THE MARKING OF

ABBREVIATIONS

#### Wildfire Responsibilities

### Forest Service

The Forest Service is responsible for all wildland fire operations on National Forest System Lands within the permitted area. Fire Management Representatives will be available to the Permittee and or contractor working within the permitted area for interpretation, discussion and assistance with any item appearing in this Wildland Fire Plan.

Fire Management Representatives will take action on all wildfires within the permitted area as described in the 2011 Medicine Bow-Routt National Forest and Thunder Basin National Grassland Fire Management Plan.

#### <u>Permittee</u>

The Permittee will report any wildfire located on or threatening National Forest System lands within the permit boundary. This wildfire report will first be communicated to dispatch centers for the initial response to the fire area. Only qualified personnel equipped with the proper Personal Protective Equipment will perform initial attack suppression actions.

The Permittee will monitor the permit area for compliance with the prevention and detection section of this wildland fire plan. If prevention methods are not followed within this plan, both parties will cooperate in taking corrective actions.

### **Notification and Communication**

Critical information on Wildfires will need to be communicated first and foremost to the representative Dispatch Centers:

- 1. Routt County Emergency Dispatch Center: 911
- 2. Craig Interagency Wildland Fire Dispatch Center: (970) 826-5037

The following information will be provided when reporting a *Wildfire*:

- Exact location of wildfire and values at risk
- Size of fire and fuel type grass, brush, timber, and or slash
- Character of fire smoldering, creeping, running, and or torching
- Best access to fire area
- Weather conditions cloudy, windy, sunny and or raining

Project Name		
Project Latitude / Longitude	N	W

KEY ELEMENT CHECKLIST			NO
Are the Administrative Burning Requirements up to date with the current year	ar's information?		
Are ALL county or state permits and clearances obtained?			
Are ALL fire prescription elements met?			
Has Permittee obtained the fire weather forecast and is it favorable?			
There are <b>NO</b> USFS, State or County burn restrictions in effect for the planned burn area?			
Are ALL planned personnel and equipment on-site, available, and operational?			
Have ALL assigned personnel been briefed on the project objectives, their assignment, safety hazards, escape routes, and safety zones?			
Have ALL the required pre-burn notifications been made?			
Is a USFS District Fire Duty Officer available to contact as needed?			
Is the contingency plan prepared?			
In your judgment, can this burn be carried out according to the Plan to meet the objectives?			
Permittee Project Supervisor:		Time (	24

## Permittee Supervisory Responsibility:

The Permittee shall have a representative (project supervisor) on site that shall be authorized to receive and carry out on behalf of the Permittee any and all notices or instructions by the Forest Service Approving Officer in regard to burning and fire precautions. The project supervisor's duties and responsibilities will be to supervise all debris and slash burning activities in accordance with these requirements provisions of this plan.

## Pre-Burn Notifications:

Prior to ignition, the permittee will notify the following agencies and/or individuals:

Name	Phone #	Fax #	
Name County 911 Dispatch Center			
Name Forest Fire Duty Officer			
Name Interagency Fire Dispatch			
Notifications required in APCD Permit			
Name Ski Area Permit Administrator			
Other			

## **General Requirements:**

Access: Access to burn piles by firefighting personnel shall not be restricted. Access to burn project areas must be maintained or no burning will be allowed.

Minimum Equipment and Staffing: The permittee is responsible for ensuring the staffing and equipment on site is

- adequate for maintaining control of the pile burning operation. • 1 Project Leader, minimum of 2 additional personnel. Staffing should increase proportional to the number of piles burning and the area involved.
- 1 hand tool (shovel, Pulaski, chainsaw, axe, etc.) per person assigned. Ignition devices (Fussees, drip torches, etc.) and fuel.
- Personnel Protective Equipment (PPE): Hardhat, leather gloves, non-synthetic clothing, and boots.

#### Prevention and Detection

A wildfire precautionary period will initiate on May 15<sup>th</sup> and run throughout the summer months until November 15<sup>th</sup> unless otherwise stated. During this period the Permittee will be required to keep equipment that will aid in the initial control of human caused wildfire started by the Permittee and or contractor completing work operations for the Permittee. This equipment will be strategically located in places that are easily accessible for the Permittee or contactor while conducting work operations that have ignition potential. The Permittee will also insure that field going personnel will have means of communication in case of a wildfire.

- Suggested tools to help with the initial action on Wildfires:
- Long handle spade shovel
- Pulaski or Axe
- Backpack pump or water bucket

During fire restrictions Steamboat Ski Resort Corporation in considered exempt (36 C.F.R. § 261.50 (e)) from restrictions provided that the following precautionary measures are in place:

#### **Under Stage 1 Fire Restrictions:**

- A shovel and fire extinguisher will be readily accessible in every SSRC vehicle.
- Employees shall attend a yearly fire prevention and safety briefing.
- A watchperson will be on duty after any explosives are used and will patrol the detonation area for at least one hour after operations have ceased.
- Welding will be accomplished in buildings when possible. If welding at field locations is required, the welding will be done at a location where all flammable material has been cleared to a minimum distance of 15 feet. Water and tools must also be located at this site.
- Flammables will be stored in appropriate containers and will be labeled. Storage buildings will be adequately signed if containing flammables. Areas containing
- flammables will be devoid of fuels within a 25 foot radius. • Fueling will occur in areas that are devoid of flammable fuels and or are
- surrounded by mineral soils. Smoking will take place in designated areas and/or areas that are devoid of flammable fuels.

#### **Additional Actions under Stage 2 Fire Restrictions:**

- A water source will be available on each active worksite (e.g. snowmaking, ATV mounted tank).
- A 10lb or larger fire extinguisher will be available on each active worksite.
- o Employees will visually inspect spark arrestors on chainsaws and other gasoline powered hand tools.
- o Any spark requiring fire suppression activities will be monitored for 24 hours after the incident to ensure fire is extinguished.

#### Heavy equipment (tractor/dozer) including operator or a readily available water source must be on site if burning without persistent snow cover.

Communication: Radio frequencies and channels used for the burn operation must be consistent with the Permittee's Annual Operating Plan.

Size and Location of Burn Piles: Burn piles shall not be located or constructed in such a manner that improvements or adjacent trees could be damaged.

Weather Monitoring: The Permittee Project Supervisor shall record the following weather every 2 hours: Location of Observations, Cloud Cover %, Dry Bulb Temperature, Relative Humidity, Wind Speed and Direction. All records will be provided to the Forest Service upon request.

**Cost:** All costs associated with burning operations are the responsibility of the permit holder.

## <u>PRESCRIPTION</u>

- Compliance with State Air Pollution Control Division and/or county open burn permit conditions, including
- pile size, favorable smoke dispersion forecast and wind vectors. • Snow cover of 3" over 75% of the unit - OR - > 0.25 inches precipitation in the last 48 hours, measured on site or at the *name* weather (RAWS, NWS or Snotel) station.
- Fire Danger is rated Low or Moderate • The 3 day General Weather Forecast for the Zone has NO Red Flag Watches or Warnings, NO predicted
- frontal passages and meets the following criteria: If relative humidity is 20-29%, then 20 ft winds must be < 10 mph</li>
- If relative humidity is 30-39%, then 20 ft winds must be < 20 mph</li>
- If relative humidity is > 50%, then 20 ft winds must be < 30 mph</li>

## **HOLDING ACTIONS**

General Procedures to maintain the fire within the project area and meet objectives until declared 'out':

#### Ignited piles may be left unattended at night and for multiple days as long as prescription snow cover conditions exist. Periodic checks should be performed on all ignited piles until no heat is detected and the piles can be declared "out". Frequency and duration of the checks will be determined by the Project Leader.

# B. Without 'Snow cover' provisions

Ignited piles may be left unattended overnight if prescription conditions are forecast to exist for the next 24 hours. All piles ignited under this condition must be checked daily until no heat is detected and the piles can be declared "out". Mop-up of piles may be required.

## **CONTINGENCY ACTIONS**

If any of the following Trigger Points are met, the associated Contingency Actions should be implemented:

Trigger Points	Contingency Actions	Results
Consumption objectives are not being met.	Cease Ignitions.	If conditions become favorable, ignition may continue.
Smoke or changing conditions are not consistent with Colorado APCD smoke permit	Cease Ignitions.     Mitigate as possible including mopup as needed	If contingency actions or change in conditions bring the project back within the scope of this prescribed fire plan, ignition may continue.
Significant weather changes which were not forecasted, particularly an increase in wind or drying.	<ol> <li>Cease Ignitions.</li> <li>Contact the FS Duty Officer</li> <li>Monitor fire behavior and conditions, adding additional resources as necessary.</li> </ol>	If contingency actions bring the project back within the scope of this prescribed fire plan, ignition may continue.
Unwanted fire spread within project boundary	Cease ignitions.	If contingency actions bring the project back within the scope of this

#### Wildfire Costs

The Permittee may be held responsible for costs associated with human caused fire ignitions resulting from project operations by the Permittee or contractor/personnel working on behalf of the Permittee within the permitted area. Standard reimbursement cost rates will be used if reimbursement is sought for any such fires. The Forest Service will be responsible for all management costs associated with any naturally ignited wildfire on National Forest System Lands.

#### **Prescribed Fire Responsibilities**

### Forest Service

Fire Management Representatives will periodically communicate with the Permittee to insure adequate prescribed fire preparation of designated projects.

The Permittee will designate a contact person for the planning and implementation of prescribed fire projects within the permitted area.

The Permittee will cooperate and assist the Forest Service in the preparation and location of prescribed fire project areas.

The Permittee is responsible for all prescribed fire planning, smoke management planning and

implementation of projects within the permitted area on National Forest System Lands pursuant to the Regional 2 policy and forms (attached).

### Planning and Implementation

The Permittee will develop a prescribed fire burn plan that will guide the implementation of prescribed fire projects. All Colorado Department of Air Quality smoke permits and local fire permits will be obtained by the Permittee.

Communication between the Permittee and Forest Service will periodically take place to insure the location, size and composition of prescribed fuels meet planning document requirements.

Implementation of prescribed fire projects will be conducted and coordinated by the Permittee in cooperation with the Forest Service.

#### Prescribed Fire Costs

The Permittee will be responsible for costs associated with the planning and implementation of prescribed fire within the permitted area, on National Forest System Lands.

**REVIEWED** 

Know what's below. Call before you dig.

CALL UTILITY NOTIFICATION CENTER OF

CALL 2 BUSINESS DAYS IN ADVANCE BEFORE YOU DIG. GRADE, OR EXCAVATE FOR THE MARKING OF



COMPLIANCE

Fire plan- Steamboat has a fire plan (Appendix F) which outlines preventative measures and responses related to fire mitigation. Additionally, this plan outlines necessary measures for exemptions to Stage 2 fire restrictions for welding and using vehicles off-road. This operating plan and authorized officer approval of the plan equates to the requirement that an exemption must be applied for in writing, include an appropriate mitigation plan (see Appendix) and must be authorized in writing by the appropriate Forest Service official.

Notice regarding Exemptions: Holders of valid Forest Service permits, leases and authorizations and all other persons are on notice that when proceeding with activities that are authorized pursuant to these Exemptions, such persons are responsible for conducting authorized activities in a safe and prudent manner using extra precautions and are electing to proceed at their own risk. An exemption does not absolve an individual or organization from liability or responsibility for damage, injury or loss to the United States for any fire started while undertaking the exempted activity.

Fire, Health & Sanitation Plan- The Colorado Department of Health, Routt County Building Department, Environmental Health Department, Steamboat Springs Rural Fire Protection District, as well as SSRC's insurance companies (both property and worker's compensation carriers) actively inspect the facilities and operations owned by SSRC. SSRC maintains a separate file of all fire inspections in the Facilities Maintenance offices, health and sanitation inspections in the Food & Beverage offices and other safety reviews in office of the Risk Manager. These files are available for inspection by the Forest Service administering offices. As a function of Hahns Peak/Bear's Ears District's monitoring role of the Special Use Permittee, Forest Service representatives may from time to time participate in insurance and/or regulatory agency inspections and reviews.

distributed to key directors and supervisors that might have involvement in a crisis situation.

- SSRC will cooperate with federal, state, and local law enforcement agencies in the performance of their respective duties, i.e., enforcement of Colorado Ski Safety Act of 1979, local ordinances,
- The Routt County Sheriff has jurisdiction to enforce county and state law on the Steamboat Ski
- The Colorado Division of Wildlife has jurisdiction to enforce state law on the Steamboat Ski

## 7. Vegetation Management

representative has approved in writing and marked or otherwise identified what may be removed or destroyed (Permit III G). See Appendix E for administrative use documentation. It is understood that tree removal could change the character of the forest and affect forest health where concentrated removal is proposed. Therefore, if concentrated removal is proposed through an operating plan or project record sheet, approval would be contingent upon consultation with the Forest Service and conformance with the ski area's vegetation management plan.

snowmaking; this practice is authorized. Hollyhock, Rabbit Ears gilia, lady fern, broad-leaved twayblade, and white-veined wintergreen may not be damaged. Additionally, a 100-foot buffer around intermittent and perennial streams must be maintained unless authorized by the Forest Service botanist and/or hydrologist. The following ski runs have buffer exemptions: none (Permit III G).

recommendations when changing the vegetative component or when efficiencies can be made when working in a coincident area.

scentless chamomile, and reed canarygrass.

Herbicide and pesticide use required annual written approval (Permit V E). This operating plan authorizes Activator 90 per 20 gallons).

The approved seed mix for the resort is:

40% mountain brome, 33% blue wildrye, 23% slender wheatgrass and 4% Poa ampla or canbyi.

CALL UTILITY NOTIFICATION CENTER OF

Know what's below. Call before you dig. CALL 2 BUSINESS DAYS IN ADVANCE BEFORE YOU DIG, GRADE, OR EXCAVATE FOR THE MARKING OF

**REVIEWED FOR** CODE COMPLIANCE 06/15/2022

Emergency Management Plan- SSRC maintains an up-to-date Emergency Management Plan with copies

Law Enforcement- The USFS is responsible for enforcing National Forest regulations as established in Title 36, Code of Federal Regulations.

- state laws, etc.

Trees or shrubbery may be removed or destroyed only after the authorized officer or designated

Trees that pose a safety concern to guests and infrastructure are authorized for removal.


Currently, SSRC cuts vegetation on groomed runs and mostly focused on those that receive


Trees are authorized to be planted or transplanted following consultation with Forest Service botanist (Permit III G).

To the extent possible, management actions shall integrate SSRC's vegetation management plan

SSRC is responsible for nonnative and invasive species treatment. Treatments within the resort shall be reported on an annual basis and include: weed species, treatment locations (a map or GPS), acres treated, name of the herbicide(s) used and the quantity applied (total chemical used and application rate, if possible). Known invasive/noxious species on the resort include but are not limited to: These include whitetop or hoary cress, Canada thistle, bull thistle, yellow toadflax, houndstongue, and

the use of: Kernight (6oz/gallon), Curtail (2oz/gallon), 2-4-D (16oz 2-4-D, 4 grams Escort, splash of





LEGEND: PROPERTY BOUNDARY ADJACENT PROPERTY BOUNDARY EASEMENT SECTION LINE \_\_\_\_\_\_ CENTERLINE FOUND MONUMENT FOUND SECTION CORNER BUILDING ROOF LINE/OVERHANG DECK WALL FENCE MAJOR CONTOUR ---- 6800 ----MINOR CONTOUR ASPHALT CONCRETE GRAVEL SANITARY SEWER SANITARY SEWER MANHOLE AND CLEANOUT WATER LINE FIRE HYDRANT, GATE VALVE & CURB STOP GAS METER AND MANHOLE/VAULT CABLE PEDESTAL FIBER OPTIC TELEPHONE TELEPHONE PEDESTAL AND MANHOLE/VAULT ELECTRIC ELECTRIC PED, JUNCTION BOX AND METER LIGHT POLE AND LIGHT POLE W/ MAST OVERHEAD UTILITY POLE AND GUY WIRE DITCH/SWALE CULVERT W/ END SECTIONS INLET AND STORM MANHOLE FLOW ARROW  $\Longrightarrow$ CONIFEROUS AND DECIDUOUS TREE

- THIS MAP DOES NOT REPRESENT A MONUMENTED LAND SURVEY. IT IS INTENDED ONLY TO DEPICT THAT INFORMATION REQUESTED BY OUR CLIENT.
- ALL REFERENCES HEREON TO BOOKS, PAGES, FILES, RECEPTION NUMBERS AND FILE NUMBERS ARE TO PUBLIC DOCUMENTS FILED IN THE RECORDS OF ROUTT COUNTY, COLORADO.
- EASEMENTS AND PUBLIC DOCUMENTS SHOWN OR NOTED HEREON WERE EXAMINED AS TO LOCATION AND PURPOSE AND WERE NOT EXAMINED AS TO RESERVATIONS, RESTRICTIONS, CONDITIONS, OBLIGATIONS, TERMS, OR AS TO THE RIGHT TO GRANT THE SAME.
- 4. THIS MAP DOES NOT CONSTITUTE A TITLE SEARCH BY LANDMARK CONSULTANTS, INC. TO DETERMINE OWNERSHIP OF THIS TRACT, VERIFY THE DESCRIPTIONS SHOWN, VERIFY THE COMPATIBILITY OF THIS DESCRIPTION WITH THAT OF ADJACENT TRACTS, OR VERIFY EASEMENTS OF RECORD.
- 5. UTILITIES ARE SHOWN PER APPARENT SURFACE EVIDENCE TOGETHER WITH RECORD INFORMATION. IF MORE ACCURATE LOCATIONS OF UNDERGROUND UTILITIES ARE REQUIRED, THE UTILITY WILL HAVE TO BE VERIFIED BY FIELD POTHOLING. LANDMARK CONSULTANTS, INC. AND THE SURVEYOR OF RECORD SHALL NOT BE LIABLE FOR THE LOCATION OF OR THE FAILURE TO NOTE THE LOCATION OF NON-VISIBLE UTILITIES.
- BASIS OF BEARINGS: THE NORTH LINE OF SECTION 27, T6N, R84W, 6TH P.M., BEING MONUMENTED AS SHOWN HEREON AND BEING ASSUMED TO BEAR N86°54'01"E. BEARINGS SHOWN HEREON HAVE BEEN ROTATED FROM RECORD BEARINGS.
- ANY PERSON WHO KNOWINGLY REMOVES, ALTERS OR DEFACES ANY PUBLIC LAND SURVEY MONUMENT OR LAND MONUMENT OR ACCESSORY, COMMITS A CLASS TWO (2) MISDEMEANOR PURSUANT TO STATE STATUTE 18-4-508, C.R.S.
- 8. THIS SITE CONTAINS A CALCULATED AREA OF 201.9 ACRES.
- 9. A PORTION OF THE SITE IS LOCATED WITHIN SPECIAL FLOOD HAZARD AREA ZONE A OF THE UNNAMED TRIBUTARY TO BURGESS CREEK AS DETERMINED BY FEMA FLOOD INSURANCE RATE MAP NUMBER 08107C0883D, WITH AN EFFECTIVE DATE OF FEBRUARY 4, 2005 AND LOMR 18-08-0922P.
- 10. THE MEASURED DISTANCES SHOWN HEREON ARE IN U.S. SURVEY FEET.
- 11. ALL SYMBOLS ARE ONLY GRAPHICALLY REPRESENTED AND ARE NOT TO SCALE
- 12. CONTRACTOR IS ENCOURAGED TO PERFORM DEMOLITION IN A MANNER THAT MAXIMIZES SALVAGE, RE-USE, AND RECYCLING OF MATERIALS. THIS INCLUDES APPROPRIATE SORTING AND STORING. IN PARTICULAR, DEMOLISHED CONCRETE,
- 13. CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATING AND CONFIRMING DEMOLITION, REMOVAL, REPLACEMENT, AND DISPOSAL OF ALL FACILITIES AND
- 14. THE DEMOLITION OF THE MINI-GOLF AND MOUNTAIN COASTER ARE NOT A PART BUT

# PROPERTY DESCRIPTION:

15. LOT 2, PARCEL D, SKI HILL SUBDIVISION PER FILE #14469 N ROUTT COURS AND LOT 1. OPERALION PROVIDED TO THE PROVIDED PROVIDED TO THE PROVIDED PROVIDED TO THE PROVIDED PROVID RECORDS AND LOT 1, GREEN HORN RANCH PER FILE #14 524 IN ROUTT COUNTY RECORDS, CITY OF STEAMBOAT SPRINGS, ROUTT COUNTY, COLOR DO DE

CALL UTILITY NOTIFICATION CENTER OF




Know what's **below**. Call before you dig. CALL 2 BUSINESS DAYS IN ADVANCE BEFORE YOU DIG, GRADE, OR EXCAVATE FOR THE MARKING OF UNDERGROUND MEMBER UTILITIES.

C.010

ak Express Fondition (Overall)





## LEGEND:

PROPERTY BOUNDARY		
ADJACENT PROPERTY BOUNDARY		
EASEMENT		
SECTION LINE		
CENTERLINE		
OUND MONUMENT	•	)
OUND SECTION CORNER	4	<b>&gt;</b>
BUILDING	<u> </u>	
OOF LINE/OVERHANG		
PECK		
VALL		
ENCE	x x	— x — — x —
MAJOR CONTOUR	680	00 — — —
MINOR CONTOUR		
ASPHALT		
CONCRETE		
RAVEL		
SIGN	•	,
SANITARY SEWER	xsxs	—xsxs
ANITARY SEWER MANHOLE AND CLEANOUT	(XS)	©
ATER LINE	xwxw	xwxw
IRE HYDRANT, GATE VALVE & CURB STOP	$\forall$	(i)
AS	XGXG	— XG ——— XG —
AS METER AND MANHOLE/VAULT	GM	<b>©</b>
CABLE	XTVXTV	—XTV ———XTV
CABLE PEDESTAL	TV	
BER OPTIC	—— XFO ——— XFO ———	— XF0 ——— XF0
ELEPHONE	XTXT	—хт——хт—
ELEPHONE PEDESTAL AND MANHOLE/VAULT	T	$\bigcirc$
ELECTRIC	XEXE	—XEXE
ELECTRIC PED, JUNCTION BOX AND METER	₽ EJ	EM
IGHT POLE AND LIGHT POLE W/ MAST	- <del>\</del>	<b>♦</b>
OVERHEAD	хонхон	—хон ——хон
JTILITY POLE AND GUY WIRE		$\leftarrow$
DITCH/SWALE		
CULVERT W/ END SECTIONS		
NLET AND STORM MANHOLE		(ST)
LOW ARROW	<u> </u>	<del>2</del>
==:::::::::::::::::::::::::::::::::::::	. W///	

CONIFEROUS AND DECIDUOUS TREE

- THIS MAP DOES NOT REPRESENT A MONUMENTED LAND SURVEY. IT IS INTENDED ONLY TO DEPICT THAT INFORMATION REQUESTED BY OUR CLIENT.
- ALL REFERENCES HEREON TO BOOKS, PAGES, FILES, RECEPTION NUMBERS AND FILE NUMBERS ARE TO PUBLIC DOCUMENTS FILED IN THE RECORDS OF ROUTT COUNTY, COLORADO.
- EASEMENTS AND PUBLIC DOCUMENTS SHOWN OR NOTED HEREON WERE EXAMINED AS TO LOCATION AND PURPOSE AND WERE NOT EXAMINED AS TO RESERVATIONS, RESTRICTIONS, CONDITIONS, OBLIGATIONS, TERMS, OR AS TO THE RIGHT TO GRANT THE SAME.
- THIS MAP DOES NOT CONSTITUTE A TITLE SEARCH BY LANDMARK CONSULTANTS, INC. TO DETERMINE OWNERSHIP OF THIS TRACT, VERIFY THE DESCRIPTIONS SHOWN, VERIFY THE COMPATIBILITY OF THIS DESCRIPTION WITH THAT OF ADJACENT TRACTS, OR VERIFY EASEMENTS OF RECORD.
- UTILITIES ARE SHOWN PER APPARENT SURFACE EVIDENCE TOGETHER WITH RECORD INFORMATION. IF MORE ACCURATE LOCATIONS OF UNDERGROUND UTILITIES ARE REQUIRED, THE UTILITY WILL HAVE TO BE VERIFIED BY FIELD POTHOLING. LANDMARK CONSULTANTS, INC. AND THE SURVEYOR OF RECORD SHALL NOT BE LIABLE FOR THE LOCATION OF OR THE FAILURE TO NOTE THE LOCATION OF NON-VISIBLE UTILITIES.
- BASIS OF BEARINGS: THE NORTH LINE OF SECTION 27, T6N, R84W, 6TH P.M., BEING MONUMENTED AS SHOWN HEREON AND BEING ASSUMED TO BEAR N86°54'01"E. BEARINGS SHOWN HEREON HAVE BEEN ROTATED FROM RECORD BEARINGS.
- ANY PERSON WHO KNOWINGLY REMOVES, ALTERS OR DEFACES ANY PUBLIC LAND SURVEY MONUMENT OR LAND MONUMENT OR ACCESSORY, COMMITS A CLASS TWO (2) MISDEMEANOR PURSUANT TO STATE STATUTE 18-4-508, C.R.S.
- 8. THIS SITE CONTAINS A CALCULATED AREA OF 201.9 ACRES.
- A PORTION OF THE SITE IS LOCATED WITHIN SPECIAL FLOOD HAZARD AREA ZONE A OF THE UNNAMED TRIBUTARY TO BURGESS CREEK AS DETERMINED BY FEMA FLOOD INSURANCE RATE MAP NUMBER 08107C0883D, WITH AN EFFECTIVE DATE OF FEBRUARY 4, 2005 AND LOMR 18-08-0922P.
- 10. THE MEASURED DISTANCES SHOWN HEREON ARE IN U.S. SURVEY FEET.

ASPHALT, AND BASE COURSE SHOULD BE RECYCLED IF POSSIBLE.

ARE PERMITTED SEPARATELY UNDER PERMIT SPRDE22( 354.

- 11. ALL SYMBOLS ARE ONLY GRAPHICALLY REPRESENTED AND ARE NOT TO SCALE
- 12. CONTRACTOR IS ENCOURAGED TO PERFORM DEMOLITION IN A MANNER THAT MAXIMIZES SALVAGE, RE-USE, AND RECYCLING OF MATERIALS. THIS INCLUDES APPROPRIATE SORTING AND STORING. IN PARTICULAR, DEMOLISHED CONCRETE,
- 13. CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATING AND CONFIRMING DEMOLITION, REMOVAL, REPLACEMENT, AND DISPOSAL OF ALL FACILITIES AND

# PROPERTY DESCRIPTION:

15. LOT 2, PARCEL D, SKI HILL SUBDIVISION PER FILE #14469 N ROUTT COUNCER RECORDS AND LOT 1, GREEN HORN RANCH PER FILE #16524 IN ROUTE COUNTY RECORDS, CITY OF STEAMBOAT SPRINGS, ROUTE COUNTY, COLOR OF COUNTY

CALL UTILITY NOTIFICATION CENTER OF





Know what's **below**. Call before you dig. CALL 2 BUSINESS DAYS IN ADVANCE BEFORE YOU DIG, GRADE, OR EXCAVATE FOR THE MARKING OF UNDERGROUND MEMBER UTILITIES.

erial Imagery 14. THE DEMOLITION OF THE MINI-GOLF AND MOUNTAIN COASTER ARE NOT A PART BUT

SHEET

C.011





## I FGFND.

PROPERTY BOUNDARY			
ADJACENT PROPERTY BOUNDARY			
EASEMENT			
SECTION LINE			
CENTERLINE			- —
FOUND MONUMENT		ledow	
FOUND SECTION CORNER		lack	
BUILDING	<b>.</b>	<u> </u>	
ROOF LINE/OVERHANG			
DECK			
WALL			
FENCE	x :	х —— х	
MAJOR CONTOUR		6800 -	
MINOR CONTOUR			
ASPHALT			
CONCRETE		land of the second	
GRAVEL			
SIGN			_
SANITARY SEWER	xsx	sxs	
SANITARY SEWER MANHOLE AND CLEANOUT	(xs)		©
WATER LINE	xwx	wxw	/
FIRE HYDRANT, GATE VALVE & CURB STOP	~	$\bowtie$	(
GAS	XGX	g ——— xg	
GAS METER AND MANHOLE/VAULT	GM		G
CABLE	XTVXT	VXT	v ——
CABLE PEDESTAL		TV	
FIBER OPTIC		0 XF	0
TELEPHONE	xx	т——хт	
TELEPHONE PEDESTAL AND MANHOLE/VAULT	T		$\bigcirc$
ELECTRIC	xex	:EXE	
ELECTRIC PED, JUNCTION BOX AND METER		EJ	E
LIGHT POLE AND LIGHT POLE W/ MAST	->>-		<b>\rightarrow</b>
OVERHEAD	— хон — хо	нхо	н
UTILITY POLE AND GUY WIRE	0		$\leftarrow$
DITCH/SWALE		<u> </u>	
CULVERT W/ END SECTIONS			
INLET AND STORM MANHOLE			(s
FLOW ARROW		<b>≕</b> >	0
CONIFEROUS AND DECIDUOUS TREE		-	

- THIS MAP DOES NOT REPRESENT A MONUMENTED LAND SURVEY. IT IS INTENDED
- ALL REFERENCES HEREON TO BOOKS, PAGES, FILES, RECEPTION NUMBERS AND FILE NUMBERS ARE TO PUBLIC DOCUMENTS FILED IN THE RECORDS OF ROUTT COUNTY, COLORADO.
- EASEMENTS AND PUBLIC DOCUMENTS SHOWN OR NOTED HEREON WERE EXAMINED AS TO LOCATION AND PURPOSE AND WERE NOT EXAMINED AS TO RESERVATIONS, RESTRICTIONS, CONDITIONS, OBLIGATIONS, TERMS, OR AS TO THE RIGHT TO GRANT THE SAME.
- THIS MAP DOES NOT CONSTITUTE A TITLE SEARCH BY LANDMARK CONSULTANTS, INC. TO DETERMINE OWNERSHIP OF THIS TRACT, VERIFY THE DESCRIPTIONS SHOWN, VERIFY THE COMPATIBILITY OF THIS DESCRIPTION WITH THAT OF ADJACENT TRACTS, OR VERIFY EASEMENTS OF RECORD.
- UTILITIES ARE SHOWN PER APPARENT SURFACE EVIDENCE TOGETHER WITH RECORD INFORMATION. IF MORE ACCURATE LOCATIONS OF UNDERGROUND UTILITIES ARE REQUIRED, THE UTILITY WILL HAVE TO BE VERIFIED BY FIELD POTHOLING. LANDMARK CONSULTANTS, INC. AND THE SURVEYOR OF RECORD SHALL NOT BE LIABLE FOR THE LOCATION OF OR THE FAILURE TO NOTE THE LOCATION OF NON-VISIBLE UTILITIES.
- BASIS OF BEARINGS: THE NORTH LINE OF SECTION 27, T6N, R84W, 6TH P.M., BEING MONUMENTED AS SHOWN HEREON AND BEING ASSUMED TO BEAR N86°54'01"E. BEARINGS SHOWN HEREON HAVE BEEN ROTATED FROM RECORD BEARINGS.
- ANY PERSON WHO KNOWINGLY REMOVES, ALTERS OR DEFACES ANY PUBLIC LAND SURVEY MONUMENT OR LAND MONUMENT OR ACCESSORY, COMMITS A CLASS TWO (2) MISDEMEANOR PURSUANT TO STATE STATUTE 18-4-508, C.R.S.
- 8. THIS SITE CONTAINS A CALCULATED AREA OF 201.9 ACRES.
- 9. A PORTION OF THE SITE IS LOCATED WITHIN SPECIAL FLOOD HAZARD AREA ZONE A OF THE UNNAMED TRIBUTARY TO BURGESS CREEK AS DETERMINED BY FEMA FLOOD INSURANCE RATE MAP NUMBER 08107C0883D, WITH AN EFFECTIVE DATE OF FEBRUARY 4, 2005 AND LOMR 18-08-0922P.
- 10. THE MEASURED DISTANCES SHOWN HEREON ARE IN U.S. SURVEY FEET.
- 11. ALL SYMBOLS ARE ONLY GRAPHICALLY REPRESENTED AND ARE NOT TO SCALE
- MAXIMIZES SALVAGE, RE-USE, AND RECYCLING OF MATERIALS. THIS INCLUDES APPROPRIATE SORTING AND STORING. IN PARTICULAR, DEMOLISHED CONCRETE, ASPHALT, AND BASE COURSE SHOULD BE RECYCLED IF POSSIBLE.
- 13. CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATING AND CONFIRMING DEMOLITION, REMOVAL, REPLACEMENT, AND DISPOSAL OF ALL FACILITIES AND
- 14. THE DEMOLITION OF THE MINI-GOLF AND MOUNTAIN COASTER ARE NOT A PART BUT

## PROPERTY DESCRIPTION:


15. LOT 2, PARCEL D, SKI HILL SUBDIVISION PER FILE #14469 N ROUTT COUNCER RECORDS AND LOT 1, GREEN HORN RANCH PER FILE #16524 IN ROUTE COUNTY RECORDS, CITY OF STEAMBOAT SPRINGS, ROUTE COUNTY, COLOR OF COUNTY


CALL UTILITY NOTIFICATION CENTER OF



Know what's **below**. Call before you dig. CALL 2 BUSINESS DAYS IN ADVANCE BEFORE YOU DIG, GRADE, OR EXCAVATE FOR THE MARKING OF UNDERGROUND MEMBER UTILITIES.

C.012





# **EASEMENT LEGEND:**

2	BOOK 729, PAGE 339, RECE	PTION NO. 746875: BUDDY'S RUN DECK ENCROACHMENT EASEM
3	RECEPTION NO. 693287:	INTERFACE EASEMENT
4	RECEPTION NO. 693287:	INTERFACE EASEMENT, REVOCABLE PORTION
5	BOOK 532, PAGE 820:	10' SANITARY SEWER EASEMENT
6	RECEPTION NO. 693286:	PARKING, ACCESS & MAINTENANCE EASEMENT

BOOK 729, PAGE 338, RECEPTION NO. 687253, RECEPTION NO. 705974: EAST HOTEL ACCESS EASEMENT

RECEPTION NO. 693016: 20' ACCESS EASEMENT EAST HOTEL ACROSS OSP

BOOK 374, PAGE 345, BOOK 376, PAGE 318, RECEPTION NO. 770696 : 20' WATER LINE EASEMENT

BOOK 337, PAGE 337: PERPETUAL VISUAL EASEMENT BOOK 393, PAGE 509 & BOOK 395, PAGE 376: ROAD EASEMENT

BOOK 412, PAGE 341: ENTRYWAY EASEMENT BOOK 412, PAGE 343: ACCESS EASEMENT

BOOK 580, PAGE 70, RECEPTION NO. 727257, RECEPTION NO. 727903: LANDSCAPING AND ACCESS EASEMENT (BEAR CLAW II)

BOOK 745, PAGE 286: 20' SEWER EASEMENT RECEPTION NO. 673610, RECEPTION NO. 705975, RECEPTION NO. 789275: SEWER EASEMENT

RECEPTION NO.s 673610 & 705975: SEWER EASEMENT RELOCATION AREA

RECEPTION NO. 789275: SEWER ENCROACHMENT AREA

RECEPTION NO. 678035: FIRE SEPARATION EASEMENT RECEPTION NO. 692162: SKI EASEMENT

RECEPTION NO. 693153: WATER MAINS EASEMENT

RECEPTION NO. 699297, RECEPTION NO. 749729, RECEPTION NO. 702319, RECEPTION NO. 713742:

RECEPTION NO. 699297, RECEPTION NO. 713742: PUBLIC IMPROVEMENTS EASEMENT (BOILER HOUSE)

RECEPTION NO. 699720: SEWER MAINS EASEMENT RECEPTION NO. 699721: WATER MAINS EASEMENT

RECEPTION NO. 718939, RECEPTION NO. 733617: PUBLIC IMPROVEMENTS EASEMENT (LITTLE P

RECEPTION NO. 728342: ACCESS AND LANDSCAPE EASEMENT

BOOK 583, PAGE 238 & RECEPTION NO. 693278: ACCESS EASEMENT (1ST AMENDMENT EAST HOTEL

RECEPTION NO. 699296: STORM SEWER & ACCESS AND MAINTENANCE EASEMENT RECEPTION NO. 693152: SANITARY SEWER EASEMENT

RECEPTION NO. \_\_\_\_\_: ELECTRIC EASEMENT

RECEPTION NO. \_\_\_\_\_: GAS EASEMENT

BOOK 532, PAGE 756: TELEPHONE EASEMENT

RECEPTION NO. 789276: DECK EASEMENT AGREEMENT

BOOK 629, PAGE 832: PEDESTRIAN ACCESS EASEMENT

BOOK 532, PAGE 820, BOOK 532, PAGE 774: 10' SANITARY SEWER EASEMENT BOOK 760, PAGE 976: BUILDING ENCROACHMENT EASEMENT

RECEPTION NO. 513746 (FILE NO. 12770); RECEPTION NO. 307130 (FILE NO. 8823): STORM SEWER

BOOK 532, PAGE 758: 16' TELEPHONE EASEMENT

BOOK 596, PAGE 1611: EXCLUSIVE PARKING SPACES; ENTRANCE FROM ACCESS ROUTE NO. 1;

ENTRANCE FROM ACCESS ROUTE NO.2; VEHICULAR AND PEDESTRIAN INGRESS AND EGRESS ACCESS EASEMENT (ACCESS ROUTE 2); STORAGE, CLOSET, ELEVATOR & STAIRWAY

BOOK 532, PAGE 774: 10' ELECTRIC EASEMENT

BOOK 729, PAGE 342: HOTEL ACCESS EASEMENT

RECEPTION NO. 307130: ACCESS EASEMENT SKI HILL SUBDIVISION

BOOK 559, PAGE 98: TRUCK TURNAROUND LICENSE AGREEMENT

RECEPTION NO. 693288: INTERFACE EASEMENT

RECEPTION NO. 693289: NO BUILD EASEMENT

BOOK 596, PAGE 1487, EX A: BUILDING IMPROVEMENT EASEMENT

RECEPTION NO. 600980: AERIAL TRAMWAY EASEMENT

RECEPTION NO. 680175: SHORING EASEMENT AGREEMENT

(MULTIPLE EXHIBITS), GONDOLA SQUARE ACCESS EASEMENT, WEST SIDE DRAINAGE EASEMENT, ETC.

RECEPTION NO. 693283: PEDESTRIAN ACCESS EASEMENT OSP

BOOK 532, PAGE 802: 10' WATERLINE EASEMENT

RECEPTION NO. 693285: PATIO EASEMENT, DOORWAY EASEMENT, ENTRY EASEMENTS RECEPTION NO. 693280: SANITARY SEWER EASEMENT

RECEPTION NO. 693283: EMERGENCY ACCESS EASEMENT OSP

RECEPTION NO. 693290: SKI AREA EASEMENT, STORM SEWER & DRAINAGE EASEMENT, RECIPROCAL UTILITY EASEMENT, GONDOLA SQUARE ACCESS EASEMENT

RECEPTION NO. 693016, BOOK 729, PAGE 338: AGREEMENT (ACCESS TO EASTERN SIDE RECEPTION NO. 693278: DECLARATION OF EASEMENT

RECEPTION NO. 600979: ACCESS EASEMENT

BOOK 596, PAGE 1487, EX C-7: WALKWAY EASEMENT

RECEPTION NO. 596269, BOOK 596, PAGE 1487, EX C-8 AND C-9: STORM SEWER LINE EASEMENT AND STORM LINE EASEMENT

BOOK 358, PAGE 473: PRIVATE RIGHT-OF-WAY

RECEPTION NO. 661066: OSP EASEMENT AREA

RECEPTION NO. 693018: RIGHT OF WAY EASEMENT (ELECTRIC RECEPTION NO. 693279: SNOWMAKING LINE EASEMENT

BOOK 583, PAGE 238: 30' ACCESS EASEMENT

BOOK 519, PAGE 577: 10' TELEPHONE EASEMENT

BOOK 729, PAGE 343: HOTEL BRIDGE ACCESS, PEDESTRIAN MAINTENANCE VEHICLE ACCESS


BOOK 532, PAGE 782: ELECTRIC EASEMENT


CALL UTILITY NOTIFICATION CENTER OF



Know what's **below**. Call before you dig. CALL 2 BUSINESS DAYS IN ADVANCE BEFORE YOU DIG, GRADE, OR EXCAVATE FOR THE MARKING OF UNDERGROUND MEMBER UTILITIES.

C.020





# **EASEMENT LEGEND:**

BOOK 729, PAGE 339, RECEPTION NO. 746875: BUDDY'S RUN DECK ENCROACHMENT EASEMENT RECEPTION NO. 693287: INTERFACE EASEMENT RECEPTION NO. 693287: INTERFACE EASEMENT, REVOCABLE PORTION BOOK 532, PAGE 820: 10' SANITARY SEWER EASEMENT

RECEPTION NO. 693286: PARKING, ACCESS & MAINTENANCE EASEMENT BOOK 729, PAGE 338, RECEPTION NO. 687253, RECEPTION NO. 705974: EAST HOTEL ACCESS EASEMENT AS AMENDED BY RECEPTION NO. \_\_\_

BOOK 374, PAGE 345, BOOK 376, PAGE 318, RECEPTION NO. 770696: 20' WATER LINE EASEMENT BOOK 337, PAGE 337: PERPETUAL VISUAL EASEMENT

BOOK 393, PAGE 509 & BOOK 395, PAGE 376: ROAD EASEMENT

BOOK 412, PAGE 343: ACCESS EASEMENT BOOK 580, PAGE 70, RECEPTION NO. 727257, RECEPTION NO. 727903: LANDSCAPING AND ACCESS

EASEMENT (BEAR CLAW II) BOOK 745, PAGE 286: 20' SEWER EASEMENT

RECEPTION NO. 673610, RECEPTION NO. 705975, RECEPTION NO. 789275: SEWER EASEMENT

RECEPTION NO.s 673610 & 705975: SEWER EASEMENT RELOCATION AREA

RECEPTION NO. 789275: SEWER ENCROACHMENT AREA

RECEPTION NO. 692162: SKI EASEMENT RECEPTION NO. 693153: WATER MAINS EASEMENT

RECEPTION NO. 699297, RECEPTION NO. 749729, RECEPTION NO. 702319, RECEPTION NO. 713742:

RECEPTION NO. 699297, RECEPTION NO. 713742: PUBLIC IMPROVEMENTS EASEMENT (BOILER HOUSE)

RECEPTION NO. 699720: SEWER MAINS EASEMENT

RECEPTION NO. 699721: WATER MAINS EASEMENT RECEPTION NO. 718939, RECEPTION NO. 733617: PUBLIC IMPROVEMENTS EASEMENT (LITTLE P

RECEPTION NO. 728342: ACCESS AND LANDSCAPE EASEMENT

BOOK 583, PAGE 238 & RECEPTION NO. 693278: ACCESS EASEMENT (1ST AMENDMENT EAST HOTEL

RECEPTION NO. 699296: STORM SEWER & ACCESS AND MAINTENANCE EASEMENT

RECEPTION NO. 693152: SANITARY SEWER EASEMENT RECEPTION NO. \_\_\_\_\_: ELECTRIC EASEMENT

RECEPTION NO. \_\_\_\_\_: GAS EASEMENT

BOOK 532, PAGE 756: TELEPHONE EASEMENT

RECEPTION NO. 789276: DECK EASEMENT AGREEMENT

BOOK 629, PAGE 832: PEDESTRIAN ACCESS EASEMENT

BOOK 532, PAGE 820, BOOK 532, PAGE 774: 10' SANITARY SEWER EASEMENT BOOK 760, PAGE 976: BUILDING ENCROACHMENT EASEMENT

RECEPTION NO. 513746 (FILE NO. 12770); RECEPTION NO. 307130 (FILE NO. 8823): STORM SEWER

BOOK 532, PAGE 758: 16' TELEPHONE EASEMENT

BOOK 596, PAGE 1611: EXCLUSIVE PARKING SPACES; ENTRANCE FROM ACCESS ROUTE NO. 1;

ENTRANCE FROM ACCESS ROUTE NO.2; VEHICULAR AND PEDESTRIAN INGRESS AND EGRESS ACCESS EASEMENT (ACCESS ROUTE 2); STORAGE, CLOSET, ELEVATOR & STAIRWAY

BOOK 532, PAGE 774: 10' ELECTRIC EASEMENT

BOOK 729, PAGE 342: HOTEL ACCESS EASEMENT

RECEPTION NO. 307130: ACCESS EASEMENT SKI HILL SUBDIVISION

BOOK 559, PAGE 98: TRUCK TURNAROUND LICENSE AGREEMENT

RECEPTION NO. 693288: INTERFACE EASEMENT

RECEPTION NO. 693289: NO BUILD EASEMENT

BOOK 596, PAGE 1487, EX A: BUILDING IMPROVEMENT EASEMENT

RECEPTION NO. 600980: AERIAL TRAMWAY EASEMENT

RECEPTION NO. 680175: SHORING EASEMENT AGREEMENT

(MULTIPLE EXHIBITS), GONDOLA SQUARE ACCESS EASEMENT, WEST SIDE DRAINAGE EASEMENT, ETC.

RECEPTION NO. 693283: PEDESTRIAN ACCESS EASEMENT OSP

BOOK 532, PAGE 802: 10' WATERLINE EASEMENT RECEPTION NO. 693285: PATIO EASEMENT, DOORWAY EASEMENT, ENTRY EASEMENTS

RECEPTION NO. 693280: SANITARY SEWER EASEMENT

RECEPTION NO. 693283: EMERGENCY ACCESS EASEMENT OSP

RECEPTION NO. 693290: SKI AREA EASEMENT, STORM SEWER & DRAINAGE EASEMENT, RECIPROCAL UTILITY EASEMENT, GONDOLA SQUARE ACCESS EASEMENT

RECEPTION NO. 693016, BOOK 729, PAGE 338: AGREEMENT (ACCESS TO EASTERN SIDE RECEPTION NO. 693278: DECLARATION OF EASEMENT

RECEPTION NO. 600979: ACCESS EASEMENT

BOOK 596, PAGE 1487, EX C-7: WALKWAY EASEMENT

RECEPTION NO. 596269, BOOK 596, PAGE 1487, EX C-8 AND C-9: STORM SEWER LINE EASEMENT AND STORM LINE EASEMENT

BOOK 358, PAGE 473: PRIVATE RIGHT-OF-WAY

RECEPTION NO. 661066: OSP EASEMENT AREA

RECEPTION NO. 693018: RIGHT OF WAY EASEMENT (ELECTRIC RECEPTION NO. 693279: SNOWMAKING LINE EASEMENT

BOOK 583, PAGE 238: 30' ACCESS EASEMENT

BOOK 519, PAGE 577: 10' TELEPHONE EASEMENT


BOOK 729, PAGE 343: HOTEL BRIDGE ACCESS, PEDESTRIAN A MAINTENANCE VEHICLE ACCESS

BOOK 532, PAGE 782: ELECTRIC EASEMENT

CALL UTILITY NOTIFICATION CENTER OF

Know what's **below**. Call before you dig. CALL 2 BUSINESS DAYS IN ADVANCE BEFORE YOU DIG, GRADE, OR EXCAVATE FOR THE MARKING OF





# **EASEMENT LEGEND:**

2	BOOK 729, PAGE 339, RECEI	PTION NO. 746875: BUDDY'S RUN DECK ENCROACHMENT EASEMENT
3	RECEPTION NO. 693287:	INTERFACE EASEMENT
4	RECEPTION NO. 693287:	INTERFACE EASEMENT, REVOCABLE PORTION
5	BOOK 532, PAGE 820:	10' SANITARY SEWER EASEMENT
6	RECEPTION NO. 693286:	PARKING, ACCESS & MAINTENANCE EASEMENT
7	BOOK 729, PAGE 338, RECEI AS AMENDED BY RECEPTIO	PTION NO. 687253, RECEPTION NO. 705974: EAST HOTEL ACCESS EASEMENT IN NO.

BOOK 374, PAGE 345, BOOK 376, PAGE 318, RECEPTION NO. 770696: 20' WATER LINE EASEMENT

BOOK 337, PAGE 337: PERPETUAL VISUAL EASEMENT BOOK 393, PAGE 509 & BOOK 395, PAGE 376: ROAD EASEMENT

BOOK 412, PAGE 341: ENTRYWAY EASEMENT

EASEMENT (BEAR CLAW II)

BOOK 412, PAGE 343: ACCESS EASEMENT BOOK 580, PAGE 70, RECEPTION NO. 727257, RECEPTION NO. 727903: LANDSCAPING AND ACCESS

BOOK 745, PAGE 286: 20' SEWER EASEMENT

RECEPTION NO. 673610, RECEPTION NO. 705975, RECEPTION NO. 789275: SEWER EASEMENT

RECEPTION NO.s 673610 & 705975: SEWER EASEMENT RELOCATION AREA RECEPTION NO. 789275: SEWER ENCROACHMENT AREA

RECEPTION NO. 692162: SKI EASEMENT RECEPTION NO. 693153: WATER MAINS EASEMENT

RECEPTION NO. 678035: FIRE SEPARATION EASEMENT

RECEPTION NO. 699297, RECEPTION NO. 749729, RECEPTION NO. 702319, RECEPTION NO. 713742:

RECEPTION NO. 699297, RECEPTION NO. 713742: PUBLIC IMPROVEMENTS EASEMENT (BOILER HOUSE)

RECEPTION NO. 699720: SEWER MAINS EASEMENT RECEPTION NO. 699721: WATER MAINS EASEMENT

RECEPTION NO. 718939, RECEPTION NO. 733617: PUBLIC IMPROVEMENTS EASEMENT (LITTLE P

RECEPTION NO. 728342: ACCESS AND LANDSCAPE EASEMENT

BOOK 583, PAGE 238 & RECEPTION NO. 693278: ACCESS EASEMENT (1ST AMENDMENT EAST HOTEL

RECEPTION NO. 699296: STORM SEWER & ACCESS AND MAINTENANCE EASEMENT

RECEPTION NO. 693152: SANITARY SEWER EASEMENT RECEPTION NO. \_\_\_\_\_: ELECTRIC EASEMENT

RECEPTION NO. \_\_\_\_\_: GAS EASEMENT BOOK 532, PAGE 756: TELEPHONE EASEMENT

RECEPTION NO. 789276: DECK EASEMENT AGREEMENT BOOK 629, PAGE 832: PEDESTRIAN ACCESS EASEMENT

BOOK 532, PAGE 820, BOOK 532, PAGE 774: 10' SANITARY SEWER EASEMENT

BOOK 760, PAGE 976: BUILDING ENCROACHMENT EASEMENT RECEPTION NO. 513746 (FILE NO. 12770); RECEPTION NO. 307130 (FILE NO. 8823): STORM SEWER

BOOK 532, PAGE 758: 16' TELEPHONE EASEMENT

BOOK 596, PAGE 1611: EXCLUSIVE PARKING SPACES; ENTRANCE FROM ACCESS ROUTE NO. 1;

ENTRANCE FROM ACCESS ROUTE NO.2; VEHICULAR AND PEDESTRIAN INGRESS AND EGRESS ACCESS EASEMENT (ACCESS ROUTE 2); STORAGE, CLOSET, ELEVATOR & STAIRWAY

BOOK 532, PAGE 774: 10' ELECTRIC EASEMENT

BOOK 729, PAGE 342: HOTEL ACCESS EASEMENT

RECEPTION NO. 307130: ACCESS EASEMENT SKI HILL SUBDIVISION

BOOK 559, PAGE 98: TRUCK TURNAROUND LICENSE AGREEMENT

RECEPTION NO. 693288: INTERFACE EASEMENT

RECEPTION NO. 693289: NO BUILD EASEMENT

BOOK 596, PAGE 1487, EX A: BUILDING IMPROVEMENT EASEMENT

RECEPTION NO. 600980: AERIAL TRAMWAY EASEMENT

RECEPTION NO. 680175: SHORING EASEMENT AGREEMENT

(MULTIPLE EXHIBITS), GONDOLA SQUARE ACCESS EASEMENT, WEST SIDE DRAINAGE EASEMENT, ETC.

RECEPTION NO. 693283: PEDESTRIAN ACCESS EASEMENT OSP

BOOK 532, PAGE 802: 10' WATERLINE EASEMENT

RECEPTION NO. 693285: PATIO EASEMENT, DOORWAY EASEMENT, ENTRY EASEMENTS RECEPTION NO. 693280: SANITARY SEWER EASEMENT

RECEPTION NO. 693283: EMERGENCY ACCESS EASEMENT OSP

RECEPTION NO. 693290: SKI AREA EASEMENT, STORM SEWER & DRAINAGE EASEMENT, RECIPROCAL UTILITY EASEMENT, GONDOLA SQUARE ACCESS EASEMENT RECEPTION NO. 693016, BOOK 729, PAGE 338: AGREEMENT (ACCESS TO EASTERN SIDE

RECEPTION NO. 693278: DECLARATION OF EASEMENT

RECEPTION NO. 600979: ACCESS EASEMENT

BOOK 596, PAGE 1487, EX C-7: WALKWAY EASEMENT

RECEPTION NO. 596269, BOOK 596, PAGE 1487, EX C-8 AND C-9: STORM SEWER LINE

EASEMENT AND STORM LINE EASEMENT BOOK 358, PAGE 473: PRIVATE RIGHT-OF-WAY

RECEPTION NO. 661066: OSP EASEMENT AREA

RECEPTION NO. 693018: RIGHT OF WAY EASEMENT (ELECTRIC RECEPTION NO. 693279: SNOWMAKING LINE EASEMENT

BOOK 583, PAGE 238: 30' ACCESS EASEMENT

BOOK 519, PAGE 577: 10' TELEPHONE EASEMENT

BOOK 729, PAGE 343: HOTEL BRIDGE ACCESS, PEDESTRIAN A MAINTENANCE VEHICLE ACCESS

BOOK 532, PAGE 782: ELECTRIC EASEMENT

CALL UTILITY NOTIFICATION CENTER OF

Know what's **below**. Call before you dig. CALL 2 BUSINESS DAYS IN ADVANCE BEFORE YOU DIG, GRADE, OR EXCAVATE FOR THE MARKING OF