


1. EXTEND AND CONNECT NEW SANITARY WASTE TO CIVIL POINT OF CONNECTION (POC) IN AREA SHOWN. PROVIDE 2-WAY CLEANOUT AT SANITARY WASTE/SEWER JUNCTION AT EXTERIOR OF BUILDING. FIELD VERIFY EXACT LOCATION AND INVERT ELEVATION AT POINT OF CONNECTION.


**REVIEWED  
FOR  
CODE  
COMPLIANCE**  
04/01/2025



 **LOWER LEVEL 1 SEWER PLAN**  
3/16" = 1'-0"

DETAIL NOTES THIS SHEET

1. EXTEND AND CONNECT NEW SANITARY WASTE TO CIVIL POINT OF CONNECTION (POC) IN AREA SHOWN. PROVIDE 2-WAY CLEANOUT AT SANITARY WASTE/SEWER JUNCTION AT EXTERIOR OF BUILDING. FIELD VERIFY EXACT LOCATION AND INVERT ELEVATION AT POINT OF CONNECTION.
2. ROUTE WASTE PIPING FROM DISHWASHER TO 2" HD IN CASEWORK, CONNECT VIA 1" AIRGAP AND SECURE DISHWASHER DISCHARGE HOSE TO HUB DRAIN. PROVIDE DUCT ALTERNATE PRICING TO CONNECT VIA DISHWASHER KNOCK OUT ON GARBAGE DISPOSAL; COORDINATE ACCEPTANCE WITH OWNER. INSTALLATION OF DISHWASHER SHALL BE PER IPC 403.4.
3. ROUTE WASTE FROM MECHANICAL UNIT(S) AND/OR WATER HEATERS TO FLOOR DRAIN/SINK IN MECHANICAL CLOSET.
4. NO PIPING SHALL BE ROUTED OVER ELECTRICAL PANEL. COORDINATE ALL PIPING ROUTING IN THIS AREA TO AVOID ELECTRICAL PANEL.
5. PROVIDE AIR ADMITTANCE VALVE UNDER SINK, SHOWN OFFSET IN WALL FOR CLARITY. RE: DIAGRAM FOR ADDITIONAL INFORMATION.
6. ROUTE STEAMER DRAIN TO HUB DRAIN IN WALL.



**NOTICE: DUTY OF COOPERATION**

Release of these plans contemplates further cooperation among the owner, his contractor and the architect. Design and construction are complex. Although the architect and his consultants have performed their services with due care and diligence, they cannot guarantee perfection. Communication is imperfect and the architect cannot control the construction process. Any ambiguity or discrepancy discovered by the user of these plans shall be reported immediately to the architect. Failure to notify the architect compounds misunderstanding and increases construction costs. A failure to cooperate by a simple contractor or architect shall relieve the architect of any responsibility for the consequences. Changes made from the plans without consent of the architect are unauthorized and shall relieve the architect of responsibility for all consequences arising out of such changes.

All design, documents and data prepared by Eric Smith Associates, P.C. as instruments of service shall remain property of Eric Smith Associates, P.C. and shall not be copied, changed or disclosed in any form whatsoever without first obtaining the express written consent of Eric Smith Associates, P.C.

Eric Smith Associates, P.C.

## REVISIONS

[illegible]

ASTRID BUILDING 7  
STEAMBOAT SPRINGS, COLORADO




**1919 SEVENTH STREET  
BOULDER, COLORADO, 80302  
(303) 442-5458, (303) 442-4745 FAX**

<b>Job Number:</b>	23035-7
<b>Date:</b>	03/ 21/ 24
<b>Drawn By:</b>	CK&SS
<b>Checked By:</b>	MV

<b>Project Phase</b>
PERMIT
<b>Sheet Title</b>
LOWER LEVEL   SEWER PLAN

Sheet Number  
P1.1



 LOWER LEVEL 1 PIPING PLAN  
3/16" = 1'-0"

DETAIL NOTES THIS SHEET

1. NO PIPING SHALL BE ROUTED OVER ELECTRICAL PANEL, COORDINATE ALL PIPING ROUTING IN THIS AREA TO AVOID ELECTRICAL PANEL.
2. PROVIDE UNIT SHUTOFF IN APPROXIMATE LOCATION SHOWN PRIOR TO SUPPLY ANY FIXTURES ON THIS LEVEL; COORDINATE CREDIT INSTALLATION LOCATION AND ACCESS WITH G.C. AND ARCH.
3. OFFSET 1/2" HW LINE FOR DISHWASHER CONNECTION, PROVIDE WITH DEDICATED ISOLATION VALVE W/SHOCK ARRESTOR. ROUTE INDIRECT WASTE FROM DISHWASHER TO 1/2" HUB DRAIN IN CASEWORK, PROVIDE DEDUCT ALTERNATE PRICING TO CONNECT TO FOOD WASTE DISPOSAL PER IPC 409.4, WHERE APPLICABLE.
4. WALLBOX FOR REFRIGERATOR ICE MAKER CONNECTIONS, PROVIDE WITH SHUTOFF VALVE AND SHOCK ARRESTOR. PROVIDE FIRE RATED ICE MAKER BOX WHERE LOCATED WITHIN FIRE RATED WALL; COORDINATE WITH ARCH. MAKE CONNECTION TO REFRIGERATOR PER MANUFACTURERS INSTRUCTIONS.
5. ROUTE 1/2" CW LINE TO STEAMER IN APPROXIMATE LOCATION SHOWN; COORDINATE ALL PIPE ROUTING IN WALL WITH G.C. AND ARCH. RE: MANUFACTURERS INSTRUCTIONS FOR CONNECTION DETAILS.
6. ROUTE 1/2" HW AND 3/4" CW DOWN IN WALL; ROUTE 1/2" HW AND CW IN FLOOR TO BT-2 AND 1/2" CW IN FLOOR TO WC; COORDINATE ROUTING WITH G.C. AND ARCH.
7. PROVIDE THERMOSTATIC BALANCING VALVE (CIRCUIT SOLVER CS-3/4-120) IN APPROXIMATE LOCATION SHOWN; COORDINATE ACCESS PANEL AS REQUIRED WITH G.C. AND ARCH.



### NOTICE: DUTY OF COOPERATION

Release of the plans contemplates further cooperation among the owner, his contractor and the architect. Design and construction are complex. Although the architect and his consultants have performed their services with due care and diligence, the owner, contractor and architect cannot be expected to foresee every contingency cannot be anticipated, any ambiguity or discrepancy discovered by the use of these plans shall be reported immediately to the architect. Failure to notify the architect compounds misunderstanding and increases construction costs. A failure to cooperate by a simple notice to the architect shall relieve the architect from responsibility for the consequences. Changes made from the plans without consent of the architect are unauthorized and shall relieve the architect of responsibility for all consequences arising out of such changes.

All design, documents and data prepared by Eric Smith Associates, P.C. as instruments of service shall remain property of Eric Smith Associates, P.C. and shall not be copied, changed or disclosed in any form whatsoever without first obtaining the express written consent of Eric Smith Associates, P.C.

Eric Smith Associates, P.C.

## REVISIONS

[illegible]

ASTRID BUILDING 7  
STEAMBOAT SPRINGS, COLORADO



**1919 SEVENTH STREET  
BOULDER, COLORADO, 80302  
(303) 442-5458, (303) 442-4745 FAX**


<b>Job Number:</b>	23035-7
<b>Date:</b>	03/21/24
<b>Drawn By:</b>	CK&SS
<b>Checked By:</b>	MV

## Project Phase

PERMIT
<b>Sheet Title</b>
LOWER LEVEL PIPING PLAN

Sheet Number

## P1.2



 **LOWER LEVEL 2 SEWER PLAN**  
3/16" = 1'-0"

DETAIL NOTES THIS SHEET

1. ROUTE WASTE PIPING FROM DISHWASHER TO 2" HD IN CASEWORK, CONNECT VIA 1" AIRGAP AND SECURE DISHWASHER DISCHARGE HOSE TO HUB DRAIN. PROVIDE DEDUCT ALTERNATE PRICING TO CONNECT VIA DISHWASHER KNOCK OUT ON GARBAGE DISPOSAL; COORDINATE ACCEPTANCE WITH OWNER. INSTALLATION OF DISHWASHER SHALL BE PER IPC 409.4.
2. ROUTE WASTE FROM MECHANICAL UNIT(S) AND/OR WATER HEATERS TO FLOOR DRAIN/SINK IN MECHANICAL CLOSET.
3. NO PIPING SHALL BE ROUTED OVER ELECTRICAL PANEL, COORDINATE ALL PIPING ROUTING IN THIS AREA TO AVOID ELECTRICAL PANEL.
4. PROVIDE AIR ADMITTANCE VALVE UNDER SINK, SHOWN OFFSET IN WALL. FOR CLARITY, RE: DIAGRAM FOR ADDITIONAL INFORMATION.
5. ROUTE STEAMER DRAIN TO HUB DRAIN IN WALL.



**NOTICE: DUTY OF COOPERATION**

Release of these plans constitutes further cooperation among the owner, his contractor and the architect. Design and construction are complex. Although the architect and his consultants have performed their services with due care and diligence, they cannot guarantee perfection. Communication is imperfect and every cooperation contingency cannot be anticipated. Any ambiguity or discrepancy discovered in these plans shall be reported immediately to the architect. Failure to notify the architect compounds misunderstanding and increases construction costs. A failure to cooperate by a simple notice to the architect will relieve the architect of any responsibility for consequences. Changes made from the plans without the consent of the architect are unauthorized and shall relieve the architect of responsibility for all consequences arising out of such changes.

All design, documents and data prepared by Eric Smith Associates, P.C. as instruments of service shall remain property of Eric Smith Associates, P.C. and shall not be copied, changed or disclosed in any form whatsoever without first obtaining the express written consent of Eric Smith Associates, P.C.

## REVISIONS

[illegible]

ASTRID BUILDING 7  
STEAMBOAT SPRINGS, COLORADO



**1919 SEVENTH STREET  
BOULDER, COLORADO, 80302  
(303) 442-5458, (303) 442-4745 FAX**


<b>Job Number:</b>	23035-7
<b>Date:</b>	03/21/24
<b>Drawn By:</b>	CK&SS
<b>Checked By:</b>	MV

<b>Project Phase</b>
PERMIT
<b>Sheet Title</b>
LOWER LEVEL 2 SEWER PLAN


Sheet Number
P2.1




1. NO PIPING SHALL BE ROUTED OVER ELECTRICAL PANEL, COORDINATE ALL PIPING ROUTING IN THIS AREA TO AVOID ELECTRICAL PANEL..
2. PROVIDE ACCESS TO UNIT SHUT-OFF IN FLOOR.
3. OFFSET 1/2" HW LINE FOR DISHWASHER CONNECTION, PROVIDE WITH DEDICATED ISOLATION VALVE W/SHOCK ARRESTOR, ROUTE INDIRECT WASTE FROM DISHWASHER TO 1-1/2" HUB DRAIN IN CASEWORK. PROVIDE DEDUCT ALTERNATE PRICING TO CONNECT TO FOOD WASTE DISPOSAL PER IPC 409.4, WHERE APPLICABLE.
4. WALLBOX FOR REFRIGERATOR ICE MAKER CONNECTIONS, PROVIDE WITH SHUTOFF VALVE AND SHOCK ARRESTOR, PROVIDE FIRE RATED ICE MAKER BOX WHERE LOCATED WITHIN FIRE RATED WALL; COORDINATE WITH ARCH. MAKE CONNECTION TO REFRIGERATOR PER MANUFACTURERS INSTRUCTIONS.
5. ROUTE 1/2" CW LINE TO STEAMER IN APPROXIMATE LOCATION SHOWN; COORDINATE ROUTING WITH G.C. AND ARCH. RE: MANUFACTURERS INSTRUCTIONS FOR CONNECTION DETAILS.

[illegible]


ASTRID BUILDING 7  
STEAMBOAT SPRINGS, COLORADO



<b>Project Phase</b>
PERMIT
<b>Sheet Title</b>
LOWER LEVEL 2 PIPING PLAN
<b>Sheet Number</b>
P2.2



 LOWER LEVEL 2 PIPING PLAN  
3/16" = 1'-0"



# MAIN LEVEL SEWER PLAN

3/16" = 1'-0"

## DETAIL NOTES THIS SHEET

1. ROUTE WASTE PIPING FROM DISHWASHER TO 2" HD IN CASKWORK, CONNECT VIA 1" AIRGAP AND SECURE DISHWASHER DISCHARGE HOSE TO HUB DRAIN. PROVIDE DEDUCT ALTERNATE PRICING TO CONNECT VIA DISHWASHER KNOCK OUT ON GARBAGE DISPOSAL; COORDINATE ACCEPTANCE WITH OWNER. INSTALLATION OF DISHWASHER SHALL BE PER IPC 409.4.
2. ROUTE WASTE FROM MECHANICAL UNIT(S) AND/OR WATER HEATERS TO FLOOR DRAIN/SINK IN MECHANICAL CLOSET.
3. NO PIPING SHALL BE ROUTED OVER ELECTRICAL PANEL, COORDINATE ALL PIPING ROUTING IN THIS AREA TO AVOID ELECTRICAL PANEL..
4. TERMINATE PRIMARY AND OVERFLOW ROOF DRAIN VIA ARCHITECTURAL LAMBS TONGUE DOWNSPOUT IN APPROXIMATE AREA SHOWN; OVERFLOW TERMINATION TO BE HIGH ON BUILDING FOR IDENTIFICATION OF BLOCKED PRIMARY ROOF DRAIN. COORDINATE MOUNTING HEIGHT WITH G.C. AND ARCHITECT.
5. PROVIDE AIR ADMITTANCE VALVE UNDER SINK, SHOWN OFFSET IN WALL FOR CLARITY. RE: DIAGRAM FOR ADDITIONAL INFORMATION.
6. ROUTE STEAMER DRAIN TO HUB DRAIN IN WALL.

**REVIEWED  
FOR  
CODE  
COMPLIANCE**  
04/01/2025



**NOTICE: DUTY OF COOPERATION**

Release of these plans contemplates further cooperation among the owner, his contractor and the architect. Design and construction are complex. Although the architect and his consultants have performed their services with due care and diligence, they cannot guarantee perfection. Communication is imperfect and every contingency cannot be anticipated. Any ambiguity or discrepancy discovered by the use of these plans shall be reported immediately to the architect. It is the intent of this release to avoid misunderstanding and increase construction costs. A failure to cooperate by a simple notice to the architect shall relieve the architect from responsibility for the consequences. Changes made from the plans without consent of the architect are unauthorized and shall relieve the architect of responsibility for all consequences arising out of such changes.


All design, documents and data prepared by Eric Smith Associates, P.C. as instruments of service shall remain property of Eric Smith Associates, P.C. and shall not be copied, changed or disclosed in any form whatsoever without first obtaining the express written consent of Eric Smith Associates, P.C.

Eric Smith Associates, P.C.

## REVISIONS

[illegible]

ASTRID BUILDING 7  
STEAMBOAT SPRINGS, COLORADO



**ERIC SMITH ASSOCIATES, P.C.**  
1919 SEVENTH STREET  
BOULDER, COLORADO, 80302

<b>Job Number:</b>	23035-1
<b>Date:</b>	03/21/2
<b>Drawn By:</b>	CK&SS
<b>Checked By:</b>	MV


## Project Phase

PERMIT	
<b>Sheet Title</b>	
MAIN LEVEL SEWER PLAN	

Sheet Numbe

# P3.1





 **MAIN LEVEL PIPING PLAN**  
3/16" = 1'-0"

DETAIL NOTES THIS SHEET

1. EXTEND AND CONNECT NEW COMBINED FIRE SPRINKLER AND DOMESTIC COLD WATER PIPING TO CIVIL POG. FIELD VERIFY EXACT LOCATION AND CONNECTION. BASIS OF DESIGN IS EXTERIOR METER PIT WITH 4" TAP/METER ASSEMBLY. RE: DIAGRAM FOR ADDITIONAL INFORMATION.
2. NO PIPING SHALL BE ROUTED OVER ELECTRICAL PANEL. COORDINATE ALL PIPING ROUTING IN THIS AREA TO AVOID ELECTRICAL PANEL..
3. PROVIDE UNIT SHUTOFF IN APPROXIMATE LOCATION SHOWN PRIOR TO SUPPLY ANY FIXTURES ON THIS LEVEL; COORDINATE EXACT INSTALLATION LOCATION AND ACCESS WITH G.C. AND ARCH.
4. OFFSET 1/2" HW LINE FOR DISHWASHER CONNECTION, PROVIDE WITH DEDICATED ISOLATION VALVE W/SHOCK ARRESTOR. ROUTE INDIRECT WASTE FROM DISHWASHER TO 1-1/2" HUB DRAIN IN CASEWORK. PROVIDE DEDUCT ALTERNATE PRICING TO CONNECT TO FOOD WASTE DISPOSAL PER IPC 409.4, WHERE APPLICABLE.
5. WALLBOX FOR REFRIGERATOR ICE MAKER CONNECTIONS, PROVIDE WITH SHUTOFF VALVE AND SHOCK ARRESTOR. PROVIDE FIRE RATED ICE MAKER BOX WHERE LOCATED WITHIN FIRE RATED WALL; COORDINATE WITH ARCH. MAKE CONNECTION TO REFRIGERATOR PER MANUFACTURERS INSTRUCTIONS.
6. ROUTE 1/2" CW LINE TO STEAMER IN APPROXIMATE LOCATION SHOWN; COORDINATE ROUTING WITH G.C. AND ARCH. RE: MANUFACTURERS INSTRUCTIONS FOR CONNECTION DETAILS.
7. STUB OUT DOMESTIC COLD WATER LINE FOR IRRIGATION POINT OF CONNECTION. IRRIGATION CONTRACTOR TO PROVIDE CROSS CONNECTION DEVICE SUCH AS BACKFLOW ON EXTERIOR OF BUILDING. FIELD VERIFY AND COORDINATE EXACT LOCATION OF IRRIGATION STUB-OUT WITH CIVIL AND LANDSCAPE DESIGN. RE: DIAGRAM FOR ADDITIONAL INFORMATION.
8. COORDINATE WITH LOCAL UTILITY COMPANY FOR 14" WC GAS SERVICE. FIELD VERIFY EXACT METER BANK PLACEMENT WITH UTILITY PROVIDER; NOTIFY ENGINEER IF METER BANK IS RELOCATED FROM LOCATION SHOWN. REGULATORS MUST BE INSTALLED AT APPLIANCES PRIOR TO GAS BEING TURNED ON.

**REVIEWED  
FOR  
CODE  
COMPLIANCE**  
04/01/2025



### NOTICE: DUTY OF COOPERATION

Release of these plans contemplates further operation among the owner, his contractor and the architect. Design and construction are complex. Although the architect and his consultants have performed their services with due care and diligence, they cannot guarantee perfection. Communication is perfect and every contingency cannot be anticipated. Any ambiguity or discrepancy discovered by the use of these plans and specifications shall be the responsibility of the architect. Failure to notify the architect compounds misunderstanding and increases construction costs. A promise to cooperate by a simple notice to the architect shall relieve the architect from responsibility for the consequences. Changes made from the plans without consent of the architect are void and shall relieve the architect of responsibility for all consequences arising out of such changes.

All design, documents and data prepared by Eric Smith Associates, P.C. as instruments of service shall remain the property of Eric Smith Associates, P.C. and shall not be copied, reproduced or disclosed in any form whatsoever without first obtaining the express written consent of Eric Smith Associates, P.C.

## REVISIONS

[illegible]

ASTRID BUILDING 7  
STEAMBOAT SPRINGS, COLORADO



**1919 SEVENTH STREET  
BOULDER, COLORADO, 80302  
(303) 442-5458, (303) 442-4745 FAX**

<b>Job Number:</b>	23035-7
<b>Date:</b>	03/21/24
<b>Drawn By:</b>	CK&SS
<b>Checked By:</b>	MV

## Project Phase

PERMIT
<b>Sheet Title</b>
MAIN LEVEL PIPING PLAN


Sheet Number

## P3.2



P4.1





 **UPPER LEVEL PIPING PLAN**  
3/16" = 1'-0"

DETAIL NOTES THIS SHEET

1. NO PIPING SHALL BE ROUTED OVER ELECTRICAL PANEL, COORDINATE ALL PIPING ROUTING IN THIS AREA TO AVOID ELECTRICAL PANEL.
2. PROVIDE THERMOSTATIC BALANCING VALVE (CIRCUIT SOLVER GS-3/4-120) IN WALL UNDER SINK IN APPROXIMATE LOCATION SHOWN. COORDINATE ACCESS PANEL LOCATION WITH G.C. AND ARCHITECT. RE: DIAGRAM FOR ADDITIONAL INFORMATION.
3. OFFSET 1/2" HW LINE FOR DISHWASHER CONNECTION, PROVIDE WITH DEDICATED ISOLATION VALVE W/SHOCK ARRESTOR, ROUTE INDIRECT WASTE FROM DISHWASHER TO 1-1/2" HUB DRAIN IN CASEWORK. PROVIDE DEDUCT ALTERNATE PRICING TO CONNECT TO FOOD WASTE DISPOSAL PER IPC 408.4, WHERE APPLICABLE.
4. WALLBOX FOR REFRIGERATOR ICE MAKER CONNECTIONS, PROVIDE WITH SHUTOFF VALVE AND SHOCK ARRESTOR. PROVIDE FIRE RATED ICE MAKER BOX WHERE LOCATED WITHIN FIRE RATED WALL; COORDINATE WITH ARCH. MAKE CONNECTION TO REFRIGERATOR PER MANUFACTURERS INSTRUCTIONS.
5. ROUTE 1/2" CW LINE TO STEAMER IN APPROXIMATE LOCATION SHOWN; COORDINATE ROUTING WITH G.C. AND ARCH. RE: MANUFACTURERS INSTRUCTIONS FOR CONNECTION DETAILS.



**NOTICE: DUTY OF COOPERATION**

Release of these plans contemplates further cooperation among the owner, his contractor and the architect. Design and construction are complex. Although the architect and his consultants have performed their services with due care and diligence, they cannot guarantee perfection. Communication is imperfect and every contingency cannot be anticipated. Any release of the architect's liability by the use of these plans shall be reported immediately to the architect. Failure to notify the architect compounds misunderstanding and increases construction costs. A failure to cooperate by a simple notice to the architect shall relieve the architect from responsibility for the consequences. Changes made from the plans without consent of the architect are unauthorized and shall relieve the architect of responsibility for all consequences arising out of such changes.

All design, documents and data prepared by Eric Smith Associates, P.C. as instruments of service shall remain property of Eric Smith Associates, P.C. and shall not be copied, changed or disclosed in any form whatsoever without first obtaining the express written consent of Eric Smith Associates, P.C.

Eric Smith Associates, P.C.

## REVISIONS

[illegible]

ASTRID BUILDING 7  
STEAMBOAT SPRINGS, COLORADO



**ERIC SMITH ASSOCIATES, P.C.**  
**1919 SEVENTH STREET**  
**BOULDER, COLORADO, 80302**  
**(303) 442-5458, (303) 442-4745 FAX**

<b>Job Number:</b>	23035-7
<b>Date:</b>	03/21/24
<b>Drawn By:</b>	CK&SS
<b>Checked By:</b>	MV

## Project Phase

PERMIT
<b>Sheet Title</b>
UPPER LEVEL PIPING PLAN

Sheet Number

P4.2







All design, documents and data prepared by Eric Smith Associates, P.C. as instruments of service shall remain property of Eric Smith Associates, P.C. and shall not be copied, changed or disclosed in any form whatsoever without first obtaining the express written consent of Eric Smith Associates, P.C.


[illegible]

**ESA**

**ERIC SMITH ASSOCIATES, P.C.**  
1919 SEVENTH STREET  
BOULDER, COLORADO, 80302  
(303) 442-5458, (303) 442-4745 FAX

<b>Project Phase</b>
PERMIT
<b>Sheet Title</b>
OVERALL DWV ISOMETRIC

Sheet Number
P6.2





DIVISION 21 - FIRE SUPPRESSION

SECTION 21 00 00 - COMMON WORK RESULTS FOR FIRE SUPPRESSION

- 1.01 **WORK INCLUDED**
- A. The work included by this division of the specifications includes furnishing all labor, materials, equipment, and services, including minor items omitted but necessary to construct and install the complete systems described by the Contract Documents and specified below. "Contractor" refers to the Fire Sprinkler Contractor. The general conditions of the specifications apply and are included in this part of this section.
1. Fire sprinkler systems
- 1.02 **SEE SECTION 22 05 00 FOR BASIC MATERIALS AND METHODS**

SECTION 21 13 00 - FIRE SUPPRESSION SPRINKLER SYSTEM

- 2.01 **WORK INCLUDED**
- A. Provide complete automatic fire protection systems, including but not limited to inside piping, sprinkler heads, valves, hangers and supports, sleeves, fire department connections and accessories, fire hose cabinets, valves. Entire installation shall be as required by the local authorities. Consult with local authorities to determine all local requirements before submitting a bid.
1. The sprinkler system(s) shall be as follows: Wet system throughout. Type 13R
- B. Secure and pay for all necessary permits and certificates of inspection, and present to Owner with the signed certificates of final inspection.
- C. Coordinate this work with all other trades so as to have a minimum of interference. **INSTALLATION SHALL NOT BEGIN UNTIL DUCTWORK IS INSTALLED OR WRITTEN AUTHORIZATION IS MADE BY THE OWNER.**
- D. Accomplish all necessary cutting and patching for installation of piping and equipment, and provide all cutting as directed by Architect. Where necessary to cut chases in walls, reinforce walls as directed. After work is installed, patch holes to match original finish.
- E. The system design including pipe sizing and location, configuration of branches and head connections, shall accommodate the installation of up/down heads in all areas which may or may not have a dropped ceiling.
- F. **RELATED WORK:** Basic materials and methods: Section 22 05 00.

- 2.02 **QUALITY ASSURANCE**
- A. Sprinkler equipment and installation to be approved by local fire authority.
- B. Provide a complete automatic fire protection system as required. System shall be complete in all respects and in accordance with all applicable codes, ordinances, International Building Code, and NFPA Volume 2, Section 13 and NFPA Volume 2, Section 14.
- C. The system shall be designed by a firm regularly engaged in the design and installation of automatic sprinkler systems in accordance with the requirements of the National Board of Fire Underwriters. Architect may require evidence to support the above qualifications and may reject any proposed installer who cannot show suitable experience.
- D. All materials and equipment used in the installation of the sprinkler system shall be as approved in the Underwriters' Laboratories' list of inspected fire protection equipment and materials, or the Factory Mutual Laboratories' list of approved equipment and fire protection devices involving fire hazard, and shall be the latest product of the manufacturer.

- 2.03 **SUBMITTALS**
- A. Submit shop drawings showing proposed layout of Fire Protection System, showing actual equipment to be used, complete with such dimensions as are required to accurately install the system, drawn to a minimum scale of 1/8" equals 10". Drawings shall be approved by Underwriters and local authority before submission to Architect and Engineer (four copies).
- B. Shop drawings shall show detailed routing of piping. Piping shall be installed to clear all other items of equipment and Architectural and structural components within the building. Show all details required to make a complete installation from the shop drawings. After approval of drawings has been obtained, install all equipment exactly as shown. Obtain approval from Architect/Engineer to make any changes from shop drawings.
- C. Shop drawings shall clearly show any piping that will not be concealed in the building structure

- 3.01 **ACCEPTABLE MANUFACTURERS**
- A. Equipment shall be by Grinnell, Viking, Star, Reliable, Globe, Crocker-Standards, Central, Potter-Roemer, or approved substitute.
- 3.02 **INTERIOR FIRE SERVICE PLUMBING**
- A. Pipe shall be schedule 40, black seamless steel, ASTM A120, ASTM 53. Pipe 2" or larger may be schedule 10, grooved black steel pipe. Fittings may be style 74 or 75 "Victaulic" mechanical coupling system for 300 PSI working pressure.
- B. Fittings and joints shall be as follows:
1. 2" and larger : Welded with standard weight fittings or "Victaulic" fittings.
2. 1-1/2" and smaller : Serewed with 150 lb. malleable iron fittings.

- 3.03 **FIRE DEPARTMENT SIAMSESE CONNECTION**
- A. Provide a cast brass flush wall mounted fire department connection, adequately sized for the application with threads, fittings, etc acceptable to the local fire department. Connection shall include drop clapper, pin lug hose thread swivels, pin lug plugs and chain. The connection shall be labelled as directed by the local Fire Department. All components shall be chrome-plated.

- 3.04 **WATER FLOW ALARMS**
- A. Water flow indicator shall be electric, vane-type detector with two sets of normally open contacts and a time retard to prevent false alarms.

- 3.05 **AUTOMATIC SPRINKLERS**
- A. Sprinklers shall have temperature ratings as required by NFPA Standard No. 13 for the sprinkler location. Verify exact head types in finished areas with Architect. Provide specific head types as follows. The following are catalog numbers of Grinnell.
1. Finished areas (ceilings): Semi-recessed, polished chrome pendant heads. Heads shall be Model A with recessed closure.
2. Finished areas (wall):Exposed sidewall (Universal Model A).
3. Unfinished areas (ceiling): Exposed pendant or upright head, as required by the application (Universal Model A).
4. Areas exposed to freezing temperatures: Dry pendant (Model F 960).
- B. Provide steel sprinkler guards on heads, which are exposed to physical damage.

- 3.06 **TAMPER SWITCH**
- A. Provide an electric supervisory monitor switch at the required valves. Grinnell Model F640 or as required.
- 3.07 **HORN/LIGHT**
- A. Provide an electric combination horn/light, suitable for exterior application, rated for the appropriate voltage.

- 3.08 **PIPING INSTALLATION**
- A. All piping shall be concealed wherever possible. Exceptions must be clearly marked on shop drawings and shall not be installed until approved by Architect.
- B. If exposed, piping shall be installed in the most direct, straight, and least obtrusive manner possible, and as close to walls and ceilings as is consistent with good workmanship.
- C. Install piping graded to low points and in manner to make it possible to test and empty entire system.
- D. Pipe and fittings shall be inspected for soundness and cleaned of all dirt and other foreign matter prior to being installed. All damaged pipe and fittings shall be rejected. Heads shall be covered, and system shall be ready for painting.
- E. Protect open pipe ends whenever work is suspended during construction, to prevent foreign bodies entering and lodging therein. Use cast iron or malleable iron caps, or other methods as approved by the Architect

- 3.09 **VALVE IDENTIFICATION**
- A. Drain valves, test valves, and control valves shall be identified with a stamped metal tag indicating their use.
- 3.10 **TESTING**
- A. A T-1 inspector's test connection shall be installed at the farthest and most remote location in the system with discharge running to the exterior of the building.
- B. All piping and equipment shall be tested and proved tight under a hydrostatic pressure of 150% of the main pressure or 200 psig, whichever is larger. The test shall be conducted for a six-hour continuous period, with not be more than 2 pounds of pressure loss during this period in any part of the system. Any leaks found shall be repaired and the pressure test repeated.
- C. All tests shall be performed in the presence of the Architect or authorized representative of the Owner.

- 3.11 **FLUSHING**
- A. Flush piping system thoroughly with clear water to placing automatic sprinkler system in operation.
- 3.12 **SPRINKLER CABINET**
- A. Provide a reserve sprinkler cabinet with at least six spare sprinkler heads or a minimum of two of each type used for systems with less than 300 heads total. Cabinet shall be equipped with two special sprinkler wrenches. Cabinet shall be a labeled, metal, wall-mounted type with red enamel finish and a rigid hinged and locked door. Two keys shall be provided.

DIVISION 22 - PLUMBING

SECTION 22 05 00 - COMMON WORK RESULTS FOR PLUMBING

- 1.01 **WORK INCLUDED**
- A. The work included by this division of the specifications includes furnishing all labor, materials, equipment, and services, including minor items omitted but necessary to construct and install the complete systems described by the Contract Documents and specified below. "Contractor" refers to the Mechanical Contractor. The general conditions of the specifications apply and are included in this part of this section.
1. Gas piping system
2. Domestic hot and cold water systems
3. Interior sanitary sewer system
4. Interior storm sewer system and discharge
- 1.02 **CODES AND REGULATIONS**
- A. Comply with state and local codes, and utility company regulations. Final interpretations will be made by the local inspection authority. The Contractor to verify the governance of the following Codes, including any local amendments and supplementary codes such as the Codes of the National Fire Protection Association:
1. Building Code: 2021 International Building Code
2. Plumbing Code: 2021 International Plumbing Code
3. Mechanical Code: 2021 International Mechanical Code
4. Fire Code: 2021 International Fire Code
5. Gas Code: 2021 International Fuel Gas Code
6. Energy Code: 2021 International Energy Conservation Code
7. Electrical Code: 2023 National Electrical Code

- 1.03 **EQUIPMENT AND MATERIALS STANDARDS**
- A. Equipment and materials shall be new, UL-listed for the use intended, and free from damage or defect. They shall comply with the latest industry standards.

- 1.04 **CONTRACT DRAWINGS**
- A. Illustrate the general design and extent of performance required. All dimensions and locations shall be taken from the Architectural drawings. Consult with Architectural plans and locate all ceiling equipment where indicated on reflected ceiling plans

- 1.05 **SHOP DRAWINGS**
- A. Submit products data and/or shop drawings as required by the Architect for the following:

1. Insulation
2. Valves
3. Plumbing fixtures and appurtenances.
4. Pumps
- B. Quality of specific equipment is established by manufacturer's catalog number. Alterations caused by any Substitution shall be accomplished at no additional expense to the Owner.
- C. Manufacturers not listed may submit for acceptance as an "approved equivalent." Requests for an "equivalent" means "approved equivalent". Four copies of such submittal must be received by the Engineer seven (7) working days prior to bid date.
- 1.06 **WARRANTY**
- A. The Contractor shall be responsible for the successful operation of mechanical systems, equipment, and materials installed under this Contract for a period of one year from the date of final acceptance. Defective equipment or materials shall be repaired or replaced at no expense to the Owner. Provide four complete service and maintenance calls spaced at equal intervals during the warranty period.
- 1.07 **PRODUCT HANDLING AND CLEAN UP**
- A. Equipment shall be left clean and undamaged, to the satisfaction of the Owner. The General Conditions take precedence.
- 1.08 **CUTTING AND REPAIRING**
- A. The contractor shall be responsible for all cutting, drilling, welding, and repair required for his portion of the work. Coordinate with the Architect. The General Conditions take precedence.
- 1.09 **OPERATING AND MAINTENANCE DATA**
- A. Provide the Owner with operating and maintenance instructions (four copies) required for operation of all mechanical systems. Bind the written instructions in a notebook. The General Conditions take precedence. The manuals shall include the following items:
1. Operating manual and spare parts list for each piece of equipment.
2. Preventive maintenance schedule for lubricating and checking each piece of equipment.
3. Instructions on who to call for service during the warranty period.

- 1.10 **PERMITS**
- A. The contractor shall pay for all fees, taxes, secure permits, licenses, and inspections required for the project.
- 1.11 **TEMPORARY SERVICES**
- A. Provide temporary water service for construction, as required by the General Contractor.

- 1.12 **COORDINATION**
- A. Coordinate outlet device and equipment locations with the Architectural Plans and work of other trades. Locate on horizontal and vertical lines to avoid interference and to provide functional use of all equipment. Verify electrical power characteristics before ordering equipment.
- B. Electrical work performed by this contractor will conform to the standards of Division 26-28. Mechanical equipment motors and controls shall be furnished, set in place, and wired according with the following schedule unless otherwise noted or specified. MC = Division 21-23 EC = Division 26-28
- | Item                         | Furn | Set | Power  | Control |
|------------------------------|------|-----|--------|---------|
|                              | By   | By  | Wiring | Wiring  |
| Combination starters         | MC   | EC  | EC     | MC      |
| Equipment motors             | MC   | MC  | EC     | --      |
| Motor starters & O.L. relays | MC   | EC  | EC     | MC      |
| Disconnect switches          | EC   | EC  | EC     | MC      |
| Thermal overload heaters (1) | EC   | EC  | EC     | --      |
| Variable Speed Drives        | MC   | EC  | EC     | MC      |
| Control relays/transformers  | MC   | MC  | EC     | MC      |
| Temperature control panels   | MC   | MC  | EC     | MC      |
| Temperature control wiring   | MC   | MC  | --     | MC      |
| Actuator and solenoid wiring | MC   | MC  | --     | MC      |
| Pushbuttons & pilot lights   | MC   | MC  | --     | MC      |
| Room thermostats             | MC   | EC  | --     | MC      |
| Thermostats: line voltage    | EC   | EC  | EC     | --      |
- C. The general guideline for the division between control (by MC) wiring and power wiring (by EC) is that power wiring carries the current which energizes a motor, control wiring does not. Control wiring may be 120V, which would be the responsibility of the MC. Control motors are wired by the MC.
- D. Examine the site and become aware of existing conditions, utilities, and other issues affecting the satisfactory completion of the project.

- 1.13 **DELIVERY, STORAGE, HANDLING**
- A. Provide necessary hauling and hoisting equipment. Protect the materials of this Division before, during, and after installation.
- 1.14 **AS-BUILT DRAWINGS**
- A. Keep a current set of "as-built" drawings on site. Upon completion of the work, furnish engineer with a reproducible prints showing the "as-built" installation.

- 1.15 **PROJECT/SITE CONDITIONS**
- A. Visit the site to become familiar with location and the various conditions affecting the work, including existing utilities.
- 1.16 **PLAN VERIFICATION**
- A. After completion of the bidding and selection process, prior to awarding the contract, the contractor must review and verify the contract documents in their entirety, including those of other trades. At this time discrepancies, conflicts, omissions, etc in the contract documents must be documented. Alterations to the contract will be made at that time to include such items, as well other modifications which might be made by the Owner. After award of the contract, change orders caused by discrepancies, conflicts, omissions in the contract documents will not be allowed.

- 2.01 **EXPANSION JOINTS, GUIDES, AND ANCHORS**
- A. Provide expansion joints or loops, guides, and anchors in piping to allow for expansion and contractions. Expansion joints shall be bellows type.
- 2.02 **VALVES**
- A. Gate valves 2" and smaller shall be cast bronze, rising stem, solid disc, 200 PSI WOG
- B. Ball valves 2" and smaller shall be cast bronze, full port, stainless steel ball, teflon seats, 400 PSI WOG.
- C. Butterfly valves 2" and smaller shall be cast bronze, stainless steel disc, surrounding fluorelastomer seal, 350 PSI WOG.
- D. Check valves shall be horizontal, swing-cast bronze, bronze disc, 200 PSI WOG.
- E. Valves shall be domestically manufactured by Milwaukee, Powell, Nibco, or equivalent.

- 2.03 **RELIEF VALVES**
- A. Relief valves shall be all-bronze A.S.M.E. rated valves with external test levers, sized in accordance with the instructions of the appropriate manufacturer. Pipe discharge outside to or floor drain where possible and per code. Valves shall be manufactured by Watts or equivalent.
- 2.04 **FLEXIBLE CONNECTORS**
- A. Connectors in piping shall be made with molded teflon or neoprene and nylon bellows, metal reinforcing rings, flanged ends and control rods, suitable for 40F to 200F temperature range and 125 lbs. pressure. Alternative shall be stainless steel inner hose with braided exterior sleeve for steel pipe or bronze inner hose with braided exterior sleeve for copper piping. Metra-flex Company, or equivalent.

- 2.05 **SPECIALTIES**
- A. P/T Plugs: 1/4" diameter, brass with Nordel core, Sisco or equivalent.
- B. Pressure Gauges: 4 1/2" dial type, aluminum housing. Ashcroft 1010 or equivalent.
- C. Thermometers: 7" red reading mercury type. Palmer Instruments or equivalent.
- 2.06 **ELECTRICAL**
- A. Lugs: Lugs for wiring connections shall be rated for copper and aluminum, and shall have a minimum rating of 75C.
- B. Electric motors shall be rated for the appropriate application: wet location (TEFC); submersible; explosion proof, VFDs, etc.

- 2.07 **ACCESS PANELS**
- A. The Mechanical Contractor shall furnish and install access panels where required for access to equipment. Access panels shall be adequately sized, of a type approved by the Architect and shall be fire or smoke-rated as required.
- 2.08 **EXCAVATION AND BACKFILLING**
- A. Provide excavating and backfilling for Mechanical Work. Backfill in 12" layers, mechanically tamped to 95% proctor standards. Protect according to OSHA standards. The General Conditions take precedence. Verify the location of underground utilities before excavation; the contractor is responsible for any damage to underground utilities. Restore existing paving, curbs, sod, bushes, etc to match surroundings.

- 2.09 **START-UP PROCEDURES**
- A. Follow manufacturer's recommended procedures in starting up the equipment; damage caused during start-up shall be replaced at no expense to the owner.

- 2.10 **PIPING INSTALLATION**
- A. Install piping plumb and straight, parallel with walls and partitions. Conceal piping within structure whenever practical. Provide drain valves at all low points, vents at all high points, to allow complete drainage.
- B. Material and methods per ASME, ASTM, ASA, AWS, and National Plumbing Code Handbook
- C. Provide unions or flanges in piping connections to each valve, device, or item of equipment. Install each union or flange to permit the removal of parts and equipment for inspection or cleaning, without disconnecting any piping, except unions or flanges. Provide dielectric unions at locations with dissimilar materials.
- D. Piping on the roof will be supported above the roof on roof pads. The pads shall be approximately 6" wide by 6" high by the length as required. They shall be made of recycled rubber, rated for 500lb./ft load each. The pads will have galvanized steel "C" channel attached to the top, which can accommodate pipe clamps to secure the piping. This configuration of individual piping pads may be expanded to include two pads supporting a trapeze style support where multiple pipes are racked together. The pads are C-series manufactured by Cooper B-line, Erico, or approved equivalent.

- 2.11 **HANGERS AND SUPPORTS**
- A. Support piping and equipment from the structure to prevent sagging, pocketing, swaying, and vibrations, and arranged to provide for expansion and contraction. Brackets, clamps, and hangers shall be steel, except copper hangers will be used with copper piping. Hangers supporting vibrating equipment shall be provided with spring isolators. Chain, pressed iron or wire hangers are not permitted. Hangers will be of a type acceptable to the Engineer, and shall have a capacity and spacing as required by code.

- 2.12 **SLEEVES AND PLATES**
- A. Provide sleeves and inserts for all mechanical piping. The contractor shall be responsible for the cost of cutting and patching required for piping where sleeves and inserts were not installed or where incorrectly located. Sheetrock joint compound may be used to seal openings in non-rated walls(insulation to be continuous through walls.
- B. Drill holes as required for the installation of hangers required for the mechanical work.
- C. Where sleeves are placed in exterior walls below grade, the space between the pipe or conduit and the sleeves shall be made completely water-tight.
- D. Seal all piping passing through fire-rated construction with approved material to maintain air-tight, fire-rated integrity, with a U.L. listed assembly compatible with the wall or floor assembly being penetrated.

- 2.13 **PIPING TESTING**
- A. All piping systems shall be tested and witnessed by the Owner prior to concealment. Protect equipment and fixtures or equipment, isolating them during the test. DWV system shall be sealed and hold water without leaks for 24 hours. Domestic water and hydronic piping shall be air tested at 150 PSIG; natural gas piping shall be air tested at 30 PSIG. Air tests shall be held for one hour without loss of pressure.

- 2.14 **CLEANING AND STERILIZATION**
- A. After testing, water piping systems shall be filled, operated for a sufficient length of time to completely remove all foreign material, and flushed.
- B. Sterilize the domestic hot and cold water piping in accordance with the local health authority standards. Flush the systems with clear water until the residual chlorine content is equal to that of clear water.
- C. Where there is no water treatment contractor sterilize piping system with chlorine for 24 hours to 50 PPM. Completely flush to less than 1 PPM. Local health authority standards take precedence.

- 2.15 **FLEXIBLE PIPE CONNECTIONS**
- A. Provide flexible pipe connection suitable to connect to adjoining piping as specified for pipe joints. Use sized pipe units. Install flexible pipe connectors on pipes connected to equipment supported by vibration isolation.

- 2.16 **PIPE IDENTIFICATION**
- A. After completion of the piping or insulation, paint stenciled descriptive abbreviations, including directional arrows, on piping at equipment and approximately every 25'.

SECTION 22 07 00 - PLUMBING INSULATION

- 1.01 **QUALITY ASSURANCE**
- A. All insulation shall have a composite rating (insulation, jacket and adhesives) not exceeding flame spread 25 and smoke developed 50.

- 2.01 **PIPE INSULATION FOR PIPING ABOVE GRADE**
- A. Insulation shall be closed-cell, elastomeric pipe insulation having a conductivity of 0.27 at 75 °F mean, with thicknesses as follows:
- | Pipe Sizes                          | <1"    | 1" to 1 1/2" | > 1 1/2" |
|-------------------------------------|--------|--------------|----------|
| Dom. cold piping                    | 1/2"   | 1/2"         | 1"       |
| Roof drain surmps, & horiz. leaders | 1/2"   | 1/2"         | 1"       |
| Dom. hot & recirc. Piping           | 1-1/2" | 1-1/2"       | 1-1/2"   |
- B. Insulation shall be Armacell "Armaflex" or equivalent by Johns-Mansville, Owens-Corning.
- C. Buried piping insulation will be sleeved with PVC or HDPE pipe sleeve or encased in concrete. Sleeve and insulation will be sealed weathertight and installed per manufacturers instructions.
- D. Exterior piping insulation will be painted with a white solvent based alkyl finish (Armaflex AB or equivalent), including all fittings, valves, etc. Jacket and insulation will be sealed weathertight and installed per manufacturers instructions. Where exposed to physical damage, exterior piping insulation will be covered with aluminum jacket, including all fittings, valves, etc.
- E. All interior underground water (domestic and hydronic) piping shall be insulated with 1" Armaflex, except where noted.

- 2.02 **PIPE INSULATION FOR PIPING BELOW GRADE**
- A. Insulation shall be closed-cell, elastomeric pipe insulation having a conductivity of 0.27 at 75F mean, with thicknesses as follows:
- | Pipe Sizes                | <1"  | 1" to 1 1/2" | > 1 1/2" |
|---------------------------|------|--------------|----------|
| Dom. cold piping          | 1/2" | 1/2"         | 1"       |
| Dom. hot & recirc. Piping | 1"   | 1"           | 1"       |

- B. Insulation shall be Armacell "Armaflex" or equivalent by Johns-Mansville, Owens-Corning.
- C. Exterior piping insulation will be painted with a white solvent based alkyl finish (Armaflex AB or equivalent), including all fittings, valves, etc. Jacket and insulation will be sealed weathertight and installed per manufacturers instructions. Where exposed to physical damage, exterior piping insulation will be covered with aluminum jacket, including all fittings, valves, etc. Jacket and insulation will be sealed weathertight and installed per manufacturers instructions.
- D. All interior underground water (domestic and hydronic) piping shall be insulated with 1" Armaflex, except where noted.

- 3.01 **PIPE/ELASTOMERIC**
- A. Insulation shall be solid slip-on installed prior to connection. Butt joints shall be sealed with manufacturer's adhesive. Where slit seams must be installed, seal the seam with manufacturer's adhesive. Fittings shall be insulated with meter-cut pieces of insulation according to manufacturer's instructions, or insulated with similar sheet insulation installed according to manufacturer's instructions.
- B. Provide wood blocks and metal hanger shields at support strap locations on horizontal pipe runs. Insulation will not be interrupted for supports, etc.

SECTION 22 10 00 - PLUMBING

- 1.01 **WATER SERVICE**
- A. Consult with local authorities to provide water service. Provide meter pit, meter yokes, valves, RPZ valves, PRV valves, etc. for complete installation. Connect to a point 5' from building. Coordinate exact point of connection with site contractor before bidding.

- 1.02 **SANITARY SEWER CONNECTION**
- A. Consult with local authorities and connect to sewer main as required. Connect to a point 5' from building. Coordinate exact point of connection with site contractor before bidding.

- 2.01 **DOMESTIC WATER SYSTEM PIPING**
- A. Domestic cold, hot, and recirculating hot water piping may be either copper, or PEX, as noted below:
1. Copper piping:
- a. Above grade, piping shall be Type L, hard-drawn copper tubing with wrought copper fittings. Solder shall be lead-free.
- b. Below grade, piping shall be Type K, soft-drawn copper tubing with fittings only where specifically allowed by the architect. Where required, the fittings will be wrought copper. Solder shall be 95/5 tin/antimony, except underground, where it will be silver solder.
2. PEX Tubing:
- a. Tubing shall be cross-linked polyethylene using the Engel method of cross-linking. The tubing shall be rated for 80PSI at 200F, and shall be manufactured according to ASTM F 876 and ASTM F 877.
- b. Fittings shall be ABR(brass) "Pro-pek" style or equivalent. Manifolds may be copper, brass, or plastic, with balancing controls.
- c. Stub outs to be copper with brass shutoff valves. Stub outs to be properly secured to wall.
- d. Tubing in return air plenums, or other areas designed as air handling plenums, shall be installed to a flame rating of 25/50 according to ASTM E84, whether by spacing, insulation or other approved method.
- e. Tubing shall be as manufactured by Wirsbo or equivalent.

- 2.02 **SOIL, WASTE, AND STORM PIPING**
- A. Soil, waste, and vent piping, and storm piping shall be schedule 40 solid core PVC conforming to ASTM D2665 and ASTM D1785 with solvent joints conforming to ASTM D2855, except as noted below. PVC buried below slab shall be installed in conformance with ASTM D2321:
1. Hubless(No Hub), cast iron soil pipe conforming to CISPI 301 with stainless steel no-hub couplings conforming to CISPI 310 shall be used in return air plenums and other areas designed as air handling plenums, or where specifically required by local code. All cast iron soil pipe and fittings shall be marked with the collective trademark of the Cast Iron Soil Pipe Institute and be listed by the NSF International.
- B. Soil, waste, and storm piping below grade 5' beyond the building may be PVC SDR 35, installed in conformance with ASTM 3034 and utilizing push-on joints.
- C. Storm water piping shall be same as soil and waste piping when concealed and galvanized schedule 40 steel pipe when exposed to physical damage. Fittings shall be cast iron, drainage type.

- 2.03 **PLUMBING FIXTURES AND TRIM**
- A. Provide plumbing fixtures as specified on the plans. Provide carriers, trim, bolts, caps, etc according to the manufacturer's instructions and as required for a complete installation. All fittings and appurtenances (p-traps, connections, etc) shall be brass; chrome plated brass where visible.
- B. Provide carriers for wall hung or mounted fixtures such as water closets, lavatories, urinals, sinks, etc. The carriers shall be designed to fit in the wall structure available, and shall transmit the load to the floor. Fixtures will not be supported by the wall structure unless specifically indicated.

- 2.04 **GAS PIPING**
- A. Above grade in accessible locations, gas piping shall be schedule 40, black iron pipe with threaded fittings. Fittings shall be made of malleable iron. Gas piping run in return plenums, where allowed by local code, shall have welded joints.
- B. Regulators shall be Maxtrol, or equivalent, of size and capacity as required.

- 2.05 **ELECTRIC WATER HEATER**
- A. Water heaters shall be as specified on the plans. Heaters shall be U.L. listed. The tank shall be heavy-gauge, welded steel, glass-lined, insulated to conform to ASHRAE 90B-1992. The heater shall be rated for 150 PSI and shall have a five-year warranty. The heater shall use two immersion heating elements. The controls shall be completely factory-assembled and shall include immersion thermostats and high-temperature cut off. The heater shall include two (2) magnesium anodes and a pressure and temperature relief valve. The heater will be furnished with integral heat traps. Where required by local code, provide ASME certification.
- B. Water heater shall be provided with R 14 insulation. Where factory insulation does not meet insulation requirements, provide aftermarket insulated jacket as required to meet requirements.
- C. The water heaters shall be manufactured by State, Ruud, A.O. Smith, Jackson, or American Appliance.

- 2.06 **DOMESTIC RECIRCULATING PUMP**
- A. Pump shall be 2800 rpm, in-line, centrifugal oil-lubricated, sleeve-bearing pump with flanged piping connections, bronze body, plastic impeller, and having mechanical seals. Motors shall be non-overloading, open drip-proof type.
- B. The pump shall be furnished with an automatic time kit.
- C. Manufacturer shall be Bell and Gossett, Paco, Taco, or approved equivalent.

- 3.01 **DOMESTIC WATER SYSTEM**
- A. Provide drip corks so that the entire system may be drained. Provide manual air vents at high points in the system where air may be trapped. Provide stops for all fixtures and appliances. Provide a full size ball valve on each branch serving a hose bib.
- B. Provide swing or swivel joints on connections as required to prevent noise or vibration of the piping. Provide fixture stops at all fixtures, hose bibbs, wall hydrants, and Owens-Corning furnished fixtures. Run all piping on warm side of building insulation. Pipe insulation is not considered freeze protection. Provide water hammer arrestors where required. Locate to be accessible or provide access panel.

- 3.02 **SOIL, WASTE, AND STORM WATER PIPING**
- A. Lay piping true to line and grade so that sewer will have smooth and uniform invert throughout its length. Verify elevations of existing sewer before starting work.
- B. Install a clean-out at the base of each soil stack, at the base of each exterior rain-water conductor, at each change in direction, at intervals not over 50 feet interior of building, and every 100 feet exterior to building and elsewhere as shown on the drawings or required by code. Make clean-outs same size as pipe service, except they need be no larger than 4". Set tops and covers flush with floors and walls. Wall covers shall be round polished stainless steel with centered stainless steel securing screw (Joam 58710). Floor cleanouts shall be flush, cast iron, ABS plug with Nikkaloy cover(Joam 56000). Provide floor clamps at each floor for uniform support of stacks.
- C. The entire drain waste and vent, and storm sewer systems shall be watertight and odorproof, including sealing of floor drains and


- sinks, closet rings, etc.
- 3.03 **WATER HEATER INSTALLATION**
- A. Install water heaters per manufacturer's instructions. Provide 24 gauge, galvanized steel drain pan, piped with minimum 3/4" drain, piped to an approved receptor with indirect waste connection per code.
- B. Route the P/T relief valve full sized to approved receptor and discharge per code. Provide expansion device, tank or valve, as required by code, and allowed by the local jurisdiction.
- C. Flue and combustion air ducts shall be provided by the mechanical contractor, unless otherwise noted. Where sealed combustion water heaters are used, the Plumbing Contractor shall install PVC flue and combustion air piping. This piping will be of the size and type recommended by the manufacturer, and use factory recommended discharge/intake fittings as shown on the plans.
- 3.04 **PLUMBING FIXTURES AND TRIM**
- A. Furnish and install a vacuum breaker at each hot and cold water service outlet to which a hose can be attached, including janitor's faucets.
- B. Provide chrome-plated rigid or flexible supplies to fixtures with stops, reducers, and escutcheons. Insulate stops and supplies at handicapped sinks with Truebro lav guard or equivalent. Bag type covers are not allowed.
- C. Provide chrome plated brass P-traps with slip fittings for all exposed drains. Insulate P-traps at handicapped sinks with Truebro lav guard or equivalent. Bag type covers are not allowed.
- D. Flush valve handles, and flush tank handles, on handicapped water closets shall be located on the wide side of the stall for convenient access and as required by code.
- E. Provide a flexible elastomeric sheet for flashing around all shower drains, roof drains, floor drains, floor sinks, etc except for slabs on grade. The membrane shall be a minimum 0.40 inch thick, made of chlorinated polyethylene, installed per manufacturer's instructions. The flashing membrane for roof drains, floor drains, etc shall be a minimum of 2x2'. The flashing membrane for shower pans, service sink pans, etc shall have "pigs ear" folds in the corners, extending the membrane up at least 3" above the drain. The membranes shall be manufactured by Chlorlloy or equivalent.
- F. Mount fixtures the following heights above finished floor:
1. Water closet : 14"-15" to top of bowl rim;
2. Lavatory : 31" to top of basin rim.
- Handicapped : 32" to top of basin rim.
3. Floor drains : In finished areas, 1/4" - 1/2" below finished floor. In mechanical rooms and other unfinished areas, install at least 1" below floor, except where it would be a sturdy hazard.
- G. Rough-in fixture piping connections in accordance with the following table of minimum sizes or as required for particular fixtures.

	HW	CW	Waste	Vent
Lavatories	1/2"	1/2"	1-1/2"	1-1/4"
Water Closet (tank)	--	1/2"	3"	2"
Floor drains	--	--	2"	1-1/2"
Hose bibs	--	3/4"	--	--
Wash Mach Unit	1/2"	1/2"	2"	1-1/2"
Owner furnished equipment	SEE SCHEDULE & PLANS			

- 3.05 **GAS PIPING**
- A. Gas distribution system is based on both 14" W.C. and a 6" W.C. natural gas pressure except where noted on plans. Provide all gas-fired equipment with gas pressure regulators or special orifices as required to operate at 5000 ft. elevation. Provide a gas cock and drip leg at each appliance.
- B. Gas piping on roof shall be secured to uv resistant Polyethylene foam block; Erico "Pipe Pier". Provide rubberized sheet under pipe support.
- C. Piping exposed outside shall be painted with an exterior type latex paint which matches the adjacent roof or wall.
- D. Appliance connection piping to be per plans or same as appliance size, whichever is larger. Transition downstream of all shutoffs and regulators as close to appliance as possible when plans call for larger than appliance.

- 3.06 **KITCHEN**
- A. Provide final connections to all kitchen equipment in accordance with manufacturer's instructions. Provide stops or shut-off valves for hot and cold water connection; plug corks or quick-connect couplings for gas appliances. Indirect wastes shall be DWV copper, except at soda machines where plastic pipe shall be used.

REVIEWED  
FOR  
CODE  
COMPLIANCE  
04/01/2025



**NOTICE/DUTY OF COOPERATION**

Release of these plans contemplates further cooperation among the owner, the contractor and the architect. Design and construction are complex. Although the architect and his consultants have performed their services with due care and diligence, they cannot guarantee perfection. Communication is perfected and every contingency cannot be anticipated. Any ambiguity or discrepancy discovered by the use of these plans shall be reported immediately to the architect. Failure to notify the architect compounds misunderstanding and increases construction costs. A failure to cooperate by a simple notice to the architect shall release the architect from responsibility for the consequences. Charges made from the plans without consent of the architect are unauthorized and shall release the architect of responsibility for all consequences arising out of such changes.

All design, documents and data prepared by Eric Smith Associates, P.C. as instruments of service shall remain property of Eric Smith Associates, P.C. and shall not be copied, changed or disclosed in any form whatsoever without first obtaining the express written consent of Eric Smith Associates, P.C.

Eric Smith Associates, P.C.

REVISIONS
-----------




All design, documents and data prepared by Eric Smith Associates, P.C. as instruments of service shall remain property of Eric Smith Associates, P.C. and shall not be copied, changed or disclosed in any form whatsoever without first obtaining the express written consent of Eric Smith Associates, P.C.

[illegible]

1. MOUNT BATHROOM EXHAUST FAN IN CEILING. ROUTE EXHAUST DUCT IN SOFFIT/CEILING SPACE TO EXTERIOR WALL. TERMINATE IN WALL CAP WITH BACKDRAFT DAMPER. MAINTAIN MINIMUM 3'-0" FROM BUILDING OPENINGS OR MECHANICAL AIR INTAKES. EXHAUST FAN CONTROLLED BY SWITCH ON WALL. COORDINATE WIRING AND LOCATION WITH E.C.
2. ROUTE KITCHEN EXHAUST FROM KITCHEN HOOD TO EXTERIOR WALL AND TERMINATE IN WALL CAP WITH BACKDRAFT DAMPER. TRANSITION AT HOOD AS REQUIRED.
3. AIR HANDLER THERMOSTAT, COORDINATE FINAL LOCATION WITH OWNER/G.C.
4. 4" DRYER VENT FROM DRYER BOX (IN-O-VATE TECHNOLOGIES OR EQUIV.) ROUTE BEHIND DRYER IN WALL UP THRU TOP PLATE AND THRU CEILING SPACE TO EXTERIOR WALL. INSTALL BACKDRAFT DAMPER AT TERMINATION. ALL HORIZONTAL TURNS TO BE LONG TURN 'ELLS (IN-O-VATE TECHNOLOGIES OR EQUIV.) DRYER TO BE LONG VENT TYPE. INSTALL VENT PER MANUFACTURER'S REQUIREMENTS. VENT NOT TO EXCEED 40' IN TOTAL LENGTH WITH (2) 90° ELBOWS, PROVIDE PERMANENT LABEL 'DRYER MUST BE APPROVED FOR 40' WITH (2) ELBOWS BY MANUFACTURER.' RE: DETAIL ON P51. FOR DRYER BOX INSTALLATION. SHOWN OFFSET FOR CLARITY. DRYER DUCT CONSTRUCTION TO MEET IBC 603.4 WHEN PENETRATING RATED ASSEMBLIES.

- ESA**
- ERIC SMITH ASSOCIATES, P.C.**  
1919 SEVENTH STREET  
BOULDER, COLORADO, 80302  
(303) 442-5458, (303) 442-4745 FAX

<b>Project Phase</b>
PERMIT
<b>Sheet Title</b>
LOWER LEVEL HVAC PLAN
<b>Sheet Number</b>
M1.1




**REVIEWED  
FOR  
CODE  
COMPLIANCE**  
04/01/2025













**REVIEWED  
FOR  
CODE  
COMPLIANCE**  
04/01/2025

3. ELECTRIC SNOWMELT BOILER, INSTALL PER MANUFACTURER'S INSTRUCTIONS.



ASTRID BUILDING 7  
STEAMBOAT SPRINGS, COLORADO









SNOWMELT ZONE SCHEDULE								
ZONE	AREA	APPROX. AREA (FT <sup>2</sup> )	TOTAL PANEL OUTPUT (BTU/H)	PANEL MATERIAL	TUBE SPACING (IN)	TUBING REQUIRED (FT)	EST. # OF LOOPS	GPM
SM-1	GARAGE 1 DRIVEWAY	390	54,390	CONCRETE	9	520	2	4.1
SM-2	GARAGE 2 DRIVEWAY	430	67,680	CONCRETE	9	640	3	5.0
SM-3	GARAGE 3 DRIVEWAY	500	70,500	CONCRETE	9	667	3	5.2
SM-4	GARAGE 4 DRIVEWAY	460	64,260	CONCRETE	9	613	3	4.8
SM-5	MAIN ENTRY	410	57,810	CONCRETE	9	547	2	4.3
	TOTAL	2,240	315,840			2287		23.4
DESIGN PARAMETERS:								
	TUBE SIZE	3/4	in			MAXIMUM LOOP LENGTH:		333 FT
	DELTA T	30	oF			MANIFOLD RUN FACTOR:		10%
	PANEL SUPPLY WATER TEMP	140	oF			FACTORED LOOP LENGTH:		300 FT
	SURFACE DESIGN TEMP	37	oF					
	% PROP. GLYCOL (BY VOL.)	50%						

UNIT TYPE	UNIT AREA (SF)	UNIT BEDROOM QTY	CEILING HEIGHT (FT)	VENTILATION RATE (CFM) IMC 403.3.2.1	ERV-1 IMC 15 CFM/P	ERV-1 QTY PER UNIT	ERV-1 RUN TIME PER FAN (MIN)
UNIT 1	2651	4	10.00	67	75	1	60
UNIT 2	2755	4	10.00	66	75	1	60
UNIT 3	2632	4	10.00	64	75	1	60
UNIT 4	3315	6	10.00	86	105	1	63

NOTES:

1. UNITS 1 THRU 3 BASED ON ERV-1 AIRFLOW RATE OF 75 CFM
1. UNIT 4 BASED ON ERV-2 AIRFLOW RATE OF 100 CFM
2. IMC 403.3.2.1 CALCULATION BASED ON EQUATION 4-9 BELOW  

$$\text{VENTILATION RATE} = 0.01 \times \text{AREA} + 7.5(\text{BEDROOMS} + 1)$$

[illegible]

HYDRONIC SCHEDULE										
KEY	UNIT TYPE	DESCRIPTION	HEAT G	COOL G	FLOW	PRES.	WEIGHT	PWR	VOLT	MANUFACTURER/CAT. #
BLR-1	HYDRONIC BOILER	ELECTRIC BOILER, STEEL CONSTRUCTION, FLOW SWITCH, FUSED CONTROL TRANSFORMER, FUSED DISCONNECT,	120 kW	-	41 GPM	3.6" HD	700 LBS	231.5 A	208/3	ELECTRO INDUSTRIES ES-NB-120-208
P-1	CIRCULATION PUMP	CAST IRON HOUSING, COMPOSITE IMPELLER, CANNED ROTOR, 50% P.G.			42.4 GPM	3.6" HD	17.9 LBS	115 W	120/1	GRUNDFOS UPS32-40 (BOILER PUMP)
P-2	CIRCULATION PUMP	CAST IRON HOUSING, STAINLESS IMPELLER, CANNED ROTOR, 50% P.G.			25 GPM	12" HD	17.6 LBS	187 W	120/1	GRUNDFOS MAGNA3 32-120 GF (SNOWMELT LOOP)
BF	BOILER FEEDER	17 GALLON TANK, LEAK DETECTION, 50% PROPYLENE GLYCOL, MAX 48 PSI			1 GPM	12" HD	8.2 LBS	50 W	115/1	AXIOM DMF300
ET	EXPANSION TANK	8.6 GALLON TANK VOLUME, 3.2 ACCEPTANCE VOLUME, VERTICAL TANK					38 LBS			AMTROL AX-15V-DD
NOTES:	* M.C. IS RESPONSIBLE FOR ALL ANCILLARY EQUIPMENT AND DUCTWORK NEEDED TO CONNECT EQUIPMENT. IT IS THE CONTRACTORS RESPONSIBILITY TO COORDINATE ELECTRICAL CHANGES DUE TO EQUIPMENT SUBSTITUTIONS WITH EC.									

GRILLE REGISTER DIFFUSER SCHEDULE				
KEY	DESCRIPTION	CEILING	ACCESSORIES	MANUFACTURER/CAT #
S1	DOUBLE DEFLECTION SUPPLY REGISTER, FRONT BLADES PARALLEL TO SHORT DIMENSION, WHITE	GYP	OB DAMPER	HART & COOLEY A716
R1	RETURN GRILLE, 20 DEGREE FIXED BLADE, WHITE PARALLEL TO LONG DIMENSION	GYP		HART & COOLEY 650
R2	FILTERED RETURN GRILLE, 20 DEGREE FIXED BLADE, WHITE PARALLEL TO LONG DIMENSION	GYP		HART & COOLEY 659
R3	RETURN GRILLE, 30 DEGREE FIXED BLADE, FRONT BLADES PARALLEL TO LONG DIMENSION, WHITE	GYP		TITUS 25RL
L	WALL LOUVER, HEAVY GAUGE ALUMINUM, 37.5 DEG DRAINABLE BLADE		1/2" BIRDSCREEN	GREENHECK ESD-435
NOTES: COORDINATE DIFFUSER LOCATIONS WITH LIGHTS AND OTHER CEILING ELEMENTS				



**NOTICE: DUTY OF COOPERATION**

Release of these plans contemplates further cooperation among the owner, his contractor and the architect. Design and construction are complex. Although the architect and his consultants have performed their services with due care and diligence, they cannot guarantee perfection of construction. Construction is an imperfect process and contingencies cannot be anticipated. Any ambiguity or discrepancy discovered by the owner of these plans shall be reported immediately to the architect. Failure to notify the architect compounds misunderstanding and increases construction costs. A failure to cooperate by a simple notice to the architect may result in a claim for damages and other legal consequences. Changes made from the plans without consent of the architect are unauthorized and shall relieve the architect of responsibility for all consequences arising out of such changes.

All design, documents and data prepared by Eric Smith Associates, P.C. as instruments of service shall remain property of Eric Smith Associates, P.C. and shall not be copied, changed or disclosed in any form whatsoever without first obtaining the express written consent of Eric Smith Associates, P.C.

[illegible]

ASTRID BUILDING 7  
STEAMBOAT SPRINGS, COLORADO



<b>Job Number:</b>	23035-7
<b>Date:</b>	03/21/24
<b>Drawn By:</b>	AF
<b>Checked By:</b>	MV

<b>Project Phase</b>
PERMIT
<b>Sheet Title</b>
MECHANICAL SCHEDULES
<b>Sheet Number</b>
M6.1

**REVIEWED  
FOR  
CODE  
COMPLIANCE**  
04/01/2025



# LEGEND

	DUCT (INSIDE DIM. SIDE SHOWN INSIDE DIM. SIDE NOT SHOWN)
	SUPPLY DUCT (SECTION)
	RETURN DUCT (SECTION)
	EXHAUST DUCT (SECTION)
	ROUND DUCT, RIGID
	FLEXIBLE DUCT
	FLEXIBLE CONNECTOR
	TURNING VANES
	SUPPLY DIFFUSER (ARROWS INDICATE DISTRIBUTION)
	RETURN REGISTER / GRILLE
	MECHANICAL POINT OF CONNECTION
	FIRE DAMPER
	SMOKE AND FIRE DAMPER
	THERMOSTAT
	MANUAL BALANCING DAMPER
	MOTORIZED BALANCING DAMPER
	HOT WATER SUPPLY
	HOT WATER RETURN
	CHILLED WATER SUPPLY
	CHILLED WATER RETURN
	CONDENSATE
	STEAM
	GRILLE / REGISTER / DIFFUSER
	MECHANICAL EQUIPMENT
	DETAIL NOTE
	KITCHEN / MEDICAL EQUIPMENT
SA	SUPPLY AIR
OA	OUTSIDE AIR
MA	MIXED AIR
RA	RETURN AIR
EA	EXHAUST AIR
AD	ACCESS DOOR
OSD	OPPOSED BLADE DAMPER
RUS	ROUTE IN JOIST SPACE
(E)	EXISTING TO REMAIN
(ER)	EXISTING TO BE REPLACED
(ED)	EXISTING TO BE DEMOLISHED
	DUCT DETECTOR
	REMOTE INDICATING LIGHT

**REVIEWED  
FOR  
CODE  
COMPLIANCE**  
04/01/2025



**NOTICE: DUTY OF COOPERATION**

Release of these plans contemplates further cooperation among the owner, his contractor and architect. Design and construction are complex. Although the architect and his consultants have performed their services with due care and diligence they cannot guarantee perfection. Communication is imperfect and every contingency cannot be anticipated. Any serious or disclosed discrepancy among these plans shall be reported immediately to the architect. Failure to notify the architect compounds misunderstanding and increases construction cost failure to cooperate by a simple notice to the architect shall relieve the architect from responsibility for such changes. Changes made without the written consent of the architect are unauthorized and shall relieve the architect of responsibility for all consequences arising out of such changes.


All design, documents and data prepared by Eric Smith Associates, P.C. as instruments of service shall remain property of Eric Smith Associates, P.C. and shall not be copied, changed or disclosed in any form whatsoever without first obtaining the express written consent of Eric Smith Associates, P.C.

Eric Smith Associates, P.C.

## REVISIONS

[illegible]

ASTRID BUILDING 7  
STEAMBOAT SPRINGS, COLORADO




<b>Job Number:</b>	23035
<b>Date:</b>	03/21/
<b>Drawn By:</b>	AF
<b>Checked By:</b>	MV

Project Phase	
Phase 1: Initial Assessment	Phase 2: Data Collection
Phase 3: Analysis	Phase 4: Reporting

<b>Sheet Title</b>
MECHANICAL DETAILS


Sheet Number
--------------

## M6.2




## EXHAUST & DRYER VENT DETAIL

## 4 | LOW PRESSURE DUCT CONNECTIONS



## FIRE/SMOKE DAMPER INSTALLATION DIAGRAM



## HYDRONIC SNOWMELT PIPING DIAGRAM



DIVISION 23 - HEATING, VENTILATING, AND AIR-CONDITIONING

SECTION 23 05 00 - COMMON WORK RESULTS FOR HVAC

1.01 WORK INCLUDED

A. The work including by this division of the specifications includes furnishing all labor, materials, equipment, and services, including minor items omitted but necessary to construct and install the complete systems described by the Contract Documents and specified below. "Contractors" refers to the Mechanical Contractor. The general conditions of the specifications apply and are included in this part of this section.

- 1. Heating, ventilating and air conditioning systems
- 2. Snowmelt
- 3. Temperature control system

1.02 CODES AND REGULATIONS

A. Comply with state and local codes, and utility company regulations. Final interpretations will be made by the local inspection authority. The Contractor to verify the governance of the following codes, including any local amendments and supplementary codes such as the Code of the National Fire Protection Association:

- 1. Building Code: 2021 International Building Code
- 2. Plumbing Code: 2021 International Plumbing Code
- 3. Mechanical Code: 2021 International Mechanical Code
- 4. Fire Code: 2021 International Fire Code
- 5. Gas Code: 2021 International Fuel Gas Code
- 6. Energy Code: 2021 International Energy Conservation Code
- 7. Electrical Code: 2023 National Electrical Code

1.03 EQUIPMENT AND MATERIALS STANDARDS

A. Equipment and materials shall be new, UL-listed for the use intended, and free from damage or defect. They shall comply with the latest industry standards.

1.04 CONTRACT DRAWINGS

A. Illustrate the general design and extent of performance required. All dimensions and locations shall be taken from the Architectural drawings. Consult with Architectural plans and locate all ceiling equipment where indicated on reflected ceiling plans

1.05 SHOP DRAWINGS

A. Submit products data and/or shop drawings as required by the Architect for the following:

- 1. Insulation
- 2. Air handling equipment
- 3. Grilles, registers, diffusers, louvers
- 4. Fire dampers
- 5. Temperature controls, systems, and components
- 6. Valves
- 7. Boilers
- 8. Pumps

B. Quality of specific equipment is established by manufacturer's catalog number. Alterations caused by any Substitution shall be at no additional expense to the Owner.

C. Manufacturers not listed may submit for acceptance as an "approved equivalent." Requests for an "equivalent" means "approved equivalent". Four copies of such submittal must be received by the Engineer seven (7) working days prior to bid date.

1.06 WARRANTY

A. The Contractor shall be responsible for the successful operation of mechanical systems, equipment, and materials installed under this contract for a period of one year from the date of final acceptance. Defective equipment or materials shall be repaired or replaced at no expense to the Owner. Provide four complete service and maintenance calls spaced at equal intervals during the warranty period.

1.07 PRODUCT HANDLING AND CLEAN UP

A. Equipment shall be left clean and undamaged, to the satisfaction of the Owner. The General Conditions take precedence.

B. HVAC equipment shall not be used during construction as a means to heat or cool the space, unless specific approval is given by the owner. If such equipment is used, it must be completely cleaned and repaired as necessary. Cleaning involves replacing all filters; cleaning all coils and heat exchangers; inspecting fans, plenums, and ductwork and cleaning as directed by the owner.

1.08 CUTTING AND REPAIRING

A. The contractor shall be responsible for all cutting, drilling, welding, and repair required for his portion of the work. Coordinate with the Architect. The General Conditions take precedence.

1.09 OPERATING AND MAINTENANCE DATA

A. Provide the Owner with operating and maintenance instructions (four copies) required for operation of all mechanical systems. Bind the written instructions in a notebook. The General Conditions take precedence. The manuals shall include the following items:

- 1. Operating manual and spare parts list for each piece of equipment.
- 2. Preventive maintenance schedule for lubricating and checking each piece of equipment.
- 3. Instructions on who to call for service during the warranty period.

1.10 PERMITS

A. The contractor shall pay for all fees, taxes, secure permits, licenses, and inspections required for the project.

1.11 TEMPORARY SERVICES

A. Provide temporary water service for construction, as required by the General Contractor.

1.12 COORDINATION

A. Coordinate utility design and equipment locations with the Architectural Plans and work of other trades. Locate on horizontal and vertical lines to avoid interference and to provide functional use of all equipment. Verify electrical power characteristics before ordering equipment.

B. Electrical work performed by this contractor will conform to the standards of Division 26-28. Mechanical equipment motors and controls shall be furnished, set in place, and wired according with the following schedule unless otherwise noted or specified. MC – Division 21-23 EC – Division 26-28

Item	By	By	Writing
Combination starters	MC	EC	EC MC
Equipment motors	MC	MC	EC
Motor starters & O.L. relays	MC	EC	EC MC
Disconnect switches	EC	EC	EC MC
Thermal overload heaters (1)	EC	EC	EC
Variable Speed Drives	MC	EC	EC MC
Control relays/transformers	MC	MC	EC MC
Temperature control panels	MC	MC	EC MC
Tank Controls/controlling	MC	MC	EC MC
Actuator and solenoid wiring	MC	MC	EC MC
Pushbuttons & pilot lights	MC	MC	EC MC
Room thermostats	MC	MC	EC MC
Thermostats: line voltage	EC	EC	EC

C. The general guideline for the division between control (by MC) wiring and power wiring (by EC) is that power wiring carries the current which energizes a motor, control wiring does not. Control wiring may be 120V, which would be the responsibility of the MC. Control motors are wired by the MC.

D. Examine the site and become aware of existing conditions, utilities, and other issues affecting the satisfactory completion of the project.

1.13 DELIVERY, STORAGE, HANDLING

A. Provide necessary hauling and hoisting equipment. Protect the materials of this Division before, during, and after installation.

1.14 AS-BUILT DRAWINGS

A. Keep a current set of "as-built" drawings on site. Upon completion of the work, furnish engineer with a reproducible prints showing the "as-built" installation.

1.15 PROJECT/SITE CONDITIONS

A. Visit the site to become familiar with location and the various conditions affecting the work, including existing utilities.

1.16 PLAN VERIFICATION

A. After completion of the bidding and selection process, prior to awarding the contract, the contractor must review and verify the contract, including their own drawings, and those of other trades. At this time discrepancies, conflicts, omissions, etc. in the contract documents must be documented. Alterations to the contract will be made at that time to include such items, as well other modifications which might be made by the Owner. After award of the contract, change orders caused by discrepancies, conflicts, omissions in the contract documents will not be allowed.

2.01 EXPANSION JOINTS, GUIDES, AND ANCHORS

A. Provide expansion joints or loops, guides, and anchors in piping to allow for expansion and contractions. Expansion joints shall be bellows type.

2.02 VALVES

- A. Gate valves 2" and smaller shall be cast bronze, rising stem, solid disc, 200 PSI WOG
- B. Ball valves 2" and smaller shall be cast bronze, full port, stainless steel ball, leftn ends, 400 PSI WOG.
- C. Butterfly valves 2" and smaller shall be cast bronze, stainless steel disc, surrounding fluorocastomer seal, 350 PSI WOG.
- D. Check valves shall be horizontal, swing-cast bronze, bronze disc, 200 PSI WOG.
- E. Valves shall be domestically manufactured by Milwaukee, Powell, Nibco, or equivalent.

2.03 RELIEF VALVES

A. Relief valves shall be all-bronze A.S.M.E. rated valves with external test levers, sized in accordance with the instructions of the appropriate manufacturer. Pipe discharge outside or to floor drain where possible and per code. Valves shall be manufactured by Watts or equivalent.

2.04 FLEXIBLE CONNECTORS

A. Connectors in piping shall be made with molded teat or neoprene and nylon bellows, metal reinforcing rings, flanged ends and control rods, suitable for 40F to 200F temperature range and 125 lbs. pressure. Alternatives shall be stainless steel inner hose with braided exterior sleeve for steel pipe or bronze inner hose with braided exterior sleeve for copper piping. Meta-Flex Company, or equivalent.

2.05 SPECIALTIES

- A. PT Pigtails: 1/4" diameter, brass with Nordel core, Sisco or equivalent.
- B. Pressure Gauges: 4 1/2" dial type, aluminum housing. Ashcroft 1010 or equivalent.

C. Thermometers: 7" red reading mercury type. Palmer Instruments or equivalent.

2.06 ELECTRICAL

A. Lugs: Lugs for wiring connections shall be rated for copper and aluminum, nad shall have a minimum rating of 75C.

B. Electric motors shall be rated for the appropriate application: wet location (TEFC); submersible; explosion proof, VFD's, etc.

2.07 ACCESS PANELS

A. The Mechanical Contractor shall furnish and General Contractor shall install access panels where required for access to equipment. The Mechanical Contractor shall include the cost of installation in his bid. Access panels shall be adequately sized, of a type approved by the Architect and shall be fire or smoke-rated as required.

3.01 START-UP PROCEDURES

A. Follow manufacturer's recommended procedures in starting up the equipment; damage caused during start-up shall be replaced at no expense to the owner.

3.02 HANGERS AND SUPPORTS

A. Support piping and equipment from the structure to prevent sagging, pocketing, swaying, and vibrations, and arranged to provide for expansion and contraction. Brackets, clamps, and hangers shall be tested, except copper hangers will be used with copper piping. Hangers supporting vibrating equipment shall be provided with spring isolators. Chain, perforated iron or wire hangers are not permitted. Hangers will be of a type acceptable to the Engineer, and shall have a capacity and spacing as required by code.

3.03 EXCAVATION AND BACKFILLING

A. Provide excavating and backfilling for Mechanical Work. Backfill in 12" layers, mechanically tamped to 95% proctor standards. Protect according to OSHA standards. The General Conditions take precedence. Verify the location of underground utilities before excavation; the contractor is responsible for any damage to underground utilities. Restore existing paving, curbs, sod, bushes, etc. to match surroundings.

3.04 PIPING INSTALLATION

- A. Install piping plumb and straight, parallel with walls and partitions. Conceal piping within structure whenever practical. Provide drain valves at all low points, vents at all high points, to allow complete drainage.
- B. Material and methods per ASME, ASTM, ASA, AWS, and National Plumbing Code Handbook
- C. Provide unions or flanges in piping connections to each valve, device, or item of equipment. Install each union or flange to permit the removal of parts and equipment for inspection or cleaning, without disconnecting any piping, except unions or flanges.
- D. Piping on the roof will be supported above the roof or roof pads. The pads shall be approximately 6" Wide by 6" high by the length as required. They shall be made of recycled rubber, rated for 500lbs/lb loading each. The pads will have galvanized steel "C" channel attached to the top, which can accommodate pipe clamps to secure the piping. This configuration of individual piping pads may be expanded to include two pads supporting a trapeze style support where multiple pipes are racked together. The pads are C-series manufactured by Cooper B-line, Erico, or approved equivalent.

3.05 PIPING TESTING

A. All piping systems shall be tested and witnessed by the Owner prior to concealment. Protect equipment and fixtures or equipment, isolating them during the test. DWV system, including vents and vent stacks shall be sealed and hold water without leaks for 24 hours. Pressure piping shall be tested at the maximum pressure rating of the lesser of piping or fittings. Copper domestic water and hydronic piping may be air tested or hydrostatically tested; PEX or CPVC water piping shall be hydrostatically tested; natural gas piping shall be air tested.

3.06 CLEANING AND STERILIZATION

- A. After testing, water piping systems shall be filled, operated for a sufficient length of time to completely remove all foreign material, and flushed.
- B. Sterilize the domestic hot and cold water piping in accordance with the local health authority standards. Flush the systems with clear water until the residual chlorine content is equal to that of clear water.
- C. Where there is no water treatment contractor sterilize piping system with chlorine for 24 hours to 50 PPM. Completely flush to less than 1 PPM. Local health authority standards take precedence.

3.07 FLEXIBLE PIPE CONNECTIONS

A. Provide flexible pipe connection suitable to connect to adjoining piping as specified for pipe joints. Use sized pipe units. Install flexible pipe connectors on pipes connected to equipment supported by vibration isolation.

3.08 PIPE IDENTIFICATION

A. After completion of the piping or insulation, paint stenciled descriptive abbreviations, including directional arrows, on piping at equipment and approximately every 25'.

3.09 SLEEVES AND PLATES

- A. Provide sleeves and inserts for all mechanical piping. The contractor shall be responsible for the cost of cutting and patching required for piping where sleeves and inserts were not installed or where incorrectly located. Sheetrock joint compound may be used to seal openings in non-rated walls(inspection to be continuous through walls.
- B. Drill holes as required for the installation of hangers required for the mechanical work.
- C. Where sleeves are placed in exterior walls below grade, the space between the pipe or conduit and the sleeves shall be made completely water-tight.
- D. Seal all piping passing through fire-rated construction with approved material to maintain air-tight, fire-rated integrity, with a U.L. listed assembly compatible with the wall or floor assembly being penetrated.

3.10 LOW EMITTING MATERIALS

- A. All sealants & adhesives required for the installation of mechanical & plumbing system within the building envelope shall meet the requirements for low emitting materials as set for in the South Coast Air Quality Management District (SCAQMD) Rule #1168 (or LEED new construction requirements), which includes but is not limited to:
  - 1. Metal to Metal adhesive: VOC limit of 30g/L.
  - 2. Fiberglass adhesive: VOC limit of 80g/L.
  - 3. Multipurpose construction adhesive: VOC limit of 70 g/L.

SECTION 23 05 93-TESTING, ADJUSTING, AND BALANCING

2.01 GENERAL

A. Balancing shall be done by an independent firm specializing solely in the discipline of balancing air and water systems, and a member of NEBB. Firms desiring to furnish services for this project shall submit for written approval during bidding. All air and hydronic systems shall be balanced using applicable proportionate procedure.

2.01 TESTING CONDITIONS

- A. (Air) Before adjustments are made, check the system for such items as dirty filters, duct and damper leakage, vibrations, etc. All diffusers, duct sections, etc. shall be adjusted to deliver design quantities within 5%. Air quantities shall be tested simulating filters being 50% loaded. Adjust/replace sleeves and bells as required to achieve design air quantities. Replace thermal motor overloads as required.
- B. (Hydronic) Before adjustments are made, check the system to make water treatment has been completed and glycol added. Also check for leaks, vibrations, etc. All circuit streets shall be adjusted to deliver design fluid within 5%. Verify that there is no pump cavitation, and that boilers and coolers are cycling at appropriate temperatures.

2.02 REPORT

A. After all adjustments are made, a detail written report shall be prepared and submitted for approval. Final acceptance of the project will not be made until a satisfactory report is received and field verified. The report shall detail the test equipment and balancing procedures being used; the general status of the systems being tested including equipment details; provide data sheets indicating the required and actual CFM of all outlets and inlets.

SECTION 23 07 00 - INSULATION

1.01 QUALITY ASSURANCE

A. All insulation shall have a composite rating (insulation, jacket and adhesives) not exceeding flame spread 25 and smoke developed 50.

2.01 PIPE INSULATION FOR PIPING ABOVE GRADE

A. Insulation shall be closed-cell, elastomeric pipe insulation having a conductivity of 0.27 at 75 °F mean, with thicknesses as follows:

Pipe Sizes	1/2" - 1-1/2"	>1-1/2"
Refrigeration (Suction Lines)	1"	1"

2.02 INSULATION FOR PIPING BELOW GRADE

A. Insulation shall be closed-cell, elastomeric pipe insulation having a conductivity of 0.27 at 75 °F mean, with thicknesses as follows:

Pipe Sizes	1/2" - 1-1/2"	>1-1/2"
Refrigeration (Suction Lines)	1"	1"

- B. Insulation shall be Armaflex "Armaflex" or equivalent by Johns-Manville, Owens-Corning.
- C. Exterior piping insulation will be painted with a white solvent based alkyl finish(Armaflex AB or equivalent), including all fittings, valves, etc. Jacket and insulation will be sealed weathertight and installed per manufacturers instructions. Where exposed to physical damage, exterior piping insulation will be covered with aluminum jacket, including all fittings, valves, etc. Jacket and insulation will be sealed weathertight and installed per manufacturers instructions.

D. All interior underground water(domestic and hydronic) piping shall be insulated with 1" Armaflex, except where noted.

2.02 PIPE INSULATION FOR PIPING BELOW GRADE

A. Insulation shall be closed-cell, elastomeric pipe insulation having a conductivity of 0.27 at 75 °F mean, with thicknesses as follows:

Pipe Sizes	1/2" - 1-1/2"	>1-1/2"
Refrigeration (Suction Lines)	1"	1"

- B. Insulation shall be Armaflex "Armaflex" or equivalent by Johns-Manville, Owens-Corning.
- C. Exterior piping insulation will be painted with a white solvent based alkyl finish(Armaflex AB or equivalent), including all fittings, valves, etc. Jacket and insulation will be sealed weathertight and installed per manufacturers instructions. Where exposed to physical damage, exterior piping insulation will be covered with aluminum jacket, including all fittings, valves, etc. Jacket and insulation will be sealed weathertight and installed per manufacturers instructions.

D. All interior underground water(domestic and hydronic) piping shall be insulated with 1" Armaflex, except where noted.

2.03 REFRIGERANT PIPE INSULATION

- A. Insulation shall be 1" thick, closed-cell, elastomeric pipe insulation having a conductivity of 0.27 at 75 °F mean.
- B. Exterior piping insulation will be painted with a white solvent based alkyl finish(Armaflex AB or equivalent), including all fittings, valves, etc. Jacket and insulation will be sealed weathertight and installed per manufacturers instructions. Where exposed to physical damage, exterior piping insulation will be covered with aluminum jacket, including all fittings, valves, etc. Jacket and insulation will be sealed weathertight and installed per manufacturers instructions.

per manufacturers instructions.

2.04 DUCT LINER

- A. Duct liner shall be 1-1/2 lb density (3.0lb for exterior ducts), constructed of glass fiber liner. The air stream surface is coated with black-coated mat surface. Liner shall have a "K" value of 0.24-inch at 75F mean.
- B. Duct liner shall be installed as follows or as shown on the plans:
  - 1. Exterior supply, return, or make up air ducts: 3"
  - 2. Return air ducts(within 15' of fan): 12"
  - 3. Outside air intakes within space: 1"
  - 4. Treated make up air within space: (not insulated)
- C. Liner shall be Johns-Manville "Linacoustic" or equivalent by Owens-Corning. Certained or Knuf.

2.05 EXTERIOR DUCT INSULATION BOARD

- A. Duct insulation shall be rigid polystyrene board insulation. Insulation shall have a K-factor no greater than .23 at 75°F mean.
- B. Duct board shall be installed as follows or as shown on the plans:
  - 1. Supply, return, or make up air ducts air ducts(exterior): 2" 3"
- C. Cover insulation board with metal jacket, secure with screws or bands. Seal jacket weather tight with silicone caulk.
- D. Or at the contractors discretion: cover insulation with a self-adhering weather proof membrane. Polyguard or equiv. Install per manufacturer's recommendations.

3.01 PIPE(ELASTOMERIC)

- A. Insulation shall be solid slip-on installed prior to connection. Butt joints shall be sealed with manufacturer's adhesive. Where slit seams must be installed, seal the seam with manufacturer's adhesive. Fittings shall be insulated with method of insulation according to manufacturer's instructions, or insulated with similar sheet insulation installed according to manufacturer's instructions.
- B. Provide wood blocks and metal hanger shields at support strap locations on horizontal pipe runs. Insulation will not be interrupted for supports, etc.

3.02 ACOUSTIC DUCT LINER

- A. Liner shall be secured to all duct surfaces by pressing into wet adhesive, applied to 100% of the duct surface. In addition, liner shall be held in place with insulings welded to duct and with clips shipped over the pins. Insulings shall be located per SMACNA Standards. Liner shall be lapped and compressed in all four corners of the duct. Both upstream and downstream transverse edges shall be coated with adhesive, coated a minimum of 1" over the edge in all places.

SECTION 23 09 00 -AUTOMATIC TEMPERATURE CONTROLS

1.01 SCOPE

- A. Furnish, install, and place in operation a complete system of automatic temperature controls. The temperature control contractor may be the mechanical contractor or approved sub-contractor.
- B. Acceptable automatic temperature control equipment manufacturer's shall be Honeywell, Johnson Controls, or controls furnished by the specific equipment manufacturer.
- C. The control system shall include all components and accessories necessary to provide a complete system. All wiring for automatic temperature controls, regardless of voltage shall be the responsibility of the ATC Contractor. 120VAC water shall be installed in conformance with requirements of Division 16. The Temperature Contractor shall coordinate all electrical work associated with his installation with the Electrical Contractor. Power wiring for all equipment, shall be the responsibility of the Electrical Contractor.

1.02 QUALITY ASSURANCE

- A. Upon completion of the work, instruct the building operating personnel and provide two (2) complete sets of operating and maintenance instruction booklets.
- B. Submit copies of complete temperature control diagrams with written "sequence of control" and factory-printed specification data sheets covering each control device proposed to be used, prior to installation of any equipment or part of system.

1.03 SERVICE AND GUARANTEE

A. The Contractor shall guarantee the control system installed under this section of the specification to be free from defects in workmanship and material under normal use, and agrees to provide service for one (1) year after acceptance by the Engineer or of beneficial occupancy of the building. Any defects in workmanship or material during this time shall be corrected at no charge to the Owner.

2.01 THERMOSTATS

A. HVAC unit thermostats shall be low-voltage, programmable, heating/cooling type with fan on-auto switch. Units shall be Honeywell TH6000 or equivalent .

3.01 SEQUENCE OF OPERATION

- A. HVAC units shall each be controlled by a heating/cooling thermostat.
- B. Toilet exhaust fans shall be controlled with associated lights.
- C. Activation of a duct detector shall shut down its respective HVAC unit.

SECTION 23 21 00 - HYDRONIC PIPING SYSTEMS

1.01 WORK INCLUDED:

A. The work required is indicated on the drawings and includes, but is not necessarily limited to, a complete hydronic heating system, using a boiler as the heat source.

2.01 PIPING:

A. Piping shall be Type "L" copper with 50/50 solder joints or schedule 40 black steel with threaded or welded joints.

2.02 EXPANSION TANK:

A. The expansion tank shall be a welded steel, diaphragm type tank, ASME rated, sized as shown and sized on the drawings. The tank fitting shall include an air purger, air vent, and fill valve.

2.03 PUMPS:

- A. Pumps shall be 1750 rpm single-stage, in-line, centrifugal oil-lubricated, sleeve-bearing pump bronze fitted with cast iron casting with flanged piping connections, and having mechanical seals.
- B. Motor selections shall be such that they are non-overloading under all conditions of operation. Motors shall be open drip-proof type. Provide motor controller for each pump.
- C. All pumps shall be by the same manufacturer, Grundfos, Bell & Gossett, Taco, Paco, or approved equiv.

2.04 BOILER

- A. (Air) Before adjustments are made, check the system for such items as dirty filters, duct and damper leakage, vibrations, etc. All diffusers, duct sections, etc. shall be adjusted to deliver design quantities within 5%. Air quantities shall be tested simulating filters being 50% loaded. Adjust/replace sleeves and bells as required to achieve design air quantities. Replace thermal motor overloads as required.
- B. (Hydronic) Before adjustments are made, check the system to make water treatment has been completed and glycol added. Also check for leaks, vibrations, etc. All circuit streets shall be adjusted to deliver design fluid within 5%. Verify that there is no pump cavitation, and that boilers and coolers are cycling at appropriate temperatures.
- C. The boiler shall be furnished with a heavy-gauge aluminumized steel base with aluminumized steel curtain walls. The end, front, and back base panels shall be protected with high-temperature insulation board panels. The boiler base shall be factory packaged with burner manifolds, main burners, base panels, and insulation board panels.
- D. Gas burners: The boiler shall be provided with stainless steel main burners which shall be manufactured of one-piece construction. The burner shall modulate down to 10%.
- E. Controls:
  - 1. All electrical safety controls are to be of accepted quality manufacture and shall be U.L. and A.G.A. design certified.
  - 2. The boiler shall be equipped with intermittent ignition pilot system.
  - 3. The inlet gas pressure to the boiler manual main shut-off gas valves should be no less than 5" water column or no more than 7" water column.
  - 4. Operating controls shall be as shown on the plans.

F. Water Boiler Sizing and Controls:

- 1. Low-limit (operating) and high-limit temperature controls. The low-limit control shall be set according to the design requirements of the heating system. The high-limit control should be set at least 20aF higher than the low-limit control setting.
- 2. ASME-certified pressure relief valves and the valves shall be set to relieve at the rated boiler ASME working pressure.
- 3. Low water cut-off with manual reset, per the state boiler code.
- G. The boiler will be manufactured by Triangle Tube, Laars, Raypak, or equivalent.

WATER HEATER (HYDRONIC):

- A. Provide a hydronic water heater, sized as shown on the plans. The heater shall be constructed of a polyethylene tank, insulated with urethane foam insulation, with a steel outer shell. The heat exchanger shall be made of coiled copper tubes, completely immersed within the tank. An immersion thermostat shall be provided with adjustable temperature control, including necessary interlocks and relays for the hydronic pump control interface. Provide a P/T relief, reset for the heater, piped full size to a nearby floor drain.
- B. Location: Sheet metal may be used throughout the project.
- C. Flexible Ductwork (Polymer Liner):
  - 1. Flexible ductwork shall be constructed of a spring steel helix supporting a plastic core. It shall be insulated with 1" fiberglass having a density of 1 lb./cu. ft. The insulation is sheathed in an copolymer vapor barrier jacket.
  - 2. The duct shall be rated at 10" w.g., and a maximum velocity of 4000 fpm. The duct shall be listed in conformance with UL Standard 181, Class 1.
  - 3. Flexible duct shall be limited to a maximum length of 2', as a means of connecting boxes, diffusers, etc. to the duct system. Uninsulated flexduct may be used where the adjacent ductwork is uninsulated or unlined.
  - 4. Flexduct shall be manufactured by Hart & Cooley, Cleveflex or equivalent.

1.02 SPECIAL DUCT SYSTEMS

- A. Kitchen hood exhaust:
  - 1. Duct shall be constructed strictly according to the latest ASHRAE and SMACNA standards. All duct work shall be constructed of 16-gauge steel or 304 stainless steel, 18-gauge minimum. All duct, and duct to hood joints, with longitudinal seams and transverse joints continuously but welded. Slope exhaust duct at not less than 1/2"/ft, except where other code requirements require a steeper slope. Duct connections to fans shall be flanged and gasketed to be airtight.
  - 2. Ducts shall be wrapped with a two layers of fire encapsulated, alumina/silica fibrous blanket, in strict accordance with the manufacturer's instructions, and in conformance with ASTM sd 2336. Joints shall be butt joints with overlaps. The blanket shall be firmly secured to the duct using carbon steel bands. Blanket shall be 3M Firemaster, Ductwrap or Firewrap, or equivalent.
- B. Exterior ducts shall be painted with paint rated for 150F, color as selected by the Architect. The duct will be cleaned and primed prior to painting.
- C. Flue Piping:
  - 1. All parts of the vent system shall be Underwriters Laboratories-listed, type B, double-wall, gas vent piping. The outer wall shall be galvanized steel; inner wall shall be 1100 alloy aluminum with built-in 1" air space. All flues shall terminate in a roof cap, as required by code.
  - 2. The flue vent piping shall be manufactured by Metalbestos. Approved equivalents are Heat-fab, Selkir, or Hart and Cooley.

SECTION 23 21 13 - RADIANT SNOW MELT SYSTEM


4.01 GENERAL

- A. The General Conditions of the Contract, Supplementary Conditions, and General Requirements shall be used in conjunction with this division as a part of the Contract Documents. Contractors shall be responsible for and be governed by all requirements hereof.
- B. Provide hydronic snow melt system that is manufactured, fabricated and installed to comply with regulatory agencies and authorities with jurisdiction, and maintain




1. PROVIDE QUAD WITH COMBINATION DUPLEX RECEPTACLE WITH HALF SWITCHED PORT. TOP RECEPTACLE IS TO BE SWITCHED PORTION FOR GARBAGE DISPOSAL OPERATION. PROVIDE TOTAL OF 3 UNSWITCHED RECEPTACLES.
2. TYPICAL UNIT ELECTRICAL PANEL, COORDINATE PANEL MOUNTING HEIGHT WITH ADA REQUIREMENTS (N ACCESSIBLE UNITS), MAINTAIN MINIMUM CLEARANCE TO FRONT OF PANEL AS REQUIRED PER NEC, NO PIPING, DUCTWORK OR OTHER TRACES WORK TO BE ROUTED OVER PANEL. ALL WORK IN THIS AREA TO BE COORDINATED WITH G.C. AND E.C. PROPOSED ELECTRICAL SERVICE/GEAR. FIELD VERIFY EXACT LOCATION, MAINTAIN REQUIRED CLEARANCES PER NEC.
3. UNIT TELEPHONE/CABLE TERMINAL: FIELD VERIFY LOCATION AND MOUNTING HEIGHT ON WALL WITH TELECOM SERVICE PROVIDER. LOCATE DUPLEX RECEPTACLE BELOW TERMINAL FOR CONNECTION OF TELECOM EQUIPMENT, RE; TELEPHONE/CABLE DETAIL FOR ADDITIONAL INFORMATION.
4. HOISTING MOTOR LOCATED IN ELEVATOR SHAFT: PROVIDE NON-FUSED DISCONNECT, FIELD VERIFY AND COORDINATE THE LOCATION & CONNECTION REQUIREMENTS WITH THE ELEVATOR MFG'S INSTALLATION SPECIFICATIONS PRIOR TO ROUGH-IN.
5. PROVIDE TELEPHONE, POWER, CIRCUIT(S), WIRING, J-BOX(ES) AND CONNECTION FOR ELEVATOR CAR. PROVIDE OVER CURRENT PROTECTION AND A LOCKABLE DISCONNECTING MEANS FOR ELEVATOR CAR RECEPTACLES, LIGHTING AND VENTILATION. THE E.C. SHALL FIELD VERIFY AND COORDINATE EXACT LOCATION AND CONNECTION REQUIREMENTS WITH THE ELEVATOR VENDOR PRIOR TO ROUGH-IN. LABEL SWITCH "120V ELEVATOR CAR DISCONNECT".
6. PROVIDE LOCKABLE SHUNT TRIP BREAKER FOR ELEVATOR MOTOR, LOCATED WITHIN 18" OF DOOR. PROVIDE CONTROL WIRING AS REQUIRED BY LOCAL INSPECTOR.
7. PROVIDE GFCI TYPE RECEPTACLE; DO NOT CONNECT LUMINAIRE TO LOAD SIDE OF GFCI.
8. PROVIDE COUNTERTOP POP-UP 15A GFCI-PROTECTED RECEPTACLE.
9. COORDINATE RADIANT FLOOR HEAT SIZE AND LOCATION WITH ARCHITECTURAL PLANS. FIELD VERIFY CONNECTION LOCATION.
10. BASIS OF DESIGN FOR STEAMER; AMEREC AKS. COORDINATE INSTALLATION AND VERIFY REQUIREMENTS WITH MANUFACTURER.
11. TOWEL WARMER ASSUMED TO BE 150W/UNIT. COORDINATE ACTUAL WATTAGE AND VERIFY REQUIREMENTS WITH MANUFACTURER. FIELD VERIFY CONNECTION LOCATION.
12. POWER FOR ELEVATOR SMOKE CURTAIN. COORDINATE CONNECTION TYPE AND INSTALLATION REQUIREMENTS WITH MANUFACTURER.
13. POWER FOR WINDOW SHADE. COORDINATE WITH MANUFACTURER/INSTALLER FOR POWER AND LOW VOLTAGE REQUIREMENTS.

- A. ELECTRICAL CONDUITS, WATER, SEWER AND GAS LINES MUST FIT WITHIN WALLS. CONFLICTS WITH OTHER TRADES MUST BE COORDINATED OR WORK WILL BE REDONE.
- B. GFCI PROTECTION: BASIS OF DESIGN IS GFCI PROTECTION PROVIDED AT PANEL. EC MAY PROVIDE ALTERNATE PRICING WHERE PERMITTED BY CODE TO PROVIDE DOWNSTREAM GFCI PROTECTION OF DEVICES WITH A SINGLE GFCI RECEPTACLE. (DEDICATED NEUTRAL SHALL BE PROVIDED FOR GFCI BREAKERS)
- C. COORDINATE ALL DEVICE AND FIXTURE LOCATIONS WITH FURNITURE, EQUIPMENT, MILLWORK AND MECHANICAL SYSTEM (DUCTWORK) LAYOUT PRIOR TO ROUGH-IN.
- D. ALL EXTERIOR ELECTRICAL COMPONENTS SHALL MEET ALL NEC INSTALLATION AND LABELING REQUIREMENTS FOR WET LOCATIONS.
- E. ALL RECEPTACLES TO BE LABELED WITH PANEL CIRCUIT ID ON BACKSIDE OF COVER PLATE.

[illegible]

**REVIEWED  
FOR  
CODE  
COMPLIANCE**  
04/01/2025

ASTRID BUILDING 7  
STEAMBOAT SPRINGS, COLORADO




Project Phase
PERMIT
Sheet Title
LOWER LEVEL   POWER PLAN
Sheet Number
E1.1




1. STAIRS SHALL BE ON EM BACKUP. SEE MAIN LEVEL LIGHTING PLAN FOR REFERENCE.


- A. E.C. SHALL VERIFY THE EXACT LOCATION, MOUNTING HEIGHTS AND QUANTITY OF ALL FIXTURES AND DEVICES WITH THE ARCHITECTURAL DRAWINGS.
- B. E.C. SHALL VERIFY FIXTURE LOCATION, DETAILS, AND QUANTITY OF ALL FIXTURES WITH THE LIGHTING DESIGNER DRAWINGS.
- C. SOME LIGHTING FIXTURES AND DEVICES ARE SHOWN OFFSET ON THE PLAN FOR GRAPHIC PURPOSES. E.C. SHALL COORDINATE THE EXACT LOCATION AND ROUGH-IN HEIGHT OF ALL FIXTURES AND DEVICES.
- D. ALL EMERGENCY EGRESS LIGHTING SHALL COMPLY WITH 2021 - IBC 1008.2.1
- E. ALL EXTERIOR LIGHTING FIXTURES SHALL BE INSTALLED, SHIELDED AND/OR CONTROLLED IN COMPLIANCE WITH LOCAL ORDINANCES.
- F. ALL EXTERIOR ELECTRICAL COMPONENTS SHALL MEET ALL NEC INSTALLATION AND LABELING REQUIREMENTS FOR WET LOCATIONS.
- G. COORDINATE REQUIRED BLOCKING FOR ADDED CEILING FANS WITH LANDLORD'S REPRESENTATIVE.

[illegible]

**REVIEWED FOR  
CODE  
COMPLIANCE**  
04/01/2025



ASTRID BUILDING 7  
STEAMBOAT SPRINGS, COLORADO



<b>Job Number:</b>	23035-7
<b>Date:</b>	03/21/24
<b>Drawn By:</b>	Author
<b>Checked By:</b>	EM

Project Phase
PERMIT
Sheet Title
LOWER LEVEL   LIGHTING PLAN

Sheet Number

E1.2







1. STAIRS SHALL BE ON EM BACKUP. SEE MAIN LEVEL LIGHTING PLAN FOR REFERENCE.
2. WIRE TO ELEVATOR SHAFT 120V POWER. HOUSE PA CKT-2. SEE POWER PLAN FOR REFERENCE.



All design, documents and data prepared by Eric Smith Associates, P.C. as instruments of service shall remain property of Eric Smith Associates, P.C. and shall not be copied, changed or disclosed in any form whatsoever without first obtaining the express written consent of Eric Smith Associates, P.C.

[illegible]

**REVIEWED  
FOR  
CODE  
COMPLIANCE**  
04/01/2025



ASTRID BUILDING 7  
STEAMBOAT SPRINGS, COLORADO




<b>Job Number:</b>	23035
<b>Date:</b>	03/21/
<b>Drawn By:</b>	Author
<b>Checked By:</b>	EM

<b>Project Phase</b>
PERMIT
<b>Sheet Title</b>
LOWER LEVEL 2 LIGHTING PLAN

Sheet Number  
**E2.2**



1. PROVIDE QUAD WITH COMBINATION DUPLEX RECEPTACLE WITH HALF SWITCHED PORT. TOP RECEPTACLE IS TO BE SWITCHED PORTION FOR GARBAGE DISPOSAL OPERATION. PROVIDE TOTAL OF 3 UNSWITCHED RECEPTACLES.
2. TYPICAL UNIT ELECTRICAL PANEL, COORDINATE PANEL MOUNTING HEIGHT WITH ADA REQUIREMENTS (IN ACCESSIBLE UNITS). MAINTAIN MINIMUM CLEARANCE TO FRONT OF PANEL AS REQUIRED PER NEC, NO PIPING, DUCTWORK OR OTHER TRADES WORK TO BE ROUTED OVER PANEL. ALL WORK IN THIS AREA TO BE COORDINATED WITH G.C. AND E.C. PROPOSED ELECTRICAL SERVICE/GEAR. FIELD VERIFY EXACT LOCATION, MAINTAIN REQUIRED CLEARANCES PER NEC.
3. UNIT TELEPHONE/CABLE TERMINAL; FIELD VERIFY LOCATION AND MOUNTING HEIGHT ON WALL WITH TELECOM SERVICE PROVIDER. LOCATE DUPLEX RECEPTACLE BELOW TERMINAL FOR CONNECTION OF TELECOM EQUIPMENT. RE: TELEPHONE/CABLE DETAIL FOR ADDITIONAL INFORMATION.
4. PROVIDE COUNTERTOP POP-UP 15A GFCI-PROTECTED RECEPTACLE.
5. COORDINATE RADIANT FLOOR HEAT SIZE AND LOCATION WITH A163 AND ARCHITECT.
6. PROPOSED LOCATION FOR ELECTRICAL SERVICE, MAINTAIN NECESSARY CLEARANCES. FIELD VERIFY CONNECTION LOCATION.
7. BASIS OF DESIGN FOR STEAMER: AMEREC AKS. COORDINATE INSTALLATION AND VERIFY REQUIREMENTS WITH MANUFACTURER.
8. TOWEL WARMER ASSUMED TO BE 150W/UNIT. COORDINATE ACTUAL WATTAGE AND VERIFY REQUIREMENTS WITH MANUFACTURER. FIELD VERIFY CONNECTION LOCATION.
9. POWER FOR ELEVATOR SMOKE/FIRE CURTAIN. COORDINATE CONNECTION TYPE AND INSTALLATION REQUIREMENTS WITH MANUFACTURER.
10. POWER FOR WINDOW SHADE. COORDINATE WITH MANUFACTURER/INSTALLER FOR POWER AND LOW VOLTAGE REQUIREMENTS.
11. ELEVATOR SMOKE/FIRE CURTAIN GROUP CONTROL PANEL. COORDINATE CLEARANCES WITH MANUFACTURER AND MECHANICAL EQUIPMENT. PROVIDE J BOX FOR POWER.



**REVIEWED  
FOR  
CODE  
COMPLIANCE**  
04/01/2025



Release of these plans contemplates further operation among the owner, his contractor and the architect. Design and construction are complex. Although the architect and his consultants have performed their services with due care and diligence, the owner and contractor are responsible for the proper and every contingency cannot be anticipated. Ambiguity or discrepancy discovered by the use of these plans shall be reported immediately to the architect. Failure to notify the architect compounds understanding and increases construction costs. A is to cooperate by a simple notice to the architect shall relieve the architect from responsibility for the sequences. Changes made from the plans without the consent of the architect are unauthorized and shall relieve the architect of responsibility for all consequences arising out of such changes.

all design, documents and data prepared by Eric Smith Associates, P.C. as instruments of service shall remain property of Eric Smith Associates, P.C. and shall not be copied, changed or disclosed in any form whatsoever without first obtaining the express written consent of Eric Smith Associates, P.C.

Eric Smith Associates, P.C.

[illegible]

**ASTRID BUILDING 7**  
**STEAMBOAT SPRINGS, COLORADO**



**1919 SEVENTH STREET  
BOULDER, COLORADO, 80302  
(303) 442-5458, (303) 442-4745 FAX**


<b>Job Number:</b>	23035-7
<b>Date:</b>	03/21/24
<b>Drawn By:</b>	Author
<b>Checked By:</b>	EM

Sheet Title

### E3.1



1. STAIR LIGHTING SHALL BE ON EM INVERTER (LITEMINDER PWII OR SIMILAR) TO RUN FULL BRIGHT FOR 90 MIN UNDER POWER LOSS. FINAL WATTAGE SHALL BE COORDINATED WITH LIGHTING DESIGNER.




Eric Smith Associates, P.C.

p.	Description	Date

---

Page 10 of 10



### Project Phase


## ГЛАВА 2

---







1. PROVIDE QUAD WITH COMBINATION DUPLEX RECEPTACLE WITH HALF SWITCHED PORT. TOP RECEPTACLE IS TO BE SWITCHED PORTION FOR GARBAGE DISPOSAL OPERATION. PROVIDE TOTAL OF 3 UNSWITCHED RECEPTACLES.
2. TYPICAL UNIT ELECTRICAL PANEL, COORDINATE PANEL MOUNTING HEIGHT WITH ADA REQUIREMENTS (IN ACCESSIBLE UNITS). MAINTAIN MINIMUM CLEARANCE TO FRONT OF PANEL AS REQUIRED PER NEC, NO PIPING, DUCTWORK OR OTHER TRADES WORK TO BE ROUTED OVER PANEL. ALL WORK IN THIS AREA TO BE COORDINATED WITH G.C. AND E.C. PROPOSED ELECTRICAL SERVICE/GEAR. FIELD VERIFY EXACT LOCATION, MAINTAIN REQUIRED CLEARANCES PER NEC.
3. UNIT TELEPHONE/CABLE TERMINAL; FIELD VERIFY LOCATION AND MOUNTING HEIGHT ON WALL WITH TELECOM SERVICE PROVIDER. LOCATE DUPLEX RECEPTACLE BELOW TERMINAL FOR CONNECTION OF TELECOM EQUIPMENT. RE: TELEPHONE/CABLE DETAIL FOR ADDITIONAL INFORMATION.
4. PROVIDE COUNTERTOP POP-UP 15A GFCI-PROTECTED RECEPTACLE.
5. COORDINATE RADIANT FLOOR HEAT SIZE AND LOCATION WITH ARCHITECTURAL PLANS.
6. BASIS OF DESIGN FOR STEAMER: AMEREC AK9. COORDINATE INSTALLATION AND VERIFY REQUIREMENTS WITH MANUFACTURER.
7. TOWEL WARMER ASSUMED TO BE 150W/UNIT. COORDINATE ACTUAL WATTAGE AND VERIFY REQUIREMENTS WITH MANUFACTURER.
8. POWER FOR ELEVATOR SMOKE CURTAIN. COORDINATE CONNECTION TYPE AND INSTALLATION REQUIREMENTS WITH MANUFACTURER.
9. POWER FOR WINDOW SHADE. COORDINATE WITH MANUFACTURER/INSTALLER FOR POWER AND LOW VOLTAGE REQUIREMENTS.





1. STAIRS SHALL BE ON EM BACKUP. SEE MAIN LEVEL LIGHTING PLAN FOR REFERENCE.
2. WIRE TO ELEVATOR SHAFT 120V POWER. HOUSE PANEL CKT-2. SEE POWER PLAN FOR REFERENCE.

[illegible]

ASTRID BUILDING 7  
STEAMBOAT SPRINGS, COLORADO



<b>Job Number:</b>	23035-7
<b>Date:</b>	03/21/24
<b>Drawn By:</b>	Author
<b>Checked By:</b>	EM

<b>Project Phase</b>
PERMIT
<b>Sheet Title</b>
UPPER LEVEL LIGHTING PLAN

Sheet Number  
**E4.2**



1. COORDINATE SOLAR ARRAY LOCATION AND SIZE IWTH ARCHITECT AND PV VENDOR. VERIFY AREA OF ROOF USED FOR FUTURE PV INSTALLATION.

1. COORDINATE SOLAR ARRAY LOCATION AND SIZE IWTH ARCHITECT AND PV VENDOR. VERIFY AREA OF ROOF USED FOR FUTURE PV INSTALLATION.

A. BASIS OF DESIGN IS RAYCHEM ICESTOP SYSTEM (GM-2XT;

- A. BASIS OF DESIGN IS RAYCHEM ICEBOST SYSTEM (GM-2XT; 208V/1Ø). SYSTEM STARTUP TEMPERATURE TO BE SET AT 20°F. MAXIMUM LENGTH OF CABLE PER CIRCUIT:
1. 15A @208V = 150 L.F.
  2. 20A @208V = 235 L.F.
- B. PROVIDE WITH APS SERIES MASTER SNOW CONTROLLER AND SC-20C SLAVE CONTROLLER AS REQUIRED.
- C. SYSTEM COMPONENTS TO INCLUDE AERIAL SNOW SENSOR (RAYCHEM SNOW OWL), BUTTER SENSOR (GIT-1), CABLE POWER CONNECTION KITS (FTC-P), SPLICER-TIE KITS (FTC-ST-PLUS), END SEAL KIT (FTG-CLICE), ROOF CLIPS (SMK-RC) DOWNSPOUT HANGER (GM-RAKE) AND ANY ADDITIONAL ACCESSORIES REQUIRED TO INSTALL SYSTEM PER MANUFACTURER'S INSTRUCTIONS.
- D. GFCI PROTECTION TO BE PROVIDED AT SNOW MASTER/SLAVE CONTROLLERS.
- E. TOTAL LENGTH OF HEAT TRACE ESTIMATED TO BE 1060 FT (FIVE 20A @208V CIRCUITS MINIMUM). COORDINATE CONNECTION ACCESSORIES AND INSTALLATION WITH MANUFACTURER. FIELD VERIFY INDIVIDUAL SEGMENT LENGTHS. J-BOXES SHOWN FOR COORDINATION AND LOAD ESTIMATION ONLY.
- F. FOR VERTICAL DOWNSPOUTS: PROVIDE SINGLE RUN OF HEAT TRACE WITH 12" LOOP AT BOTTOM.
- G. FOR GUTTERS: PROVIDE ONE RUN OF HEAT TRACE. CONTRACTOR TO PROVIDE A COMPLETE SYSTEM INCLUDING CONTROLS, TRANSFORMERS, PIPE STRAP, END SEAL KIT, GLASS TAPE, ECT. PROVIDE ONE CONTROLLER WITH TEMPERATURE SENSORS PER CIRCUIT. REFER TO DETAIL ON SHEET E300 FOR FURTHER INFORMATION.



NOTICE: DUTY OF COOPERATION

Release of these plans contemplates further cooperation among the owner, his contractor and the architect. Design and construction are complex. Although the architect and his consultants have performed their services with due care and diligence, they cannot guarantee perfection. Communication is imperfect and some emergency changes are inevitable. Any legal or disciplinary action covered by the use of these plans shall be reported immediately to the architect. Failure to notify the architect constitutes misunderstanding and increases construction costs. A failure to cooperate by a simple notice to the architect shall relieve the architect from responsibility for the consequences. Changes made from the plans without consent of the architect are unauthorized and shall relieve the architect of responsibility for all consequences arising out of such changes.

All design, documents and data prepared by Eric Smith Associates, P.C. as instruments of service shall remain property of Eric Smith Associates, P.C. and shall not be copied, changed or disclosed in any form whatsoever without first obtaining the express written consent of Eric Smith Associates, P.C.

Eric Smith Associates, P.C.

## REVISIONS

[illegible]

ASTRID BUILDING 7  
STEAMBOAT SPRINGS, COLORADO



<b>Job Number:</b>	23035-7
<b>Date:</b>	03/21/24
<b>Drawn By:</b>	Author
<b>Checked By:</b>	EM

## Project Phase

PERMIT	
<b>Sheet Title</b>	
ROOF ELECTRICAL PLAN	

Sheet Number

## E5.1



## ROOF ELECTRICAL PLAN







PANEL 4-BED UNIT 2 (LARGEST)																				
SUPPLY FROM:					VOLTS: 120/208 Wye					A.I.C. RATING: 65,000										
MOUNTING: RECESSED					PHASES: 3					MAINS TYPE: MLO										
ENCLOSURE: NEMA 1					WIRES: 4					MAINS RATINGS: 400 A										
CIRCUIT DESCRIPTION	LT	TRIP	P	BT		A	B	C		BT	P	TRIP	LT	CIRCUIT DESCRIPTION	LT	TRIP	P	BT		
BEDROOM #1 RECEPTS	ND	20	1	A	1					2	AG	1	20	ND	KITCHEN RECEPTS	ND	20	1	A	1
BEDROOM #2 RECEPTS	ND	20	1	A	3					4	AG	1	20	ND	KITCHEN RECEPTS	ND	20	1	A	3
BEDROOM #3 RECEPTS	ND	20	1	A	5					6	AG	1	20	ND	DISH / DISPOSAL	ND	20	1	A	5
LIVING RM RECEPTS	ND	20	1	A	7					8	A	1	20	ND	MICRO / HOOD	ND	20	1	A	7
LIVING RM RECEPTS / SPARE	ND	20	1	A	9					10	AG	1	20	ND	REFRIG / ISLAND RECEPTS	ND	20	1	A	9
BATHROOM GFCI	ND	20	1	AG	11					12	AG	1	20	ND	WASHER	ND	20	1	AG	11
LTG CKT - BATHROOM	ND	20	1	A	13					14	A	1	20	ND	DATA / TELECOM	ND	20	1	A	13
LTG CKT - EXT	ND	20	1	A	15					16	S	2	70	ND	COOKTOP	ND	20	1	A	15
EXTERIOR GFCI	ND	20	1	AG	17					18	S	2	70	ND	SPARE	ND	35	2	S	21
DRYER	ND	35	2	S	21					22	A	1	20	--	CU 1.5	ND	20	1	A	23
BED #4/BUNK RECEPTS	ND	20	1	A	23					24	S	2	20	ND	GRILL / SPARE	ND	20	1	A	25
OFFICE RECEPTS/BED #5	ND	20	1	A	25					26	S	1	20	ND	BATHROOM GFCI	ND	20	1	A	27
HALLWAY RECEPTS	ND	20	1	A	27					28	AG	1	20	ND	AH 1.5	ND	30	2	S	29
2X EUH-1	ND	30	2	S	29					30	S	2	20	ND	BATHROOM GFCI	ND	20	1	AG	33
BATHROOM GFCI	ND	20	1	AG	33					34	S	2	35	ND	BATHROOM GFCI	ND	20	1	AG	35
BATHROOM GFCI	ND	20	1	AG	35					36	S	2	20	ND	EVH	ND	35	2	S	37
EVH	ND	35	2	S	37					38	S	2	20	ND	ERV DUCT HEAT	ND	35	2	S	39
HUMIDIFIER	ND	20	2	S	41					42	AG	1	20	ND	RADIANT FLOOR...	ND	20	2	S	43
FIREPLACE	ND	20	1	A	45					44	AG	1	20	ND	RADIANT FLOOR BATH 1/2	ND	20	1	A	45
ERV & AH 4	ND	20	2	S	47					46	AG	1	20	ND	RADIANT FLOOR BATH 3	ND	20	2	S	49
WALL OVEN 1	ND	35	2	S	53					48	S	2	35	ND	RADIANT FLOOR PRIM BATH	ND	35	2	S	51
AH 4 DUCT HEATER	ND	50	2	S	55					50	S	2	35	ND	WALL OVEN 2	ND	35	2	S	53
EV CHARGER	ND	40	2	S	59					56	S	2	35	ND	AH 1.5 DUCT HEATER	ND	50	2	S	55
GARAGE DOOR OPENER	ND	20	1	S	63					58	AG	1	20	ND	BATHROOM GFCI	ND	20	1	AG	33
CU 4	ND	20	2	S	65					59	AG	1	20	ND	BATHROOM GFCI/SPARE	ND	40	2	S	59
STEAMER 1	ND	60	2	S	71					60	S	1	20	ND	BH1	ND	20	1	S	63
STEAMER 2	ND	60	2	S	73					61	A	1	20	ND	SPARE	ND	20	1	S	65
STEAMER 3	ND	60	2	S	75					62	S	1	20	ND	TOWEL WARMER	ND	20	2	S	67
SPACE	--	--	1	S	81					63	A	1	20	ND	SPARE	ND	60	2	S	71
SPACE	--	--	1	S	83					64	A	1	20	ND	LTG CKT - EAST	ND	60	2	S	73
										65	A	1	20	ND	LTG CKT - WEST	ND	60	2	S	75
										66	S	1	20	ND	GARAGE	ND	60	2	S	77
										67	A	1	20	ND	FA (120V)	ND	60	2	S	79
										68	AG	1	20	ND	GARAGE GFCI	ND	60	2	S	77
										69	S	3	60	--	FOR FUTURE SOLAR ELECTRIC	ND	--	--	1	81
										70	S	3	60	--		ND	--	--	1	83
										71	S	3	60	--		ND				
										72	S	3	60	--		ND				
										73	S	3	60	--		ND				
										74	S	3	60	--		ND				
										75	S	3	60	--		ND				
										76	S	3	60	--		ND				
										77	S	3	60	--		ND				
										78	S	3	60	--		ND				
										79	S	3	60	--		ND				
										80	S	3	60	--		ND				
										81	S	3	60	--		ND				
										82	S	3	60	--		ND				
										83	S	3	60	--		ND				
										84	S	3	60	--		ND				
TOTAL LOAD:					25.93 kVA					25.93 kVA					25.93 kVA					
TOTAL AMPS:					216 A					216 A					216 A					
LOAD TYPE		CONNLOAD		DEMAND FACT.		EST. DEMAND		BREAKER TYPE		PANEL TOTALS										
LIGHTING / EV - L		O KVA		0%		O KVA		SHUNT TRIP - ST												
RECEPTACLE - R		O KVA		0%		O KVA		GFCI - G												
MOTOR - M		O KVA		0%		O KVA		HANDLE BLOCK - H												
KITCHEN - K		O KVA		0%		O KVA		HANDLE TIE - T												
OTHER - O		O KVA		0%		O KVA		AFCI - A												
EXISTING - E		O KVA		0%		O KVA		STANDARD - S												
NEC-220.84								LOCKOUT - L												
TOTAL CONN. LOAD:					77.73 kVA					TOTAL EST. DEMAND:					77.73 kVA					
TOTAL CONN. LOAD:					216 A					TOTAL EST. DEMAND:					216 A					

PANEL 6-BED UNIT 4 (LARGEST)																			
SUPPLY FROM:					VOLTS: 120/208 Wye					A.I.C. RATING: 65,000									
MOUNTING: RECESSED					PHASES: 3					MAINS TYPE: MLO									
ENCLOSURE: NEMA-1					WIRES: 4					MAINS RATINGS: 400 A									
CIRCUIT DESCRIPTION	LT	TRIP	P	BT		A	B	C		BT	P	TRIP	LT	CIRCUIT DESCRIPTION					
BEDROOM #1 RECEPTS	--	20	1	A	1					2	AG	1	20	--					
BEDROOM #2 RECEPTS	--	20	1	A	3					4	AG	1	20	--					
BEDROOM #3 RECEPTS	--	20	1	A	5					6	AG	1	20	--					
LIVING RM RECEPTS	--	20	1	A	7					8	A	1	20	--					
LIVING RM RECEPTS / SPARE	--	20	1	A	9					10	AG	1	20	--					
BATHROOM GFCI/REIRC PUMP	--	20	1	AG	11					12	AG	1	20	--					
LTG CKT - BATHROOM	--	20	1	A	13					14	A	1	20	--					
LTG CKT - EXT	--	20	1	A	15					16	S	2	70	--					
EXTERIOR GFCI	--	20	1	AG	17					18	S	2	70	--					
DRYER	--	20	2	AG	19					20	A	1	20	ND					
BED #4/BUNK RECEPTS	--	20	1	A	23					24	S	2	20	--					
BEDROOM #5	--	20	1	A	25					26	S	1	20	--					
HALLWAY RECEPTS	--	20	1	A	27					28	AG	1	20	--					
2X EUH 1	--	20	2	S	29					30	S	2	20	--					
BATHROOM GFCI	--	20	1	AG	33					34	S	2	35	--					
BATHROOM GFCI	--	20	1	AG	35					36	S	2	35	--					
EVH	--	35	2	S	37					38	S	2	20	--					
										40	S	2	20	--					
HUMIDIFIER	--	20	2	S	41					42	AG	1	20	--					
FIREPLACE	--	20	1	A	45					46	AG	1	20	--					
ERV & AH 4	--	20	2	S	47					48	AG	1	20	--					
										50	S	2	35	--					
WALL OVEN 1	--	35	2	S	51					52	S	2	35	--					
										54	S	2	35	--					
AH 4 DUCT HEATER	--	50	2	S	55					56	S	2	35	--					
										58	AG	1	20	--					
EV CHARGER	--	40	2	S	59					60	AG	1	20	--					
										62	S	1	20	--					
GARAGE DOOR OPENER	--	20	1	S	63					64	AG	1	20	ND					
CU 4	--	20	2	S	65					66	S	1	20	--					
										68	AG	1	20	ND					
STEAMER 1	--	60	2	S	71					72	A	1	20	ND					
										74	A	1	20	ND					
STEAMER 2	--	60	2	S	73					76	A	1	20	ND					
										78	AG	1	20	ND					
STEAMER 3	--	60	2	S	77					80	S	1	20	--					
										82	S	3	80	--					
STEAMER 4	ND	60	2	S	83					84	S	3	80	--					
TOTAL LOAD:					28.41 kVA	28.41 kVA	28.41 kVA												
TOTAL AMPS:					237 A	237 A	237 A												
LOAD TYPE	CONN/LOAD	DEMAND	FACT.	EST. DEMAND	BREAKER TYPE		PANEL TOTALS												
LIGHTING / EV - L	O KVA	0%		O KVA	SHUNT TRIP -	ST													
RECEPTACLE - R	O KVA	0%		O KVA	GFCI -	G	TOTAL CONN. LOAD: 65.24 kVA												
MOTOR - M	O KVA	0%		O KVA	HANDLE BLOCK -	H	TOTAL EST. DEMAND: 65.24 kVA												
KITCHEN - K	O KVA	0%		O KVA	HANDLE TIE -	T	TOTAL CONN. LOAD: 237 A												
OTHER - O	O KVA	0%		O KVA	AFCI -	A	TOTAL EST. DEMAND: 237 A												
EXISTING - E	O KVA	0%		O KVA	STANDARD -	S													
NEC-220.84:							LOCKOUT -	L											



4

PANEL 4-BED UNIT 1																								
SUPPLY FROM:						VOLTS: 120/208 Wye						A.I.C. RATING: 65,000						MOUNTING: RECESSED						
ENCLOSURE: NEMA 1						PHASES: 3						MAINS TYPE: MLO						WIRES: 4						
MAINS RATINGS: 400 A																								
CIRCUIT DESCRIPTION		LT	TRIP	P	BT	A		B		C		BT	P	TRIP	LT	CIRCUIT DESCRIPTION								
BEDROOM #1 RECEPTS	--	20	1	A	1	0	0					2	AG	1	20	--	KITCHEN RECEPTS							
BEDROOM #2 RECEPTS	--	20	1	A	3			0	0			4	AG	1	20	--	KITCHEN RECEPTS							
BEDROOM #3 RECEPTS	--	20	1	A	5					0	0	6	AG	1	20	--	DISH / DISPOSAL							
LIVING RM RECEPTS	--	20	1	A	7	0	0					8	A	1	20	--	MICRO / HOOD							
LIVING RM RECEPTS / SPARE	--	20	1	A	9			0	0			10	AG	1	20	--	REFRIG / ISLAND RECEPTS							
BATHROOM GFCI	--	20	1	AG	11					0	0	12	AG	1	20	--	WASHER							
LTG CKT - BATHROOM	--	20	1	A	13	0	0					14	A	1	20	--	DATA / TELECOM							
LTG CKT - EXT	--	20	1	A	15			0	0			16	S	2	70	--								
EXTERIOR GFCI	--	20	1	AG	17					0	0	18	S	2	70	--	COOKTOP							
DRYER	--	35	2	S	19	0	0					20	S	1	20	--	SPARE							
					21			0	0			22	S	2	20	--	CU 1.5							
BED #4/BUNK RECEPTS	--	20	1	A	23			0	0		0	24	S	2	20	--								
OFFICE RECEPTS/BED #5	--	20	1	A	25	0	0					26	S	1	20	--	GRILL / SPARE							
HALLWAY RECEPTS	--	20	1	A	27							28	AG	1	20	--	BATHROOM GFCI							
2X EUH-1	--	20	2	S	29			0	0		0	30	S	2	20	--	AH 1.5							
					31							32	S	2	20	--								
BATHROOM GFCI	--	20	1	AG	33			0	0			34	S	2	35	--								
BATHROOM GFCI	--	20	1	AG	35					0	0	36	S	2	35	--	EWV							
EWV	--	35	2	S	37	0	0					38	S	2	20	--								
					39			0	0			40	S	2	20	--	ERV DUCT HEAT							
HUMIDIFIER	--	20	2	S	41					0	0	42	AG	1	20	--	RADIANT FLOOR...							
					43	0	0					44	AG	1	20	--	RADIANT FLOOR BATH 1/2							
FIREPLACE	--	20	1	A	45			0	0		0	46	AG	1	20	--	RADIANT FLOOR BATH 3							
ERV & AH 4	--	20	2	S	47					0	0	48	AG	1	20	--	RADIANT FLOOR PRIM BATH							
					49							50	S	2	35	--								
WALL OVEN 1	--	35	2	S	51			0	0			52	S	2	35	--	WALL OVEN 2							
					53					0	0	54	S	2	20	--	AH 1.5 DUCT HEATER							
AH 4 DUCT HEATER	--	50	2	S	55	0	0					56	S	2	20	--								
					57			0	0			58	AG	1	20	--	BATHROOM GFCI							
EV CHARGER	--	40	2	S	59			0	0		0	60	AG	1	20	--	BATHROOM GFCI/SPARE							
					61							62	S	1	20	--	BH1							
GARAGE DOOR OPENER	--	20	1	S	63			0	0			64	S	1	20	--	SPARE							
CU 4	--	20	2	S	65					0	0	66	S	1	20	--	TOWEL WARMER							
					67			0	0			68	S	1	20	--	SPARE							
STEAMER 1	--	60	2	S	69					0	0	70	A	1	20	--	LTG CKT - EAST							
					71						0	72	A	1	20	--	LTG CKT - WEST							
STEAMER 2	--	60	2	S	73	0	0					74	A	1	20	--	GARAGE							
					75			0	0			76	A	1	20	--	FA (120V)							
STEAMER 3	--	60	2	S	77					0	0	78	AG	1	20	--	GARAGE GFCI							
					79	0	0					80	S	3	80	--								
SPARE	--	20	1	S	81							82	S	3	80	--								
SPARE	--	20	1	S	83							84	S	3	80	--	FOR FUTURE SOLAR ELECTRIC							
TOTAL LOAD:						25.67 kVA						25.67 kVA						25.67 kVA						
TOTAL AMPS:						214 A						214 A						214 A						
LOAD TYPE		CONN. LOAD		DEMAND FACT.		EST. DEMAND		BREAKER TYPE		ST		PANEL TOTALS												
LIGHTING / EV -	L	0	kVA	0%		0	kVA	SHUNT TRIP -	G	TOTAL CONN. LOAD: 77.02 kVA														
RECEPTACLE -	R	0	kVA	0%		0	kVA	GFCI -	G	TOTAL EST. DEMAND: 77.02 kVA														
MOTOR -	M	0	kVA	0%		0	kVA	HANDLE BLOCK -	H	TOTAL CONN. DEMAND: 214 A														
KITCHEN -	K	0	kVA	0%		0	kVA	HANDLE TIE -	T	TOTAL EST. DEMAND: 214 A														
OTHER -	O	0	kVA	0%		0	kVA	AFCI -	A															
EXISTING -	E	0	kVA	0%		0	kVA	STANDARD -	S															
NEC-220.84-								LOCKOUT -		L														

PANEL 4-BED UNIT 3																								
SUPPLY FROM:						VOLTS: 120/208 Wye						A.I.C. RATING: 65,000						MOUNTING: RECESSED						
ENCLOSURE: NEMA 1						PHASES: 3						MAINS TYPE: MLO						WIRES: 4						
CIRCUIT DESCRIPTION						A						B						C						
CIRCUIT DESCRIPTION						BT						P						TRIP						
BEDROOM #1 RECEPTS	--	20	1	A	1	0	0					2	AG	1	20	--								
BEDROOM #2 RECEPTS	--	20	1	A	3			0	0			4	AG	1	20	--								
BEDROOM #3 RECEPTS	--	20	1	A	5			0	0			6	AG	1	20	--								
LIVING RM RECEPTS	--	15	1	A	7			0	0			8	A	1	20	--								
LIVING RM RECEPTS / SPARE	--	20	1	A	9			0	0			10	AG	1	20	--								
BATHROOM GFCI	--	20	1	AG	11			0	0			12	AG	1	20	--								
LTG CKT - BATHROOM	--	15	1	A	13	0	0			0	0	14	A	1	20	--								
LTG CKT - EXT	--	15	1	A	15			0	0			16	S	2	70	--								
EXTERIOR GFCI	--	20	1	AG	17			0	0			18	S	2	70	--								
DRYER	--	35	2	S	19			0	0			20	S	1	20	--								
BED #4/BUNK RECEPTS	--	20	1	A	21			0	0			22	S	2	20	--								
OFFICE RECEPTS/BED #5	--	20	1	A	23			0	0			24	S	1	20	--								
HALLWAY RECEPTS	--	20	1	A	25			0	0			26	AG	1	20	--								
2X EUH-1	--	30	2	S	29			0	0			30	S	2	20	--								
BATHROOM GFCI	--	20	1	AG	33			0	0			34	S	2	35	--								
BATHROOM GFCI	--	20	1	AG	35			0	0			36	S	2	35	--								
EWVH	--	35	2	S	37	0	0					38	S	2	20	--								
HUMIDIFIER	--	20	2	S	41	0	0					42	AG	1	20	--								
FIREPLACE	--	20	1	A	45	0	0			0	0	44	AG	1	20	--								
ERV & AH 4	--	20	2	S	49			0	0			48	AG	1	20	--								
WALL OVEN 1	--	35	2	S	53			0	0			52	S	2	35	--								
AH 4 DUCT HEATER	--	50	2	S	55			0	0			56	S	2	35	--								
EV CHARGER	--	40	2	S	59			0	0			60	AG	1	20	--								
GARAGE DOOR OPENER	--	20	1	S	63			0	0			64	S	1	20	--								
CU 4	--	20	2	S	65					0	0	66	S	1	20	--								
STEAMER 1	--	60	2	S	69	0	0					68	S	1	20	--								
STEAMER 2	--	60	2	S	71			0	0			70	A	1	20	--								
STEAMER 3	--	60	2	S	73	0	0					74	A	1	20	--								
SPARE	--	20	1	A	75			0	0			76	A	1	20	--								
SPARE	--	20	1	S	77			0	0			78	AG	1	20	--								
SPARE	--	20	1	81				0	0			80	S	3	80	--								
SPARE	--	20	1	83				0	0			82	S	3	80	--								
TOTAL LOAD:						25.56 kVA						25.56 kVA												
TOTAL AMPS:						213 A						213 A												
LOAD TYPE	CONNLOAD		DEMAND FACT.		EST. DEMAND		BREAKER TYPE		SHUNT TRIP		T		ST		PANEL TOTALS									
LIGHTING - EV - L	0 KVA		0%		0 KVA		GFCI -		G		GFCI -		G		TOTAL CONNN. LOAD: 76.67 kVA									
RECEPTACLE - R	0 KVA		0%		0 KVA		HANDLE BLOCK -		H		HANDLE BLOCK -		H		TOTAL EST. DEMAND: 76.67 kVA									
MOTOR - M	0 KVA		0%		0 KVA		HANDLE TIE -		T		HANDLE TIE -		T		TOTAL CONNN. 213 A									
KITCHEN - K	0 KVA		0%		0 KVA		AFCI -		A		AFCI -		A		TOTAL EST. DEMAND: 213 A									
OTHER - O	0 KVA		0%		0 KVA		STANDARD -		S		STANDARD -		S											
EXISTING - E	0 KVA		0%		0 KVA		LOCKOUT -		L		LOCKOUT -		L											
NEC-220.64.																								



DIVISION 26 - ELECTRICAL

SECTION 26 01 00 - GENERAL PROVISIONS

1.01 WORK INCLUDED:

A. The work included by this division of the specifications includes furnishing all labor, materials, equipment, and services, including minor items omitted but necessary to construct and install the complete systems described by the Contract Documents and specified below. "Contractor" refers to the Electrical Contractor. The general conditions of the specifications apply and are included in this part of this section.

- Power Distribution System
- Interior and Exterior Lighting System
- Telephone Raceway System
- Data Raceway System
- Fire Alarm System
- Emergency Lighting System
- Electric Heating System

1.02 CODES AND REGULATIONS:

A. Comply with state and local codes, and utility company regulations. Final interpretations will be made by the local inspection authority. The Contractor to verify the governance of the following Codes, including any local amendments and supplementary codes such as the Codes of the National Fire Protection Association:

- Building Code: 2021 International Building Code
- Plumbing Code: 2021 International Plumbing Code
- Mechanical Code: 2021 International Mechanical Code
- Fire Code: 2021 International Fire Code
- Gas Code: 2021 International Fuel Gas Code
- Energy Code: 2021 International Energy Conservation Code
- Electrical Code: 2023 National Electrical Code

1.03 EQUIPMENT AND MATERIALS STANDARDS:

A. Equipment and materials shall be new, UL-listed for the use intended, and free from damage or defect. They shall comply with the latest industry standards.

1.04 CONTRACT DRAWINGS:

A. Illustrate the general design and extent of performance required. All dimensions and locations shall be taken from the Architectural drawings. Consult with Architectural plans and detail all ceiling equipment where indicated on reflected ceiling plans.

1.05 SHOP DRAWINGS

A. Submit products data and/or shop drawings as required by the Architect for the following:

- Switches, dimmers, receptacles and coverplates
- Switchboards, Panelboards/Loadcenters
- Disconnect switches
- Fuses
- Light fixtures
- Fire alarm system and equipment

B. Quality of specific equipment

established by manufacturer's catalog number. Alterations caused by any Substitution shall be accomplished at no additional expense to the Owner  
C. Manufacturers not listed may submit for acceptance as an "approved equivalent." Requests for an "equivalent" means "approved equivalent". Four copies of such submittal must be received by the Engineer seven (7) working days prior to bid date.

1.06 WARRANTY:

A. The contractor shall be responsible for the successful operation of electrical systems, equipment, and materials installed under this Contract for a period of one year from the date of final acceptance. Defective equipment or materials shall be repaired or replaced at no expense to the Owner.

1.07 PRODUCT HANDLING AND CLEAN UP:

A. Equipment shall be left clean and undamaged, to the satisfaction of the Owner. The General Conditions take precedence.

1.08 CUTTING AND REPAIRING:

A. The contractor shall be responsible for all cutting, drilling, welding, and repair required for his portion of the work. Coordinate with the Architect. The General Conditions take precedence.

1.09 OPERATING AND MAINTENANCE DATA:

A. Provide the Owner with operating and maintenance instructions(four copies) required for operation of all electrical systems. Bind the written instructions in a notebook. The General Conditions take precedence.

1.10 PERMITS:

A. The contractor shall pay for all fees, taxes, secure permits, licenses, and inspections required for the project.

1.11 TEMPORARY SERVICES:

A. Provide temporary power and lighting as required by the General Contractor, in accordance with OSHA and N.E.C. standards.

1.12 COORDINATION

A. Coordinate outlet device and equipment locations with the Architectural Plans and work of other trades. Locate on horizontal and vertical lines to avoid interference and to provide functional use of all equipment. Verify electrical power characteristics before ordering fixtures, equipment, etc.  
B. Mechanical work performed by this contractor will conform to the standards of Division 21-23. Mechanical equipment motors and controls shall be furnished, set in place, and wired according with the following schedule unless otherwise noted or specified. MC = Division 21-23 EC = Division 26-28

Item	Furn By	Set By	Power By	Control Wiring
Combination starters	MC	EC	EC	MC
Equipment motors	MC	MC	EC	--
Motor starters & O.L. relays	MC	EC	EC	MC
Disconnect switches	EC	EC	EC	MC
Thermal overload heaters (1)	EC	EC	EC	--
Variable Speed Drives	MC	EC	EC	MC
Control relays/transformers	MC	MC	EC	MC
Temperature control panels	MC	MC	EC	MC
Temp. Controls conduit/wiring	MC	MC	--	MC
Actuator and solenoid wiring	MC	MC	--	MC
Pushbuttons & pilot lights	MC	MC	--	MC
Room thermostats	MC	MC	MC	--
Thermostat: line voltage	EC	EC	EC	--

C. The general guideline for the division control(by MC) wiring and power wiring(by EC) is that power wiring carries the current which energizes a motor, control wiring does not. Control wiring may be 120V, which would be the responsibility of the MC. Control motors are wired by the MC.  
D. Examine the site and become aware of existing conditions, utilities, and other issues affecting the satisfactory completion of the project.

1.13 DELIVERY, STORAGE, HANDLING:

A. Provide necessary hauling and hoisting equipment. Protect the materials of this Division before, during, and after installation.

1.14 AS-BUILT DRAWINGS:

A. Keep a current set of "as-built" drawings on site. Upon completion of the work, furnish engineer with a reproducible prints showing the "as-built" installation.

1.15 PROJECT/SITE CONDITIONS:

A. Visit the site to become familiar with location and the various conditions affecting the work, including existing utilities.

2.01 ACCESS PANELS:

A. The electrical Contractor shall furnish and General Contractor shall install access panels where required for access to equipment. The electrical Contractor shall include the cost of installation in his bid. Access panels shall be adequately sized, of a type approved by the Architect and shall be fire or smoke-rated as required.

3.01 EXCAVATION AND BACKFILLING:

A. Verify the location of underground utilities before excavation; the contractor is responsible for any damage to underground utilities. Provide excavating and backfilling for electrical work. Backfill in 12" layers, mechanically tamp to 95% proctor standards. Protect according to OSHA standards. The General Conditions take precedence.  
B. Provide marker tape 12" above exterior underground service conduits(power, telephone, television).

3.02 START-UP PROCEDURES:

A. Follow manufacturer's recommended procedures in starting up the equipment; damage caused during start-up shall be replaced at no expense to the owner.

3.03 HANGERS AND SUPPORTS:

A. Support conduit and equipment from the structure to prevent sagging, pocketing, swaying, and vibrations, and arranged to provide for expansion and contraction. Brackets, clamps, and hangers shall be steel or copper of a type, acceptable to the Engineer. Chain, perforated iron or wire hangers are not permitted.  
B. Conduit on the roof will be supported above the roof on roof pads. The pads shall be approximately 6"wide by 6" high by the length as required. They shall be made of recycled rubber, rated for 500lbs/ft loading each. The pads will have galvanized steel "C" channel attached to the top, which can accommodate pipe clamps to secure the conduit. This configuration of individual piping pads may be expanded to include two pads supporting a trapeze style support where multiple conduits are racked together. The pads are C-series manufactured by Cooper B-line or approved equivalent.

3.04 SLEEVES AND PLATES:

A. Provide sleeves and inserts for all conduit. The contractor shall be responsible for the cost of cutting and patching required for piping where sleeves and inserts were not installed or where incorrectly located. Sheetrock joint compound may be used to seal openings in non-rated walls(insulation to be continuous through walls.  
B. Drill holes as required for the installation of hangers required for the mechanical work.  
C. Where sleeves are placed in exterior walls below grade, the space between the pipe or conduit and the sleeves shall be made completely water-tight.  
D. Seal all piping passing through fire-rated construction with approved material to maintain air-tight, fire-rated integrity, with a U.L. listed assembly compatible with the wall or floor assembly being penetrated.

SECTION 26 05 00 - COMMON WORK RESULTS FOR ELECTRICAL

1.01 GENERAL:

A. Provide complete systems of conductors and raceways using conduit and/or cable assemblies appropriate to the function and location,

and specifically approved in chapter three of the N.E.C..

2.01 CONDUIT:

A. The following raceways are approved for use on this project, where approved by the N.E.C.:

- EMT: Electrical metallic tubing, galvanized
- GRC: Rigid steel conduit, galvanized
- PVC: Polyvinyl chloride conduit, schedule 40
- IMC: Intermediate metal conduit, galvanized

2.02 CABLE ASSEMBLIES:

A. The following cable assemblies may be used in the power distribution system in concealed locations, where approved by the N.E.C.:

- MC: Metal clad cable
- NM/NMC: Non-metallic sheathed cable
- SE/SEF: Service entrance cable (From MDC to residences)

2.03 BOXES:

A. Provide galvanized steel outlet and junction boxes, except where otherwise indicated. Boxes shall be a minimum 4" square or octagonal, depth as required. Provide weather-proof type cast boxes with gasket and cast coverplate for exterior outlets or wet locations. Outlet boxes shall be of the proper type and design for the fixture or device to be installed. Through the wall boxes are not permitted. Provide plaster or tie rings for all flush outlets installed where required. Boxes shall be manufactured by Raco, Steel City, National or equivalent.  
B. Interior floor boxes shall be non-metallic or cast steel in concrete or slab on grade installations, and shall be rated for the use. Floor boxes above grade shall be non-metallic or stamped steel, rated for the use. Multi-gang boxes shall be used where specified. Coverplates shall be polished brass with /lip lids for receptacles and connectors. Provide carpet flanges where appropriate.

2.04 CONDUCTORS:

A. Provide a complete set of power conductors, rated 600 volts, of the quantity, size and type required for the function.  
1. Conductors shall be copper, except where specifically noted. Conductors shall be solid for wire sizes No. 10 AWG and smaller; stranded for No. 8 AWG and larger.  
2. Aluminum conductors will be accepted only where specifically indicated by the Contract Documents. Aluminum conductors must be terminated according to the manufacturers instructions, including use of proper joint compound, use with aluminum rated lugs, and proper torquing of the lugs.

2.05 INSULATION:

A. Provide wire with the following minimum insulation standards:

- Branch circuits, panelboard feeders, service entrance conductors: THWN-2, XHHW(90C). The conductors shall be applied using the 75C rating.
- Connections to fixture ballasts, and wiring runs in or through fixture wiring channels: Insulations listed in table 402.5 of the N.E.C., except for wiring made with asbestos.
- Cord connections: Cords listed in table 400.4 of the N.E.C., except for wiring made with asbestos.

2.06 LUGS:

A. Lugs for all equipment will be rated for the use. Lugs will be suitable for copper or aluminum conductors, rated for 75C.

2.07 SWITCHES AND RECEPTACLES:

A. Provide specification grade devices throughout. Switches and duplex receptacles may be commercial grade. Devices shall be manufactured by Hubbell, Leviton, General Electric, Bryant, Slater, Pass & Seymour, Inc., Sierra, or Arrow-Hart.  
B. Except where noted, plates shall be plastic, color to match the devices with matching screws for receptacles, switches, telephone, and TV outlets. Provide blank coverplates for unused outlets. Coverplates for multi-gang boxes shall be sized for the box it covers.  
C. Devices and their coverplates colors shall be coordinated with Architect and Owner. In mechanical rooms, etc, the coverplates may be galvanized steel

2.08 DIMMERS:

A. Incandescent dimmers shall be the linear slide-type with aluminum fins. Dimmers shall be Lutron Nova series or equivalent.  
B. Fluorescent dimmers shall be the linear slide-type with aluminum fins. The dimmers shall be closely coordinated with the ballast type of the specific fixture being controlled and must be field coordinated before ordering. Dimmers shall be Lutron Nova series or equivalent.  
C. LED dimmers must be selected by, or specifically approved by, the specific fixture manufacturer or supplier. Slide type dimmers are preferred where available.  
D. When switches and dimmers are located side by side, switches shall have identical appearance as dimmers. Dimmers shall in no case have heat fins removed or modified.  
E. Dimmers shall be manufactured by Lutron, Hunt, Prescolite, or equivalent

3.01 WIRING:

A. The drawings are schematic in nature; alternative wiring paths, different conduit fill, etc, installed in conformance with the N.E.C. are allowed. Conductors must be derated per code.  
B. Branch circuits shall use minimum No. 12 AWG wiring for branch circuits, protected by 20 ampere circuit breakers. Control wiring may be No. 14 minimum. If distance from panel to first outlet is 75 feet or greater (for 120-volt circuits) or 150 feet or greater (for 277-volt circuits), provide No. 10 AWG.  
C. Use PVC in earth or in slabs in contact with earth. Outside the building, install a minimum of 30" below finished grade.  
D. Where mechanical damage occur, use galvanized rigid steel or intermediate metal conduit.  
E. Electric metallic tubing may be used in all applications, except where prohibited by code or otherwise noted.  
F. Do not install exposed conduit in areas open to the public. Exposed conduit may be installed at surface-mounted equipment and other locations acceptable to the Architect. Run exposed conduit parallel to, and at right angles with, the building lines.  
G. Direct burial wiring shall not be used.  
H. Use flexible metallic conduit for connections to motors, fixtures, or other equipment where vibration is encountered. Provide sealrite flexible metallic conduit in wet areas such as kitchens, equipment rooms, on roofs, etc.  
I. Provide a ground wire in non-metallic conduit and flexible conduit. Ground wires shall be increased in size where circuit wiring is increased for voltage drop.  
J. Circuits fed through AFCI breakers shall have separate neutrals with no cross or ground connections; wiring shall be installed per the breaker manufacturers instructions.  
K. Multi-wire branch circuits shall utilize handle ties on breakers, or other grouped disconnecting means per NEC 210.4(B).

3.02 OUTLET BOXES, DEVICES AND FITTINGS:

A. Install receptacle and telephone outlets 18" to center-line above floor in general locations; install at switch height where shown in combination; install 46" center-line in mechanical equipment rooms.  
B. Install receptacles vertically, ground pole down.  
C. Install switch outlets 46" to center-line above floor on latch side of door. Verify door swing prior to installation. Use gang boxes for multiple-device installation as required.  
D. Install outlets shown on the drawings "back-to-back" with a minimum of 6" lateral separation between them.

SECTION 26 20 00 - SERVICE AND DISTRIBUTION

1.01 SERVICE ENTRANCE:

A. Power will be available from the secondary side of transformer(s) provided by the utility company. This service shall be 120/208 volt, 3 phase, 4 wire, 60 hertz A.C. for normal power and lighting requirements. General arrangement of the service equipment is shown on the drawings. Load balance the entire system to within 15% per phase.

1.02 GROUNDING:

A. Provide a complete grounding system in accordance with Section 25.0 of the N.E.C.  
B. Supplemental electrode to be installed unless resistance of 25 ohms to earth can be documented.

2.01 PANELBOARDS:

A. Provide circuit breaker-type panelboards as detailed on the drawings. Provide separate ground bus. Provide fronts with door and latch with locks keyed alike. Install panels 6'6" above finished floor to top of trim. Where panels are mounted side by side, align tops of panels. Mount a typed directory, identifying each circuit, in a directory frame. Provide typed source label identifying source of power for each panel. Install trim and doors with primer coats in finished areas. Provide one spare 3/4" conduit for each 3 unused poles in flush-mounted panelboards; extend from to an accessible point above a hung ceiling; cap and identify.  
B. Breakers shall be full width, thermal magnetic, bolt-on type. Provide multi-pole breakers with common trip and single operating handle; handle ties are acceptable for multi-wire branch circuits.  
1. Breakers serving restaurant kitchens and bars, or where required by code, shall be GFCI breakers. GFCI receptacles may be used only where the receptacles are not located behind equipment.  
2. HACR breakers shall be used for HVAC equipment in accordance with the equipment manufacturer.  
C. Lugs on mains and branch breakers shall be rated for 75C or 60C, copper or aluminum wiring.  
D. Panelboards(240VAC) shall be Square D type NQOD or equivalent by I.T.E., G.E., or Cutler Hammer.

2.02 FUSIBLE DISTRIBUTION SWITCHGEAR:

A. Provide free-standing, floor-mounted, fusible type switchboard as shown on the plans.  
B. Switchboard shall be 90" high, depth as indicated, constructed so rear sections align, with internal components removable from the front.  
C. Buses shall be copper or tin-plated aluminum, braced for short-circuit currents of 100,000 RMS symmetrical amperes. Horizontal bars shall be tape-wrapped and insulated. Maximum temperature rise shall be 55C over 25C ambient. Provide full length and sized horizontal buses, including neutral and ground. Vertical sections shall be fully bussed. All lugs shall be rated for 75C or 60C copper or aluminum wiring.  
D. Manufacturers shall be General Electric "AV line" with QMR construction or equivalent by Square D, I.T.E., or Westinghouse.

2.03 CURRENT TRANSFORMER CABINETS:

A. Provide current transformer cabinets, including interior lugs and bussing, as required to accommodate the requirements of the utility company. The cabinets shall be U.L. listed, weatherproof as required. All lugs shall be rated for 75C or 60C wiring.

2.04 METER STACK:

A. Provide wall mounted modular meter stacks where shown on the plans. The unit shall be NEMA 3(NEMA 1), made of galvanized steel. The incoming section shall use a fused switch.  
B. The buses shall be copper or tin-plated aluminum, braced for short-circuit currents of 65,000AIC symmetrical amperes. Vertical sections shall be fully bussed top to bottom. Provide full length and sized horizontal buses, including neutral and ground. All lugs shall be rated for 75C or 60C copper or aluminum wiring.  
C. Meter stack shall accommodate both single phase and three phase, 100Amp and 200Amp meters and breakers. Additional sections shall be capable of simple connection.  
D. The meter stack shall be manufactured by American Midwest Power (AMP), Square D, G.E., Westinghouse ITE or equivalent.

2.05 SAFETY SWITCHES:

A. Provide normal duty, enclosed, fusible and non-fusible safety switches as indicated on the plans. All lugs shall be rated for 75C or 60C copper or aluminum wiring. Provide enclosures suitable for the surrounding area and conditions. Label switches for feeder or motor supplied. The switches shall be manufactured by Square D, I.T.E., G.E., Cutler Hammer, or equivalent.

2.06 FUSES:

A. Provide power fuses of the time-delay type unless otherwise indicated. Fuses shall be manufactured by Bussman, Gould Shawmut, or equivalent. Provide one (1) complete set of fuses for fuse-holding devices, sized according to the motor and/or conductor to be

protected. Provide a hinged cover cabinet for storage of spare fuses: three spare fuses of each fuse size.

3.01 WIRING FOR EQUIPMENT:

A. Provide branch circuits, feeders, junction boxes, disconnect switches, etc as required for a complete system; make power connections to motors and controls for heating, ventilating, air conditioning, plumbing, owner furnished and fire protection equipment as required.  
B. Kitchen equipment. Refer to the Kitchen Equipment Contractor's drawings for final sizing, locations, and rough-in heights. The Electrical Contractor shall provide final circuits and connections to kitchen electrical equipment. Sealante conduit and fittings shall be used on runs inside refrigerated bases and at dish tables.  
C. Provide connections to hood fire suppression system(s). The electrical contractor is responsible for wiring the interlock controls for hood related air handling equipment, including low voltage interlocks, and interlocks within building HVAC equipment where required.

SECTION 26 50 00 - LIGHTING

1.01 RECESSED LED:

A. Recessed LED luminaires shall be pre-wired. Openings shall be neatly made so they are completely concealed after the trim is installed. Luminaires installed in a grid ceiling shall be supported by the framing system, not by ceiling panels. Install metal plaster frames in plaster ceilings. Fixtures shall have thermal protection where required by the N.E.C. and local codes.

1.02 EXTERIOR LIGHTING FIXTURES:

A. Provide weather-proof luminaires for mounting as shown. Provide lamps of size and wattage as indicated on the drawings. Provide underground wiring to exterior lighting as shown on the drawings.

2.01 INTERIOR LIGHTING FIXTURES:

A. Securely support and anchor fixtures and outlet boxes. Where lighting fixtures are installed in a lay-in grid ceiling system, secure fixtures to tees by installing earthquake clips at each corner of the fixture. Provide supports required, including structural members if needed. Provide separate junction boxes and wire to recessed fixtures in flexible conduit with Type AF wire, unless acceptable pre-wired fixtures are used. Conceal openings cut in ceilings for recessed fixtures with fixture trim installed. Coordinate installation of recessed fixtures with ceiling installation.

2.02 EXTERIOR LIGHTING FIXTURES:

A. Exterior lighting fixtures, raceways, equipment, etc. shall be weather-proof and suitable for temperatures down to -20F.  
B. Ballast type, lamp wattage, and rated voltage shall be as indicated on the plans. Each ballast shall be of the separate- component type; capable of reliable lamp starting down to -20F, and shall have a minimum power factor of .90.

2.03 LAMPS:

A. Incandescent and LED replacement lamps shall be rated at 130V, H.I.D. and fluorescent lamps shall be as specified on plans with ballasts as specified in the following specifications. Lamp codes listed are ANSI. All lamps shall be Sylvania, General Electric, or approved equivalent.  
B. In porcelain fixtureless, provide medium base, self ballasted, A-line shape, fluorescent lamps, GE FLE15/2/A21 or equivalent.

2.04 DRIVERS:

A. LED drivers shall be electronic-type, labeled as compliant with radio frequency interference (RFI) requirements of FCC Title 47 Part 15, and comply with NEMA SSL 1 "Electronic Drivers for LED Devices, Arrays, or Systems". LED drivers shall have a sound rating of "A", have a minimum efficiency of 85%, and be rated for a THD of less than 20 percent at all input voltages.  
B. Dimmable LED drivers shall be 0-10V type. Dimmable LED drivers shall be capable of dimming without LED strobing or flicker across their full dimming range.  
C. Ballasts and drivers shall be rated for the ambient temperatures in which they are located. Outdoor fixtures shall be equipped with ballasts or drivers rated for reliable starting to -20 degrees F. Indoor fixtures located in areas with direct sunlight or above normal ambient temperatures shall have ballasts or drivers rated at 65 degrees C minimum.

2.05 OUTDOOR LIGHTING CONTROL:

A. Provide astronomical time switch, lighting control system as shown on drawings. Include contactors, time switches, transformers, selector switches, relays, wiring, etc. as required.  
B. Set time clock(s) to operate contacts as scheduled hours by Owner.  
C. Time clock shall be astronomical seven-day programmable type. Provide contacts as shown on plans. Time clock shall be readily adjustable.

DIVISION 27 - COMMUNICATIONS

SECTION 27 20 00 - COMPUTER SYSTEM

3.01 DESCRIPTION:

A. Provide a complete system of raceways, pull boxes, outlet boxes, and terminals. Raceways shall form a complete path up walls and across inaccessible ceilings. Computer wiring may be run wild above accessible ceiling.

4.01 CONDUIT:

A. Conduit in the building shall be galvanized EMT, with plastic bushings on ends which are not terminated in a box.

4.02 WALL OUTLETS:

A. Wall outlets shall be 4" square pressed steel boxes, with single gang plaster ring. Connectors and coverplates are to be provided by the computer system installer.  
B. Provide an alternate price for plaster rings at outlet location, and pullstrings in wall up to accessible ceiling, in lieu of conduit and boxes.

4.03 WIRING:

A. Wiring shall be provided by the computer system installer. Wiring run wild in air plenums shall be teflon coated or similarly rated for the application.

4.04 EXECUTION:

A. Provide pull strings in all conduit.  
B. Field verify all computer outlet locations. Final locations and heights shall be as designated by the Architect or Owner's representative.

SECTION 27 30 00 - TELEPHONE SYSTEM

1.01 DESCRIPTION:

A. Provide a complete system of raceways, pull boxes, outlet boxes, and terminals. Raceways shall form a complete path up walls and across inaccessible ceilings. Telephone wiring may be run wild above accessible ceiling.  
B. System will include exterior underground conduit routed to a point of connection(usually a pedestal or a power pole) as directed by the telephone company. Exterior conduit shall be sized and installed as directed by the telephone company.

2.01 CONDUIT:

A. Conduit in the building shall be galvanized EMT, with plastic bushings on ends which are not terminated in a box. Exterior underground conduit shall be schedule 40 PVC with solvent joints.  
B. Wall outlets shall be 4" square pressed steel boxes, with single gang plaster ring. Connectors and coverplates are to be provided by the telephone system installer.  
C. Provide an alternate price for plaster rings at outlet location, and pullstrings in wall up to accessible ceiling, in lieu of conduit and boxes.

2.02 TERMINALS:

A. Telephone terminals shall be constructed of 1/2" thick, fire resistant, interior finish plywood, painted white, sized as shown or required. Provide power and ground connection as required or shown on the plans.

2.03 WIRING:

A. Wiring shall be provided by the telephone system installer. Wiring run in air plenums shall be teflon coated or similarly rated for the application.

3.01 EXECUTION:

A. Provide pull strings in all conduit.  
B. Exterior underground conduit shall use long radius, sweep ell's. These elbows shall be schedule 80 PVC, or PVC coated GRC conduit.  
C. Field verify all telephone outlet locations. Final locations and heights shall be as designated by the Architect or Owner's representative.

SECTION 27 40 00 - VIDEO SYSTEM

1.01 DESCRIPTION:

A. Provide a complete system of raceways, pull boxes, outlet boxes, and terminals. Raceways shall form a complete path up walls and across inaccessible ceilings. Video wiring may be run wild above accessible ceiling.

2.01 CONDUIT:

A. Conduit in the building shall be galvanized EMT, with plastic bushings on ends which are not terminated in a box. Exterior underground conduit shall be schedule 40 PVC (schedule 80 PVC rated elbows) with solvent joints.

2.02 WALL OUTLETS:

A. Wall outlets shall be 4" square pressed steel boxes, with single gang plaster ring. Connectors and coverplates are to be provided by the video system installer. Provide an alternate price for plaster rings at outlet location, and pullstrings in wall up to accessible ceiling, in lieu of conduit and boxes.

2.03 WIRING:

A. Wiring shall be provided by the video system installer. Wiring run in air plenums shall be teflon coated or similarly rated for the application.

3.01 EXECUTION:

A. Provide pull strings in all conduit.  
B. Exterior underground conduit shall use long radius, sweep ell's. These elbows shall be schedule 80 PVC conduit.  
C. Field verify all television outlet locations. Final locations and heights shall be as designated by the Architect or Owner's representative.

DIVISION 28 - ELECTRONIC SAFETY AND SECURITY

SECTION 28 10 00 - SECURITY ALARM SYSTEM

1.01 DESCRIPTION:

A. Provide a complete door security alarm system to audibly and visually annunciate door entry/exit at a master control panel. The door alarms may be individually reset at the master control panel as well as by-passed during certain hours of the day.

2.01 ANNUNCIATOR PANEL:

A. The annunciator panel shall be comprised of (3) 4 door modules each with individual door reset/bypass pushbuttons with associated LEDs. The annunciator shall contain a common call placed LED, and alarm tone speaker, momentary action tone-silencing push button. The tone silencing circuitry shall automatically reset after the alarm is reset. Each button cap shall be marked with the door identity. The panel shall be constructed of anodized aluminum, supplied with a recessed mounting frame.

2.02 CONTROL UNIT:

A. The control unit shall include a volume control and be configured for pulsating alarm signal. A power supply shall be provided in conjunction with the control unit.

2.03 DOOR CONTACTS:

A. Door contacts shall be normally closed mechanical door contacts.

2.04 WIRING:

A. Wiring shall be low voltage 18 AWG, run per the manufacturers instructions. Wiring may be run wild above accessible ceilings, in raceways in inaccessible locations.

2.05 MANUFACT