

Project	Steamboat Base Village Redevelopment	Date	07/15/2021
Project Location	Steamboat, Colorado	Architect's Project Number	03.7835.000
Owner/Client	Alterra Mountain Company / East West Partners	File	6BL This is page 1 of 2
To	Saunders Construction Inc.	Attention	Bryan Sculthorpe
Address	86 Inverness Place North		
City	Englewood	State	CO Zip Code 80112
Delivered via:	<input type="checkbox"/> Messenger <input type="checkbox"/> Hand carried <input type="checkbox"/> Facsimile <input type="checkbox"/> Express <input type="checkbox"/> Pick-up <input type="checkbox"/> E-mail Address <input type="checkbox"/> Mail <input type="checkbox"/> UPS <input checked="" type="checkbox"/> Website Address BIM360		

This Bulletin Conveys to Contractor (Check one of the following five choices.):

- ☐ **Architect's Authorization for Minor Changes**
Architect recommends modifications to the Work as described below.
- ☐ **Architect's Clarification / Supplemental Instructions** (Use this Bulletin form in place of *Architect's Supplemental Instructions* form.)
Contractor shall carry out the Work in accordance with the following supplemental instructions.
- ☐ **Architect's Confirmation of a Field Order** (Use this Bulletin form in place of a *Field Order* form.)
This confirms Architect's verbal instructions to (individual's name) _____ on (date) _____, as described below.
Note: The above three choices are each subject to the following terms: The change(s), clarification(s) and/or confirmation(s) described below is/are issued in accordance with the Contract Documents, without change in Contract Sum and/or Time.
- ☒ **Architect's Request for Contractor's Proposal** (Use this Bulletin form in place of an *Estimate Request* form.)
Please submit an itemized proposal for changes in the Contract Sum and/or Time for proposed modifications to the Contract Documents described herein. Submit proposal **within** _____ **days** or notify the Architect in writing of the date on which you anticipate submitting your proposal. This is not a Change Order or a Construction Change Directive or a direction to proceed with the Work described in the proposed modifications.
- ☐ **Other:** As described below.

Attachments	BP3 GOLDWALK - BULLETIN 04 (MICROPILES)		
Requested by	<input type="checkbox"/> Architect <input type="checkbox"/> Owner <input checked="" type="checkbox"/> Contractor <input type="checkbox"/> Other (specify): _____		
Issued by Gensler by	Jacob Apple	Date Signed	07/15/2021
Issued by Owner by		Date Signed	
<input type="checkbox"/> Required; Please return signed copy to Gensler <input type="checkbox"/> Not Required			
Accepted by Contractor by		Date Signed	
<input type="checkbox"/> Required; Please return signed copy to Gensler <input type="checkbox"/> Not Required			
Distribution	Bryan Sculthorpe Greg Morgan Adam Cleveland Ryan Stone Mike Schmidt John Albright Gregg Riker		
Prepared by Gensler by	Jacob Apple	Date Signed	07/15/2021

Instructions / Description / References / Dates

Description of Changes:

General: This bulletin addresses revising foundations to a micropile design at the escalator.

Structural Drawing Changes:

1. 1B-S0.01
 - a. Micropiles are added to the 'deferred submittals'.
2. 1B-S0.02
 - a. Micropiles are defined in the 'Foundation Notes'.
3. 1B-S0.10
 - a. Micropile special inspections are added.
4. 1B-S1.01
 - a. Plan 1:
 - i. Micropile locations are added.
 - ii. Bottom of wall elevations are revised.
 - iii. New foundation to existing wall details are clarified.
 - b. Elevation 3:
 - i. Bottom of foundation elements are revised.
5. 1B-S2.00
 - a. Cross section 2:
 - i. Bottom of foundation elements are revised.
 - b. Cross section 3:
 - i. Bottom of foundation elements are revised.
6. 1B-S3.01:
 - a. Detail 4:
 - i. Bottom of foundation is revised for micropiles.
 - b. Detail 9:
 - i. Bottom of foundation is revised for micropiles.
 - c. Detail 10:
 - i. Bottom of foundation is revised for micropiles.
 - d. Detail 11:
 - i. Bottom of foundation is revised for micropiles.
 - e. Detail 16:
 - i. Bottom of foundation is revised for micropiles.
 - f. Detail 17:
 - i. Bottom of foundation is revised for micropiles.
 - g. Detail 19:
 - i. Pilaster geometry is revised and the pile cap is added for micropiles.
 - h. Detail 20:
 - i. Bottom of foundation is revised for micropiles.
7. 1B-S3.02
 - a. Detail 7:
 - i. Bottom of foundation is revised for micropiles.
 - b. Detail 12:
 - i. Detail is added.
 - c. Detail 13:
 - i. Detail is added.
 - d. Detail 16:
 - i. Detail is added.
 - e. Detail 18:
 - i. Detail is added.
 - f. Detail 20:
 - i. Detail is added.

ABBREVIATIONS


(E) or EXIST	Existing	EA	Each	LOC(s)	Location(s) or Locate	REIN	Reinforce(ing)(d)(ment)
(S)	Salvaged	EC	Epoxy Coated	LONG	Longitudinal	REQD	Required
@	Per	EE	Each End	Lr	Roof Live Load	REQT(s)	Requirement(s)
@	At	EF	Each Face	LSL	Laminated Strand Lumber	RET	Return
AB	Anchor Bolt	EJ	Expansion Joint	LT	Light	RO	Rough Opening
ACI	American Concrete Institute	EL	Elevation	LTE	Tension Embedment	ROF	Random Oriented Fiber S
ADDNL	Additional	ELEV	Elevator	LTS	Tension Lap Splice Length	SC	Slip Critical
AESS	Architecturally Exposed Structural Steel	EMB	Embedded	LTWT	Lightweight	SCHED	Schedule
AFF	Above Finish Floor	EN	Edge Nail	LVL	Level or Laminated Veneer Lumber	SECT	Section
ALT	Alternate	ENGR	Engineer	LWC	Light Weight Concrete	SIM	Similar
ALUM	Aluminum	EOR	Engineer-of-Record	MACH	Machine	SL	Snow Load
APA	American Plywood Association	EQ	Equal	MACH RM	Machine Room	SLH	Short Leg Horizontal
APPROX	Approximate	EQ SP	Equally Spaced	MAS	Masonry	SLRS	Seismic Load Resisting System
ARCH	Architect or Architectural	EQUIP	Equipment	MATL	Material	SLV	Short Leg Vertical
B/ or BO	Bottom of	ES	Each Side	MAX	Maximum	SOG	Slab on Grade
BAI	Balance	EW	Each Way	MECH	Mechanical	SP	Space(s)
BD	Board	EXP	Expansion	MEP	Mech/Elect/Plumb	SP @	Space at
BF	Braced Frame	EXP ANCH	Expansion Anchor	MIN	Minimum	SPECS	Specifications
BG	Backgouge	EXT	Exterior	MISC	Miscellaneous	SPRT	Support
BL	Brick Ledger	F	Fluid Load	MLS	mm	SS	Stainless Steel
BLDG	Building	FAB	Fabricate	MM	Millimeter	STD	Standard
BLKG	Blocking	FD	Footling Dowel	MNFR	Manufacturer	STIFF	Stiffener
BM	Beam	FF	Finished Floor	MO	Masonry Opening	STL	Steel
BN	Boundary Nail	FIN	Finish(ed)	MTL	Metal	STR	Structural
BOS	Bottom of Steel	FLG	Flange	N	North	SW	Shearwall
BOT or B	Bottom	FLR	Floor	N-S	North-South	SYM	Symmetrical
BOT	Bearing	FND	Foundation	NIC	Not in Contract	T	Top or Thermal Load
BSMT	Basement	FO	Face of	NM	Not in Contract	T&B	Top and Bottom
BTWN	Between	FP	Full Penetration or Fire Proofing	NO OR #	Number	T/ or T.O.	Top of
CC	Center to Center	FRAM	Framing	NOM	Nominal	THK	Thick or Thickness
CF	Cold Formed	FS	Far Side	NS	Non-Shrink or Near Side	TL	Total Load
CG	Center of Gravity	FT	Foot or Feet	NTS	Not to Scale	TOC	Top of Concrete
CIP	Cast-In-Place	FTG	Footling	NWC	Normal Weight Concrete	TOF	Top of Footing
CJ	Control Joint	FV	Field Verify	O.F.	Outside Face	TOM	Top of Masonry
CJP	Complete Joint Penetration	GA	Gage or Gauge	OAE	Or Approved Equivalent	TOP	Topping
CL	Centerline	GALV	Galvanized	OC	On Center	TOS	Top of Steel
CLG	Ceiling	GC	General Contractor	OD	Outside Diameter	TOW	Top of Wall
CLMS	Ceiling/Light/Mechanical/ Superimposed Load	GL	Glu-lam	OH	Opposite Hand	TRANS	Transverse
CLR	Clear	GR	Grade or Grind	OPNG	Opening	TWS	Two-Way Slab
CMU	Concrete Masonry Unit	GR BM	Grade Beam	OPP	Opposite	UPT	Typical
COL	Column	GR MB	Grade Beam	OVS	Oversized	ULT	Ultimate
CONC	Concrete	H	Soil Lateral Load	OWS	One-Way Slab	UNO	Unless Noted Otherwise
CONN	Connection	HAS or HDAS	Headed Anchor Stud	PAF	Powder Actuated Fastener	Vasd	Service Level/Nominal Design Wind Speed
CONST	Construction	HD	Headed or Holddown	PC	Precast	VERT	Vertical
CONT	Continue or Continuous	HDAR	Headed Anchor Rod	PCA	Portland Cement Association	VIF	Verify in Field
CONTR	Contractor	HDG	Hot Dipped Galvanized	PD	Pier Dowel	VUL	Ultimate Design Wind Speed
COORD	Coordinate	HK	Hook	PEMB	Pier-Engineered Metal Building	W	Wind Load
CSJ	Construction Joint	HORIZ	Horizontal	PEN	Penetration	W/	With
CTR(D)	Center(ed)	HT	Height	PERP	Perpendicular	W/O	Without
d	Penny	HVAC		PL	Plate (Steel)	WD	Width or Wood
D or DL	Dead Load	I.F.	Inside Face	PLF	Pounds Per Lineal Foot	WF	Wide Flange
DIAG	Deformed Anchor Stud	IN	Inch	PREFAB	Prefabricated	WI	Wind-on-Ice Load
DBL	Double	INT	Interior	PRELIM	Preliminary	WP	Working Point or Waterproofing
DCW	Demand Critical Weld	IS	Inside Diameter	PS	Prestressed	WPS	Welding Procedure Specification
DFS	Deferred Submittal	IT	Precast Inverted Tee Beam	PSF	Pounds Per Square Foot	WT	Weight
Di	Gravity Ice Load	JST	Joist	PSI	Pounds Per Square Inch	WWR	Welded Wire Reinforcing
DIA OR Ø	Diameter	JT	Joint	PT	Point or Post-Tension or Pretensioned	WxH	Width x Height
DIA	Diagonal	K	Kip	QTY	Quantity		
DIM	Dimension	L	Length or Live Load	R	Radius or Rain Load		
DN	Down	LB	Precast L-Shaped Beam	RAD	Radius		
DO	Ditto	LB(S)	Pound(s)	RB	Precast Rectangular Beam		
DP	Drilled Pier or Deep	LCE	Compression Embedment	RC	Reinforced Concrete		
DT	Precast Double Tee	LCS	Compression Lap Splice	RE: or REF	Refer to (Reference)		
DTL(s)	Detail(s)	LDH	Hook Development Length				
DWG(s)	Drawing(s)	LG	Length				
DWL(s)	Dowels(s)	LL	Live Load				
E	Earthquake Load	LLH	Long Leg Horizontal				
E-W	East-West	LLV	Long Leg Vertical				

1 I) POWDER ACTUATED FASTENERS (PAF) INTO CONCRETE OR CMU SHALL NOT BE USED TO RESIST TENSION LOADS. POWDER ACTUATED FASTENERS SHALL NOT BE USED TO RESIST GRAVITY LOADS WHICH INCLUDE BRICK VENEER.

1 J) REFERENCE COLD-FORMED STEEL FRAMING NOTES FOR ADDITIONAL DEFERRED SUBMITTAL DESIGN CRITERIA.

ROOF AREA	10 SF	100 SF	500 SF
ROOF INTERIOR NEG (ZONE 1)	-46.2	-35	-54.4
- USE THESE FOR JOIST UPLIFT WIND DESIGN FORCES UNO			
ROOF INTERIOR NEG (ZONE 1)	-24.5	-24.5	-16.0
ROOF NEGATIVE (ZONE 2)	-62.6	-48.2	-76.2
- EAVES, RAKES, RIDGES			
ROOF CORNERS NEG (ZONE 3)	-62.6	-48.2	-76.2
ROOF POSITIVE ALL ZONES	-16	-16	-16.0
ROOF NEGATIVE OVERHANG ZONE 1 & 1'	-46.2	-43.5	-54.4
ROOF NEGATIVE OVERHANG ZONE 2	-62.6	-43.4	-59.8
ROOF NEGATIVE OVERHANG ZONE 3'	-62.6	-43.4	-59.8
PARAPET PRESSURES			
SOLID PARAPET PRESSURE	10 SF	100 SF	500 SF
PARAPET CASE A: ZONE 2:	87.0	68.6	54.4
ZONE 3:	87.0	68.6	54.4
PARAPET CASE B: INTERIOR ZONE:	-49.0	-42.2	-35.4
CORNER ZONE:	-73.4	-58.5	-43.5
PARAPET CASE A = PRESSURE TOWARDS BUILDING (POS)			
PARAPET CASE B = PRESSURE AWAY FROM BLDG (NEG)			
PARAPET CAP UPLIFT PRESSURES			
ZONE 2:	-68.0 PSF		
ZONE 3:	-68.0 PSF		
5) LATERAL LOAD RESISTING SYSTEM DESCRIPTION:			
- SEISMIC RESISTING SYSTEM NOT CONSIDERED FOR ANCILLARY STRUCTURE ADDITION IN LEVEL B1 AND NEW SLAB REPLACEMENT AT LEVEL 1.			
- ESCALATOR CANOPY STRUCTURE - ROOF HSS FRAME AS DIAPHRAGM AND WOOD GLULAM COLUMN, HSS BEAM, AND ROD BRACE AS LATERAL FRAMES IN SHORT DIRECTION, WOOD GLULAM COLUMN MOMENT FRAMES IN LONG DIRECTION.			
6) GRAVITY LOADS			
6A) SEE LOAD KEY ON SHEET 1B-S0.02 FOR SUPERIMPOSED DEAD LOAD AND LIVE LOADS USED IN DESIGN.			
6B) DRIFTING, SLIDING AND UNBALANCED SNOW			
- GROUND SNOW LOAD = 132.0 PSF			
- SNOW EXPOSURE FACTOR, $C_e = 1.0$			
- SNOW LOAD IMPORTANCE FACTOR, $I_s = 1.0$			
- THERMAL FACTOR, $C_t = 1.20$ (ESCALATOR CANOPY)			
- UNIFORM ROOF SNOW LOAD = 110.9 PSF			
- FLAT ROOF SNOW LOAD = 110.9 PSF			
7) RAIN LOADS:			
7A) DESIGN RAIN INTENSITY = 2.5 INCHES PER HOUR			
7B) DESIGN RAIN ROOF PRESSURE = 21 PSF			

© 2021 Gensler © 2021 Martin/Martin

$$1/16'' = 1'-0''$$

$$1/16'' = 1'-0''$$

1) DESIGN CRITERIA:
THE GEOTECHNICAL REPORT PREPARED BY NORTHWEST COLORADO CONSULTANTS, INC., NUMBER 20-12000, DATED APRIL 22, 2021 PROVIDED CRITERIA FOR THE FOUNDATION DESIGN FOR THE PROJECT.

1) GENERAL:
1A) ENGINEER: REFERENCES ON THE STRUCTURAL DRAWINGS TO 'ENGINEER' MEAN THE STRUCTURAL ENGINEER OF RECORD. OTHER ENTITIES ARE SPECIFICALLY NOTED AS "CONTRACTOR'S ENGINEER", "MECHANICAL ENGINEER", ETC.

1. **GLUED LAMINATED MEMBERS:**
 1A) COMBINATION SYMBOL:
 - SINGLE SPAN: 24F-V4
 - MULTI- SPAN: 24F-V8
 1B) MINIMUM DESIGN VALUES ARE BASED ON THE 2018 NDS.

WOOD ELEMENT	SPECIES/ GRADE	Fb TOP/BOT (PSI)	Fv (PSI)	E (PSI)	REMARKS
GLULAMS - SINGLE SPAN	24F-V4	1850/2400	265	1,800,000	-
GLULAMS - MULTI-SPAN/COLS	24F-V4	2400/2400	265	1,800,000	SEE NOTE 2

NOTES:


1. PROPERTIES LISTED SHALL BE MET OR EXCEEDED.
2. MULTI-SPAN CONDITIONS INCLUDE GLULAM MEMBERS WITH CANTILEVERS

ALTERRA east west partners

2305 Mount Werner Circle
Steamboat Springs, CO 80487

1225 17th Street
Suite 150
Denver, CO 80202
United States

Tel 303.595.8585
Fax 303.825.6823



12499 West Colfax Ave
Lakewood, CO 80215
United States
Tel 303.431.6100

14143 Denver West Pkwy
Suite 300
Golden, CO
United States
Tel 303.421.6655



July 15, 2021

Seal / Signature

△	Date	Description
-	2021.05.19	BP3: GOLDWALK - ISSUE FOR BID AND PERMIT
1	2021.07.14	BP3: GOLDWALK - BULLETIN 04

DESIGNERS: NIC MARTIN
LEAD REVIT TECH: COLIN MONNIES
DATE PRINTED: 7/15/2021 11:06:17 AM
FILE PATH: BIM_360/703.7935.000 - Steamboat Redox/03.7935.000 Structural SBR_GSQ 2021_V2021.rvt

MM JOB #: 20.1411.S.01
PRINCIPAL: KELLY KNOWLES
LEAD: KELLY KNOWLES
PROJECT MANAGER: C. A. CHESTNUT

Project Name

SSRC | BASE AREA
IMPROVEMENTS

Project Number

003.7835.000

	Description
1	1. The first row contains the header information.
2	2. The second row contains the header information.
3	3. The third row contains the header information.
4	4. The fourth row contains the header information.
5	5. The fifth row contains the header information.
6	6. The sixth row contains the header information.
7	7. The seventh row contains the header information.
8	8. The eighth row contains the header information.
9	9. The ninth row contains the header information.
10	10. The tenth row contains the header information.
11	11. The eleventh row contains the header information.
12	12. The twelfth row contains the header information.
13	13. The thirteenth row contains the header information.
14	14. The fourteenth row contains the header information.
15	15. The fifteenth row contains the header information.
16	16. The sixteenth row contains the header information.
17	17. The seventeenth row contains the header information.
18	18. The eighteenth row contains the header information.
19	19. The nineteenth row contains the header information.
20	20. The twentieth row contains the header information.
21	21. The twenty-first row contains the header information.
22	22. The twenty-second row contains the header information.
23	23. The twenty-third row contains the header information.
24	24. The twenty-fourth row contains the header information.
25	25. The twenty-fifth row contains the header information.
26	26. The twenty-sixth row contains the header information.
27	27. The twenty-seventh row contains the header information.
28	28. The twenty-eighth row contains the header information.
29	29. The twenty-ninth row contains the header information.
30	30. The thirtieth row contains the header information.
31	31. The thirty-first row contains the header information.
32	32. The thirty-second row contains the header information.
33	33. The thirty-third row contains the header information.
34	34. The thirty-fourth row contains the header information.
35	35. The thirty-fifth row contains the header information.
36	36. The thirty-sixth row contains the header information.
37	37. The thirty-seventh row contains the header information.
38	38. The thirty-eighth row contains the header information.
39	39. The thirty-ninth row contains the header information.
40	40. The fortieth row contains the header information.
41	41. The forty-first row contains the header information.
42	42. The forty-second row contains the header information.
43	43. The forty-third row contains the header information.
44	44. The forty-fourth row contains the header information.
45	45. The forty-fifth row contains the header information.
46	46. The forty-sixth row contains the header information.
47	47. The forty-seventh row contains the header information.
48	48. The forty-eighth row contains the header information.
49	49. The forty-ninth row contains the header information.
50	50. The fiftieth row contains the header information.
51	51. The fifty-first row contains the header information.
52	52. The fifty-second row contains the header information.
53	53. The fifty-third row contains the header information.
54	54. The fifty-fourth row contains the header information.
55	55. The fifty-fifth row contains the header information.
56	56. The fifty-sixth row contains the header information.
57	57. The fifty-seventh row contains the header information.
58	58. The fifty-eighth row contains the header information.
59	59. The fifty-ninth row contains the header information.
60	60. The sixtieth row contains the header information.
61	61. The sixty-first row contains the header information.
62	62. The sixty-second row contains the header information.
63	63. The sixty-third row contains the header information.
64	64. The sixty-fourth row contains the header information.
65	65. The sixty-fifth row contains the header information.
66	66. The sixty-sixth row contains the header information.
67	67. The sixty-seventh row contains the header information.
68	68. The sixty-eighth row contains the header information.
69	69. The sixty-ninth row contains the header information.
70	70. The seventieth row contains the header information.
71	71. The seventy-first row contains the header information.
72	72. The seventy-second row contains the header information.
73	73. The seventy-third row contains the header information.
74	74. The seventy-fourth row contains the header information.
75	75. The seventy-fifth row contains the header information.
76	76. The seventy-sixth row contains the header information.
77	77. The seventy-seventh row contains the header information.
78	78. The seventy-eighth row contains the header information.
79	79. The seventy-ninth row contains the header information.
80	80. The eightieth row contains the header information.
81	81. The eighty-first row contains the header information.
82	82. The eighty-second row contains the header information.
83	83. The eighty-third row contains the header information.
84	84. The eighty-fourth row contains the header information.
85	85. The eighty-fifth row contains the header information.
86	86. The eighty-sixth row contains the header information.
87	87. The eighty-seventh row contains the header information.
88	88. The eighty-eighth row contains the header information.
89	89. The eighty-ninth row contains the header information.
90	90. The ninetieth row contains the header information.
91	91. The ninety-first row contains the header information.
92	92. The ninety-second row contains the header information.
93	93. The ninety-third row contains the header information.
94	94. The ninety-fourth row contains the header information.
95	95. The ninety-fifth row contains the header information.
96	96. The ninety-sixth row contains the header information.
97	97. The ninety-seventh row contains the header information.
98	98. The ninety-eighth row contains the header information.
99	99. The ninety-ninth row contains the header information.
100	100. The hundredth row contains the header information.

Scale

As indicated

1B-S0.02

ML 038-# 231415-01
DESIGNER: NC MARTIN
LEAD REVIT TECH COLIN WINKLES
DATE PRINTED: 7/15/2021 11:06:21 AM
PLOT PATH: S:\03\003\7835\001 - SSRC\001\SSRC.dwg
PROJECT MANAGER: C. A. CHEN

POST-INSTALLED ANCHORS/REINFORCING STEEL SPECIAL INSPECTIONS			
ITEM	FREQUENCY	STANDARD	CRITERIA
EXPANSION ANCHORS, SLEEVE ANCHORS, SCREW ANCHORS			
- PRIOR TO START OF WORK	-	ICC-ES REPORT	REVIEW CONTRACTOR'S INSTALLATION PROCEDURE
- PRIOR TO INSTALLATION OF ANCHOR	EACH ANCHOR	ICC-ES REPORT	VERIFY TYPE, DIAMETER, LENGTH, FINISH, AND BASE MATERIAL. VERIFY SOLID GROUTED AREA AROUND ANCHORS IN GROUTED MASONRY. VERIFY MAXIMUM IMPACT WRENCH TORQUE RATING FOR SCREW ANCHORS
- DURING INSTALLATION OF ANCHOR	C	ICC-ES REPORT	CONTINUOUS INSPECTION REQUIRED REGARDLESS IF PERIODIC INSPECTION IS PERMITTED BY ICC-ES REPORT. VERIFY HOLE DIMENSIONS, HOLE CLEANING, ANCHOR EMBEDMENT, EDGE DISTANCES AND SPACING
- AFTER INSTALLATION OF ATTACHED ASSEMBLY	100% VISUAL	-	VERIFY NUMBER, EDGE DISTANCES, AND ANCHOR FLUSH WITH AND PERPENDICULAR TO THE RECEIVING SURFACE
ADHESIVE ANCHORS, REINFORCING STEEL ANCHORED INTO HARDENED CONCRETE			
- PRIOR TO START OF WORK	-	ICC-ES REPORT	REVIEW CONTRACTOR'S INSTALLATION PROCEDURE
- PRIOR TO INSTALLATION OF ANCHOR	EACH ANCHOR	ICC-ES REPORT	VERIFY TYPE, DIAMETER, LENGTH, FINISH, AND BASE MATERIAL. VERIFY SOLID GROUTED AREA AROUND ANCHORS IN GROUTED MASONRY
- DURING INSTALLATION OF ANCHOR	C	ICC-ES REPORT	CONTINUOUS INSPECTION REQUIRED REGARDLESS IF PERIODIC INSPECTION IS PERMITTED BY ICC-ES REPORT. VERIFY HOLE DIMENSIONS, HOLE CLEANING, ANCHOR EMBEDMENT, EDGE DISTANCES AND SPACING
- AFTER INSTALLATION OF ATTACHED ASSEMBLY	100% VISUAL	-	VERIFY NUMBER, EDGE DISTANCES, AND ANCHOR FLUSH WITH AND PERPENDICULAR TO THE RECEIVING SURFACE
- CURE TIME	100% VISUAL	-	VERIFY FULL CURE TIME HAS ELAPSED PRIOR TO APPLICATION OF TORQUE OR LOAD TO ANCHOR

POST-INSTALLED ANCHOR/REINFORCING STEEL TESTING			
ITEM	FREQUENCY	STANDARD	CRITERIA
EXPANSION ANCHORS, SLEEVE ANCHORS, SCREW ANCHORS			
- TORQUE TEST	100%	-	TEST ANCHOR WITH CALIBRATED TORQUE WRENCH TO 100% OF THE INSTALLATION TORQUE NOTED IN ICC-ES REPORT. ATTAIN SPECIFIED TORQUE WITHIN 1/2 TURN OF THE NUT
ADHESIVE ANCHORS, REINFORCING STEEL ANCHORED INTO HARDENED CONCRETE			
- TENSION TEST	FIRST 3 AND 1% OF REMAINING	ASTM E488	TEST THE INSTALLATION OF THE FIRST 3 OF EACH TYPE, BASE MATERIAL, AND POSITION (DOWN, HORIZONTAL, OVERHEAD). OBSERVE ASTM E488 MINIMUM EDGE DISTANCES FOR DETERMINING TEST LOCATIONS. SUBMIT PROPOSED TEST LOCATIONS AND REQUESTS FOR REQUIRED TENSION TEST LOAD VALUES TO ENGINEER

STRUCTURAL CONCRETE TESTING			
ITEM	FREQUENCY	STANDARD	CRITERIA
REINFORCING STEEL, BOLTS AND EMBEDMENTS			
- WELDING	-	-	PER STRUCTURAL STEEL TESTING
CONCRETE			
- COMPOSITE SAMPLE			
1. $f_c < 5000$ PSI	100 CY/MIX/DAY	ASTM C172	OBTAIN AT POINT OF PLACEMENT. FOR DRILLED PIERS OBTAIN NEAR BEGINNING OF LOAD PRIOR TO PLACEMENT IN SHAFT. ADJUST FREQUENCY AS REQUIRED TO PROVIDE MINIMUM 5 TOTAL TESTS PER MIX BUT NOT MORE THAN ONE SAMPLE PER TRUCK LOAD
2. $f_c \geq 5000$ PSI AND SHOTCRETE	50 CY/MIX/DAY		
- SLUMP/SLUMP FLOW	EACH COMPOSITE SAMPLE	ASTM C143 (SLUMP) OR ASTM C1611 (SLUMP FLOW)	SPECIFIED SLUMP SHALL BE AS SUBMITTED IN THE MIX DESIGN $\pm 1\frac{1}{2}$ ". PERFORM ADDITIONAL TESTS WHEN CONCRETE CONSISTENCY APPEARS TO CHANGE
- AIR CONTENT WHEN AIR ENTRAINMENT IS SPECIFIED AND LIGHTWEIGHT CONCRETE	EACH COMPOSITE SAMPLE	ASTM C231 PRESSURE METHOD (NWC) OR ASTM C173 VOLUMETRIC METHOD (LWC)	-
- TEMPERATURE	EACH COMPOSITE SAMPLE AND 60 MINUTE INTERVALS	ASTM C1064	REQUIRED WHEN AIR TEMPERATURE IS 40 °F AND BELOW OR 80°F AND ABOVE
- UNIT WEIGHT FOR STRUCTURAL LIGHTWEIGHT	EACH COMPOSITE SAMPLE	ASTM C138	-
- COLD WEATHER CURING	-	ASTM C1074	RECORD MAXIMUM AND MINIMUM CONCRETE TEMPERATURE DURING CURING PERIOD, WHEN DAILY AVERAGE AIR TEMPERATURE OF 40 °F OR BELOW IS EXPECTED FOR 3 SUCCESSIVE DAYS DURING CURING PERIOD
- COMPRESSIVE STRENGTH	EACH COMPOSITE SAMPLE	ASTM C31 ASTM C39 EITHER: (4)6x12 OR (6)4x8 CYLINDERS	TEST PER SCHEDULE BELOW: - 7 DAYS: (1) 6x12 OR (1) 4x8 - 28 DAYS: (2) 6x12 OR (3) 4x8 - 56 DAYS: (1) 6x12 OR (2) 4x8 (IF 28 DAY TESTS DO NOT ACHIEVE SPECIFIED 28 DAY STRENGTH) ACCEPTANCE CRITERIA PER ACI 318
SHOTCRETE (ADDITIONAL REQUIREMENTS)			
- COMPRESSIVE	-	IBC 2018 - 1908.10	-
- CURING	-	IBC 2018 - 1908.9	-
FLOOR FLATNESS REQUIREMENTS			
- MEASURE CONCRETE FLOOR FLATNESS (FF) AND FLOOR LEVELNESS (FL)	-	ASTM E1155	PERFORM MEASUREMENTS WITHIN 48 HOURS OF FINISHING OPERATIONS AND PRIOR TO REMOVAL OF SHORES OR FORMS. MEASURE AREAS INDICATED IN THE SPECIFICATIONS

STRUCTURAL CONCRETE TESTING NOTES:

1. NONDESTRUCTIVE TESTING MAY BE PERMITTED BY THE ARCHITECT, BUT WILL NOT BE USED AS SOLE BASIS FOR APPROVAL OR REJECTION OF DEFICIENT CONCRETE.
2. REPORTS OF COMPRESSIVE STRENGTH TESTS SHALL CONTAIN THE FOLLOWING INFORMATION: DATE OF CONCRETE PLACEMENT, LOCATION OF CONCRETE BATCH IN WORK, DESIGN 28-DAY COMPRESSIVE STRENGTH, SLUMP, CONCRETE SUPPLIER AND MIXTURE ID NUMBER, TIME OF BATCH AND PLACEMENT, AMBIENT AIR TEMPERATURE, SITE ADDED WATER AND ADMIXTURES, UNIT WEIGHT, AND AS REQUIRED BY ASTM C39.

STRUCTURAL CONCRETE SPECIAL INSPECTIONS			
ITEM	FREQUENCY	STANDARD	CRITERIA
REINFORCING STEEL			
- DURING PLACEMENT	P	ACI 301-16 3.2.3.3	VERIFY GRADE, FINISH, SIZE, BAR QUANTITY, LOCATION, SPACING, COVER, HOOK LENGTHS, SPLICE LENGTH, SPLICE LOCATIONS, BEND DIAMETERS, COATING, SURFACE CONDITION, AND SUPPORT
- PRIOR TO PLACEMENT OF CONCRETE	100%		
- WELDING	C	AWS D1.4	VERIFY ASTM A706 REINFORCING STEEL
- FIELD BENDING	P	ACI 301-16 3.3.2.8	-
- COATED REINFORCING	P	ACI 301-16 3.2.1.2	-
- MECHANICAL CONNECTORS	C	ICC-ES REPORT	-
BOLTS AND EMBEDMENTS			
- PRIOR TO PLACEMENT OF CONCRETE	100%	-	VERIFY TYPE, FINISH, DIAMETER, LENGTH, QUANTITY, EMBEDMENT LENGTH, SPACING AND EDGE DISTANCES. VERIFY USE OF PLACING TEMPLATE WHERE SPECIFIED
- WELDING	-	-	INSPECT PER THE STRUCTURAL STEEL TABLE
CONCRETE			
- MIX DESIGN	EACH TRUCK	-	VERIFY USE OF APPROVED DESIGN MIXTURE FOR EACH TRUCK LOAD
- FORMWORK PRIOR TO PLACEMENT OF CONCRETE	P	ACI 301-16 2.2.2.3	INSPECT FIRST POUR OF EACH TYPE (GRADE, BEAM, COLUMN, STRUCTURAL SLAB, SLAB-ON-DECK, ETC.)
- PLACEMENT OF CONCRETE	C	ACI 301-16 5.3.2	-
- CURING	P	ACI 301-16 5.3.6	-
- SHORE/FORM REMOVAL	P	ACI 301-16 2.3.2	FOR BEAMS AND STRUCTURAL SLABS

QUALITY ASSURANCE GENERAL NOTES			
STATEMENT OF STRUCTURAL SPECIAL INSPECTIONS AND TESTING			
1. GENERAL: A. SCOPE OF WORK <ul style="list-style-type: none">• THE OWNER WILL ENGAGE A QUALIFIED INSPECTION AND TESTING AGENCY(S) TO PERFORM SPECIAL INSPECTIONS AND TESTING FOR ALL STRUCTURAL MEMBERS AND ASSEMBLIES AS NOTED HEREIN.• SPECIAL INSPECTIONS ARE IN ADDITION TO INSPECTIONS BY THE AUTHORITY HAVING JURISDICTION REQUIRED BY IBC 2018 SECTION 110.• REFER TO THE SPECIFICATIONS FOR REPORTING AND PROCEDURAL REQUIREMENTS FOR QUALITY ASSURANCE AND QUALITY CONTROL.• REFER TO ARCHITECT/ENGINEER/CIVIL SPECIFICATIONS AND DRAWINGS FOR ADDITIONAL SPECIAL INSPECTION AND TESTING THAT MAY BE REQUIRED. B. SPECIAL INSPECTIONS AND TESTING ARE APPLICABLE TO ALL REVISIONS AND/OR FUTURE WORK ADDED BY AMENDMENTS TO THESE DOCUMENTS. C. DEFINITIONS <ul style="list-style-type: none">• SPECIAL INSPECTOR: THE AGENCY ENGAGED BY THE OWNER AND APPROVED BY THE AUTHORITY HAVING JURISDICTION TO ACT AS THE DESIGNATED REPRESENTATIVE TO PERFORM INSPECTIONS.• SPECIAL INSPECTION: INSPECTION PERFORMED BY THE SPECIAL INSPECTOR ACCORDING TO IBC 2018 SECTION 1704 TO ENSURE COMPLIANCE WITH APPROVED CONSTRUCTION DOCUMENTS AND REFERENCED STANDARDS.• (P) PERIODIC INSPECTION: THE PART-TIME OR INTERMITTENT OBSERVATION BY THE SPECIAL INSPECTOR OF WORK BEING PERFORMED. SPECIAL INSPECTOR SHALL BE PRESENT IN THE AREA WHERE THE WORK IS BEING PERFORMED. OBSERVATION OF ALL WORK (100% VISUAL) SHALL BE MADE AT THE COMPLETION OF THE WORK.• (C) CONTINUOUS INSPECTION: THE FULL-TIME OBSERVATION BY THE SPECIAL INSPECTOR OF WORK BEING PERFORMED. SPECIAL INSPECTOR SHALL BE PRESENT IN THE AREA WHERE THE WORK IS BEING PERFORMED. OBSERVATION OF ALL WORK (100% VISUAL) SHALL BE MADE AT THE COMPLETION OF THE WORK. D. DEFICIENCIES IN WORK <ul style="list-style-type: none">• CORRECT DEFICIENCIES IN WORK THAT TESTS AND INSPECTIONS INDICATE DO NOT COMPLY WITH THE CONTRACT DOCUMENTS AND REFERENCED STANDARDS.• ALL COST OF ADDITIONAL TESTING AND/OR INSPECTIONS FOR CORRECTIVE WORK SHALL BE BORNE BY THE CONTRACTOR.			
2. SHOP FABRICATIONS: A. GENERAL <ul style="list-style-type: none">• PERFORM INSPECTIONS AND TESTING FOR ALL SHOP FABRICATED STRUCTURAL MEMBERS AND ASSEMBLIES AS NOTED HEREIN. SPECIAL INSPECTOR SHALL PERFORM SPECIAL INSPECTIONS AND TESTING UNLESS THE FABRICATOR IS REGISTERED AND APPROVED BY THE AUTHORITY HAVING JURISDICTION TO PERFORM SUCH WORK WITHOUT SPECIAL INSPECTION OR FABRICATION HAS A CURRENT ICC-ES EVALUATION REPORT.• SPECIAL INSPECTOR SHALL VERIFY THE FABRICATOR MAINTAINS AND FOLLOWS DETAILED SHOP FABRICATION AND QUALITY CONTROL PROCEDURES, UNLESS FABRICATOR IS REGISTERED AND APPROVED.• AT THE COMPLETION OF FABRICATION, THE APPROVED FABRICATOR SHALL SUBMIT A CERTIFICATE OF COMPLIANCE TO THE AUTHORITY HAVING JURISDICTION ACCORDING TO IBC 2018 SECTION 1704.2.5.1.• APPROVED FABRICATORS MAY PERFORM TESTING NOTED HEREIN EXCEPT THAT NONDESTRUCTIVE TESTING (NDT) SHALL ONLY BE PERFORMED BY PERSONNEL WITH QUALIFICATIONS THAT MEET OR EXCEED THE CRITERIA OF AWS D1.1 SUBCLAUSE 6.14.6 AND AMERICAN SOCIETY FOR NONDESTRUCTIVE TESTING (ASNT) SNT-TC-1A OR ASNT CP-189. B. SHOP FABRICATIONS INCLUDED <ul style="list-style-type: none">• SHOP FABRICATED STRUCTURAL STEEL INCLUDING STAIRS AND RAILING ELEMENTS• SHOP FABRICATED STEEL CONNECTIONS FOR STRUCTURAL WOOD CONNECTIONS			

SOILS SPECIAL INSPECTIONS			
ITEM	FREQUENCY	STANDARD	CRITERIA
SUBGRADE			
- EXCAVATION	P	-	VERIFY EXCAVATIONS ARE EXTENDED TO THE PROPER DEPTH AND HAVE REACHED THE PROPER BEARING MATERIAL
- BEARING MATERIAL	P	SOILS REPORT	VERIFY BEARING MATERIAL IS ADEQUATE TO ACHIEVE THE DESIGN BEARING CAPACITY
CONTROLLED FILL			
- PRIOR TO PLACEMENT	P	-	VERIFY SUBGRADE HAS BEEN PROPERLY PREPARED
- PLACEMENT	C	-	VERIFY USE OF PROPER MATERIALS, DENSITIES, COMPACTION, AND LIFT THICKNESSES

SOILS SPECIAL INSPECTION NOTES:

1. SEE CIVIL DRAWINGS AND/OR SPECIFICATIONS FOR ADDITIONAL EARTHWORK AND UTILITY INSPECTION REQUIREMENTS.
2. SEE CIVIL DRAWINGS AND/OR SPECIFICATIONS FOR CLASSIFICATION AND TESTING REQUIREMENTS FOR COMPACTED FILL AND/OR CONTROLLED LOW-STRENGTH MATERIAL.



DRILLED MICROPILE FOUNDATIONS SPECIAL INSPECTIONS			
ITEM	FREQUENCY	STANDARD	CRITERIA
VERIFICATION & PROOF TESTING			
- OBSERVE TESTING	C	-	DETERMINE CAPACITIES OF TEST ELEMENTS
DURING DRILLING			
- DRILLING OPERATIONS	C	-	PROVIDE REPORT FOR EACH MICROPILE
- SHAFT PLACEMENT	C	-	VERIFY LOCATION, PLUMBNESS, AND DIAMETER
- BEARING MATERIAL	C	PRE-CONSTRUCTION TESTING	VERIFY BEARING MATERIAL IS EQUIVALENT TO THAT USED IN PRECONSTRUCTION TESTING
- DEPTH OF PENETRATION	C	-	VERIFY DEPTH OF PENETRATION INTO BEARING MATERIAL AND OVERALL LENGTH
- CONCRETE/GROUT AND REINFORCING STEEL	-	-	PER MICROPILE SUBCONTRACTOR.

DRILLED MICROPILE FOUNDATIONS SPECIAL INSPECTION NOTES:

1. SEE DEFERRED MICROPILE SUBCONTRACTOR SPECIFICATIONS FOR REQUIREMENTS OF PRECONSTRUCTION LOAD TESTS TO BE PERFORMED BY THE SUBCONTRACTOR.

ALERRA east west partners
MOUNTAIN COMPANY

2305 Mount Werner Circle
Steamboat Springs, CO 80487

Gensler
1225 17th Street
Suite 150
Denver, CO 80202
United States
Tel 303.595.8586
Fax 303.825.6823

141 9th Street
PO Box 774943
Steamboat Springs, CO 80477
Tel 970.871.9494

DESIGNWORKSHOP
1390 Lawrence Street
Suite 100
Denver, CO 80204
Tel 303.623.5186

12499 West Colfax Ave.
Lakewood, CO 80215
United States
Tel 303.431.6100

14143 Denver West Pkwy
Suite 300
Golden, CO
United States
Tel 303.421.6655

July 15, 2021

Seal / Signature

Date	Description
- 2021.05.19	BP3: GOLDWALK - ISSUE FOR BID AND PERMIT
1 2021.07.14	BP3: GOLDWALK - BULLETIN 04


Project Name
SSRC | BASE AREA IMPROVEMENTS

Project Number
003.7835.000


Description
QUALITY ASSURANCE

Scale
12" = 1'-0"


1B-S0.10



2 PARTIAL STAIR FRAMING PLAN

$$1/8'' = 1'-0''$$


1 PLAZA PARTIAL FRAMING PLAN

$$1/8'' = 1'-0''$$


2 ESCALATOR PIT SECTION

$$1/8'' = 1'-0''$$

PLAN NOTES

1. CONTRACTOR TO VERIFY ALL EXISTING CONDITION PRIOR TO STEEL FABRICATION.
2. CONTRACTOR TO FIELD LOCATE ALL UTILITIES BELOW GRADE. CONTRACTOR SHALL NOTIFY ARCHITECT FOR DIMENSIONED DRAWING OF LOCATIONS WHERE UTILITIES CONFLICT WITH FOUNDATION INSTALLATION. CONTRACTOR SHALL MAKE ALLOWANCE FOR THE RESOLUTION OF SUCH DISCOVERIES PRIOR TO PROCEEDING WITH EFFECTED FOUNDATIONS.
3. SEE ARCH AND MECH DRAWINGS FOR SLAB SLOPES, DEPRESSIONS, FILL, PADS, AND CURBS NOT SHOWN ON THE STRUCTURAL DRAWINGS.
4. SEE 1B-S4.00 FOR TYPICAL MASONRY WALL DETAILS. SEE ARTICUTAL DRAWINGS FOR DIMENSIONS OF ALL MASONRY WALLS.



ALTERRA east west partners
MOUNTAIN COMPANY

2305 Mount Werner Circle
Steamboat Springs, CO 80487

Gensler

1225 17th Street
Suite 150
Denver, CO 80202
United States

Tel 303.595.8585
Fax 303.825.6823



141 9th Street
PO Box 774943
Steamboat Springs, CO
80477
Tel 970.871.9494

DESIGNWORKSHOP

1390 Lawrence Street
Suite 100
Denver, CO 80204
Tel. 303.623.5186



12499 West Colfax Ave
Lakewood, CO 80215
United States
Tel 303.431.6100

me
engineers

14143 Denver West Pkwy
Suite 300
Golden, CO
United States
Tel 303.421.6655



July 15, 2021


Seal / Signature

	Date	Description
-	2021.05.19	BP3: GOLDWALK - ISSUE FOR BID AND PERMIT
1	2021.06.25	BP3: GOLDWALK - BULLETIN 02
2	2021.07.14	BP3: GOLDWALK - BULLETIN 04

LEGEND

OUT OF SCOPE

KEY PLAN



Project Name

SSRC | BASE AREA
IMPROVEMENTS

Project Number

003.7835.000


Description
GOLDWALK - LEVEL 1 FRAMING PLAN

Scale



As indicated

Ref North


1B-S1.01




17 3/4" = 1'-0" STAIR EDGE WALL




19 3/4" = 1'-0" CANOPY PILASTER




20 3/4" = 1'-0" CIP STAIR TO SITE SLAB




9 3/4" = 1'-0" ESCALATOR PIT WALL




10 3/4" = 1'-0" ESCALATOR FOUNDATION WALL




11 3/4" = 1'-0" ESCALATOR PIT WALL TO STAIR




12 3/4" = 1'-0" SOG BELOW MASONRY PARTITION WALL




6 3/4" = 1'-0" INTERIOR COLUMN AT SPREAD FOOTING




2 NO SCALE TYP EXCAVATION AT FTG




3 NO SCALE TYP SPREAD FOOTING





4 NO SCALE ESCALATOR PIT




- NOTES:**
1. ALL AROUND WELD MAY BE USED IN LIEU OF THE WELD SHOWN
 2. PROVIDE 3" CLEAR COVER AT FOOTING LOCATIONS
 3. 2"Ø MAXIMUM GROUT HOLE AT CONTRACTOR'S OPTION. ONE OR TWO GROUT HOLES RECOMMENDED FOR BASE PLATES LARGER THAN 24" IN WIDTH.




1 1/4" = 1'-0" TYP FTG ADJACENT TO WALL




8 NO SCALE TYP STRIP FOOTING




1 1/4" = 1'-0" TYP FTG ADJACENT TO WALL



2 NO SCALE TYP EXCAVATION AT FTG



3 NO SCALE TYP SPREAD FOOTING



4 NO SCALE ESCALATOR PIT

ALTRRA east west partners
MOUNTAIN COMPANY

2305 Mount Werner Circle
Steamboat Springs, CO 80487

1225 17th Street
Suite 150
Denver, CO 80202
United States

Tel 303.595.8866
Fax 303.825.6823

Gensler

1225 17th Street
Suite 150
Denver, CO 80202
United States

141 9th Street
PO Box 774943
Steamboat Springs, CO 80477
Tel 970.871.9494

1390 Lawrence Street
Suite 100
Denver, CO 80204
Tel 303.623.5186

14143 Denver West Pkwy
Suite 300
Golden, CO
United States
Tel 303.421.6655

LANDMARK
CONSTRUCTION, INC.

141 9th Street
PO Box 774943
Steamboat Springs, CO 80477
Tel 970.871.9494

DESIGNWORKSHOP

1390 Lawrence Street
Suite 100
Denver, CO 80204
Tel 303.623.5186

me
engineers

12499 West Colfax Ave.
Lakewood, CO 80215
United States
Tel 303.431.6100

14143 Denver West Pkwy
Suite 300
Golden, CO
United States
Tel 303.421.6655

Seal / Signature

Date Description

- 2021.05.19 BP3: GOLDWALK - ISSUE FOR BID AND PERMIT
- 2021.06.25 BP3: GOLDWALK - BULLETIN 02
- 2021.07.14 BP3: GOLDWALK - BULLETIN 04

Project Name
SSRC | BASE AREA IMPROVEMENTS

Project Number
003.7835.000

Description
FOUNDATION DETAILS


Scale
As indicated


1B-S3.01

© 2021 Gensler © 2021 Martin/Martin

DESIGNER: NC MARTIN
LEAD REVIT: TECH COLIN MONROE
DATE PRINTED: 7/15/2021 11:05:31 AM
FILE PATH: E:\003\003\1B-S3.01 - Steamboat\Revit\03_7835_000_Steamboat_SRR_GSD_2021_1202114

MIL JOB #: 2314115.01
PRINCIPAL: KELLY KNOWLES
FOR KELL: KELLY KNOWLES
PROJECT MANAGER: C. A. CHEN





ALTRERA east west partners

2305 Mount Werner Circle
Steamboat Springs, CO 80487

Gensler

1225 17th Street
Suite 150
Denver, CO 80202
United States

Tel 303.595.8586
Fax 303.825.6823

LANDMARK

141 9th Street
PO Box 774943
Steamboat Springs, CO 80477
Tel 970.871.9494

DESIGNWORKSHOP

1390 Lawrence Street
Suite 100
Denver, CO 80204
Tel 303.623.5186

me

14143 Denver West Pkwy
Suite 300
Golden, CO
United States
Tel 303.421.6655

MARTIN/MARTIN

12499 West Colfax Ave.
Lakewood, CO 80215
United States
Tel 303.431.6100

14143 Denver West Pkwy
Suite 300
Golden, CO
United States
Tel 303.421.6655

Seal / Signature

Date

Description

- 2021.05.19 BP3: GOLDWALK - ISSUE FOR BID AND PERMIT

1 2021.06.25 BP3: GOLDWALK - BULLETIN 02

2 2021.07.14 BP3: GOLDWALK - BULLETIN 04

Project Name

SSRC | BASE AREA IMPROVEMENTS

Project Number

003.7835.000

Description

CONCRETE DETAILS

Scale

As indicated

1B-S3.02

© 2021 Gensler © 2021 Martin/Martin