

RCRBD Note:  
Plumbing Plan  
Approved for  
demolition work  
under P-21-282

Date	Description
2021.05.19	BP3: GOLDWALK - ISSUE FOR BID AND PERMIT

Seal / Signature



05/18/2021

Project Name

SSRC | BASE AREA  
IMPROVEMENTS

Project Number

003.7835.000

Description

GOLD WALK - PLUMBING PLAN -  
LEVEL 01

Scale

1/8" = 1'-0"

1B-P1.201

GENERAL NOTES:

1. FIELD VERIFY THE EXACT LOCATION OF ALL EXISTING PIPING, FIXTURES, AND EQUIPMENT SCHEDULED TO BE DEMOLISHED PRIOR TO COMMENSING WORK.
2. FIELD VERIFY THE EXACT LOCATION OF ALL EXISTING PIPING THAT REQUIRES CONNECTION TO NEW PRIOR TO COMMENSING WORK.
3. REQUIRED PIPE SIZES ARE SHOWN NEXT TO KEY NOTE.
4. PROVIDE BALL VALVE SHUTOFF AND 12"X12" ACCESS PANEL AT EACH SHOCK ABSORBER (SA). PANEL LOCATION TO BE VERIFIED AND COORDINATED WITH ARCHITECT.
5. ALL CIRCUIT SETTERS SHALL BE SET AT 1.0 GPM UNLESS NOTED OTHERWISE.

KEY NOTES:  
(SOME KEY NOTES MAY  
NOT APPLY TO THIS SHEET)

- 1 SANITARY PIPING UP
- 2 SANITARY PIPING DN
- 3 SANITARY PIPING UP & DN
- 4 GW PIPING UP
- 5 GW PIPING DN
- 6 GW PIPING UP & DN
- 7 SANITARY VENT UP
- 8 SANITARY VENT DN
- 9 SANITARY VENT UP & DN
- 10 CW PIPING UP
- 11 CW PIPING DN
- 12 CW PIPING UP & DN
- 13 HW PIPING UP
- 14 HW PIPING DN
- 15 HW PIPING UP & DN
- 16 HWC PIPING UP
- 17 HWC PIPING DN
- 18 HWC PIPING UP & DN
- 19 CW & HW PIPING UP
- 20 CW & HW PIPING DN
- 21 CW & HW PIPING UP & DN
- 22 GAS PIPING UP
- 23 GAS PIPING DN
- 24 GAS PIPING UP & DN
- 25 STORM PIPING UP
- 26 STORM PIPING DN
- 27 STORM PIPING UP & DN
- 28 OVERFLOW PIPING UP
- 29 OVERFLOW PIPING DN
- 30 OVERFLOW PIPING UP & DN
- 31 OVERFLOW PIPING DOWN AND THRU WALL TO DOWNSPOUT NOZZLE +12" AFG
- 32 SANITARY PIPING UP TO PLUMBING FIXTURES
- 33 PIPING UP TO CLEANOUT
- 34 1/2" CW & HW TO EACH LAV/SK
- 35 PIPING UP TO DRAIN
- 36 1/2" CW & HW DOWN TO SHOWER VALVE & 1/2" UP TO SHOWERHEAD

KEY PLAN

