



# EDDYLINE TOWNHOMES

## DEVELOPMENT PLAN OF FUTURE EXPANSION PARCEL RIVERFRONT PARK FILINGS NO. 2, LOCATED IN THE NW ¼ OF SECTION 7, TOWNSHIP 6 NORTH, RANGE 84 WEST OF THE 6TH P.M., STEAMBOAT SPRINGS, ROUTT COUNTY, COLORADO

LEGEND	
	EXISTING PROPERTY BOUNDARY
	PROPOSED PROPERTY BOUNDARY
	ADJACENT PROPERTY BOUNDARY
	EXISTING EASEMENT
	EXISTING OPEN SPACE
	EXISTING EDGE OF CONCRETE
	EXISTING 2' CONTOUR
	EXISTING 10' CONTOUR
	PROPOSED 2' CONTOUR
	PROPOSED 10' CONTOUR
	EXISTING DRAINAGE DITCH
	PROPOSED DRAINAGE DITCH
	EXISTING STORM SEWER
	PROPOSED STORM SEWER
	EXISTING GAS LINE
	PROPOSED GAS LINE
	EXISTING SEWER MAIN
	PROPOSED SEWER SERVICE
	EXISTING WATER MAIN
	PROPOSED WATER SERVICE
	EXISTING FIRE HYDRANT
	EXISTING HEATED CONCRETE PAVING
	PROPOSED CONCRETE PAVING
	PROPOSED STORM WATER QUALITY POND
	FLOW ARROW
	PROPOSED PARKING STRIPING
	EXISTING BUILDING FOOTPRINT
	PROPOSED BUILDING FOOTPRINT
	PROPOSED BUILDING OVERHANG
	PROPOSED FENCING
	SNOW STORAGE
	EXISTING LABEL
	PROPOSED LABEL



**GENERAL NOTES:**

- OWNER: KRUSE BUILDERS, LLC
- STREET ADDRESS: 1940 AND 1960 BRIDGE LANE, STEAMBOAT SPRINGS, CO 80487
- BENCHMARK = FOUND ORANGE PLASTIC AT SOUTH WEST PROPERTY CORNER ON #4 REBAR DOWLING - 30090, ELEVATION=7554.72 (SEE EXISTING CONDITIONS PLAN).
- PROPERTY CORNERS WERE FOUND AS INDICATED HEREON PER FIELD SURVEY.
- DIMENSIONS ARE IN FEET UNLESS OTHERWISE NOTED.
- TOPOGRAPHIC AND EXISTING CONDITIONS MAPPED BY FOUR POINTS SURVEYING & ENGINEERING COMPLETED ON NOVEMBER 11, 2024.
- ONE COPY OF THE APPROVED CONSTRUCTION PLANS AND SPECIFICATIONS SHALL BE KEPT ON THE JOB SITE AT ALL TIMES. PRIOR TO THE START OF CONSTRUCTION, CONTRACTOR TO VERIFY WITH PROJECT ENGINEER THE LATEST REVISION DATE OF THE APPROVED CONSTRUCTION PLANS.
- CONTRACTOR SHALL VERIFY THE LOCATION OF ALL UTILITIES. CALL THE UTILITY NOTIFICATION CENTER OF COLORADO (UNCC) AT 1-800-922-1987 AND ANY NECESSARY PRIVATE UTILITY TO PERFORM LOCATES PRIOR TO CONDUCTING ANY SITE WORK.
- ALL WATER AND SANITARY SEWER CONSTRUCTION AND RELATED WORK SHALL CONFORM TO THE CITY OF STEAMBOAT SPRINGS STANDARDS AND SPECIFICATIONS, LATEST EDITION.
- CONTRACTOR SHALL OBTAIN ALL NECESSARY PERMITS AND APPROVALS REQUIRED TO PERFORM THE WORK SUCH AS RIGHT-OF-WAY PERMIT, GRADING AND EXCAVATION PERMIT, CONSTRUCTION DEWATERING PERMIT, STORM WATER QUALITY PERMIT, ARMY CORP OF ENGINEER PERMIT, ETC. IT IS THE CONTRACTOR'S RESPONSIBILITY TO OBTAIN A COPY OF ALL APPLICABLE CODES, LICENSES, SPECIFICATIONS, AND STANDARDS NECESSARY TO PERFORM THE WORK, AND BE FAMILIAR WITH THEIR CONTENTS PRIOR TO COMMENCING ANY WORK.
- PRIOR TO START OF CONSTRUCTION CONTRACTOR SHALL COORDINATE WITH PROJECT ENGINEER TO IDENTIFY PROJECT INSPECTION AND TESTING REQUIREMENTS. CONTRACTOR SHALL PROVIDE FOR INSPECTIONS AND TESTING AT AN ADEQUATE FREQUENCY FOR THE PROJECT ENGINEER TO DOCUMENT THAT PROJECT IS CONSTRUCTED IN CONFORMANCE WITH THE APPROVED PLANS AND SPECIFICATIONS.
- CONTRACTOR IS RESPONSIBLE FOR ALL NECESSARY TRAFFIC CONTROL. TRAFFIC CONTROL SHALL BE IN ACCORDANCE WITH THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (MUTCD), LATEST EDITION.
- CONTRACTOR SHALL PROVIDE ALL NECESSARY TRAFFIC CONTROL (SIGNS, BARRICADES, FLAGMEN, LIGHTS, ETC) IN ACCORDANCE WITH THE MUTCD, CURRENT EDITION.
- CONTRACTOR MUST SUBMIT A CONSTRUCTION SITE MANAGEMENT PLAN (CSMP) FOR REVIEW AND APPROVAL BY THE CITY CONSTRUCTION SERVICES FOREMAN PRIOR TO START OF CONSTRUCTION. THE CSMP MUST BE MAINTAINED ON-SITE AND UPDATED AS NEEDED TO REFLECT CURRENT CONDITIONS.
- THE FOLLOWING PRIVATE IMPROVEMENTS REQUIRE CONSTRUCTION OBSERVATION PER THE CITY'S ENGINEERING SERVICES SPECIFICATION: WATER, SEWER, STORM SEWER, PONDS.
- RECORD DRAWINGS ARE REQUIRED FOR: PUBLIC AND PRIVATE WATER AND SEWER
- DRIVEWAY CURB CUTS TO BE INSTALLED DURING PUBLIC IMPROVEMENTS, DRIVEWAYS AND LANDSCAPING FOR INDIVIDUAL UNITS TO BE INSTALLED PRIOR TO BUILDING CERTIFICATE OF OCCUPANCY.
- ALL PIPE OUTFALLS REQUIRE FLARED END SECTIONS AND RIPRAP. ALL VALLEY PAN OUTFALLS REQUIRE RIPRAP.

**GRADING:**

- GRADING SHALL OCCUR WITHIN THE PROPERTY LIMITS. WHERE OFF-SITE WORK IS APPROVED, WRITTEN PERMISSION OF THE ADJACENT PROPERTY OWNER MUST BE OBTAINED PRIOR TO ANY OFF-SITE GRADING OR CONSTRUCTION.
- NO WORK SHALL OCCUR IN WETLANDS OR FLOODPLAINS WITHOUT APPROPRIATE PERMITS. ANY WORK SHALL BE IN ACCORDANCE WITH THE ISSUED PERMITS.
- VEGETATED SLOPES GREATER THAN 2:1 REQUIRE SOIL STABILIZATION.

**EROSION CONTROL:**

- CONTRACTOR SHALL SUBMIT A CONSTRUCTION SITE MANAGEMENT PLAN TO THE CITY FOR APPROVAL PRIOR TO BUILDING PERMIT ISSUANCE.
- CONTRACTOR SHALL WORK IN A MANNER THAT MINIMIZES THE POTENTIAL FOR EROSION.
- CONTRACTOR SHALL BE RESPONSIBLE FOR INSTALLING, INSPECTING, AND MAINTAINING ALL NECESSARY EROSION AND SEDIMENT CONTROL DURING CONSTRUCTION AND REMOVING EROSION CONTROL WHEN PROJECT IS COMPLETE AND VEGETATION IS ESTABLISHED.
- ANY AREA DISTURBED BY CONSTRUCTION AND NOT PAVED OR NATURAL ROCK SURFACE SHALL BE REVEGETATED WITHIN ONE CONSTRUCTION SEASON.

**ABBREVIATIONS:**

BOW	BOTTOM OF WALL
BLDG	BUILDING
CL	CENTERLINE
CMU	CONCRETE MASONRY UNITS
CO	CLEAN OUT
CONC	CONCRETE
ELEV	ELEVATION
EOC	EDGE OF CONCRETE
EOG	EDGE OF GRAVEL
EX	EXISTING
FES	FLARED END SECTION
FFE	FINISHED FLOOR ELEVATION
FND	FOUNDATION
HP	HIGH POINT
INV	INVERT
LF	LINEAR FEET
PR	PROPOSED
SCH	SCHEDULE
SF	SQUARE FEET
SS	SNOW STORAGE
SWR	SEWER
TOW	TOP OF WALL
WTR	WATER

**PROJECT CONTACT LIST**

**PROJECT OWNER & ARCHITECT**

KRUSE BUILDERS, LLC  
996 Captain Jack Drive  
Steamboat Springs, CO 80487

PHONE: 229-798-2145  
EMAIL: accounts@krusebuilders.com

**CIVIL ENGINEER**

FOUR POINTS SURVEYING AND ENGINEERING  
ATTN: WALTER MAGILL, P.E.  
410 S. Lincoln Ave, #15  
Steamboat Springs, CO 80487

OFFICE: (970) 871-6772  
CELL: (970) 819-1161  
EMAIL: walterm@fourpointsse.com

**SHEET INDEX:**

C1	COVER PAGE
C2	EXISTING CONDITIONS PLAN
C3	SITE PLAN
C4	GRADING AND DRAINAGE PLAN
C5	ACCESS PROFILE
C6	UTILITY PLAN
C7	SNOW STORAGE PLAN
C8	LIGHTING PLAN
C9	PHASING PLAN
C10	CONSTRUCTION SITE MANAGEMENT PLAN
C11	PROPOSED REPLAT AND EASEMENT EXHIBIT

(Cover): Remove from all plan sheets and documents. Qualifying descriptor may be present on applicable plan sheets, but must instead state exactly "For Approval, Not for Construction".

**FOR APPROVAL - NOT FOR CONSTRUCTION**



DRAWINGS PREPARED BY FOUR POINTS SURVEYING & ENGINEERING	No.	DATE	REVISIONS	INT
DATE: 8-25-2025	1	10/22/25	PER DRT COMMENTS	CFB
JOB #: 2349-003	2	12/2/25	PER DRT COMMENTS	CFB
DRAWN BY: CFB				
DESIGN BY: CFB				
REVIEW BY: WNM				
IF THIS DRAWING IS PRESENTED IN A FORMAT OTHER THAN 24" X 36", THE GRAPHIC SCALE SHOULD BE UTILIZED.				



**Four Points Surveying & Engineering**  
410 S. Lincoln Ave, Unit 15  
P.O. Box 775966  
Steamboat Springs, CO 80487  
(970)-871-6772  
walterm@fourpointsse.com

SHEET #

**C1**